

## REPORT

---

### Government of Northwest Territories Department of Infrastructure

#### Hay River Harbour Restoration – Spill Contingency Plan 2023-8356



MARCH 2023

#### **CONFIDENTIALITY AND © COPYRIGHT FOR THIS REPORT**

This document is for the sole use of the addressee and Associated Environmental Consultants Inc. The document contains proprietary and confidential information that shall not be reproduced in any manner or disclosed to or discussed with any other parties without the express written permission of Associated Environmental Consultants Inc. Information in this document is to be considered the intellectual property of Associated Environmental Consultants Inc. in accordance with Canadian copyright law.

This report was prepared by Associated Environmental Consultants Inc. for the account of Government of Northwest Territories Department of Infrastructure. The material in it reflects Associated Environmental Consultants Inc.'s best judgement, in the light of the information available to it, at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Associated Environmental Consultants Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

## REVISIONS PAGE

# Hay River Harbour Restoration – Spill Contingency Plan

Client:

Consultant:

Government of Northwest Territories  
Department of Infrastructure

Associated Environmental Consultants Inc.

[illegible]

## TABLE OF CONTENTS

SECTION	PAGE NO.
Table of Contents	i
List of Tables	iii
List of Figures	iv
List of Abbreviations	v
1 Introduction	1
1.1 Corporate Contact Information	1
1.2 Effective Date of Plan	1
1.3 Distribution List	1
1.4 Purpose and Scope of Plan	1
1.5 Health Safety and Environmental Policy	1
1.6 Project Description	3
1.7 Potentially Impacted Communities and Environments	3
1.8 Site Description	5
1.9 Type, Amount, and Location of Main Hazardous Materials	5
2 Response Organization	5
3 Spill Prevention	8
4 Spill Response Action Plan	9
4.1 Procedure for Initial Actions	9
4.2 Procedure for Reporting a Spill	11
4.3 Procedure for Containing and Controlling a Spill	11
4.4 Containing a Spill on Land	12
4.5 Containing a Spill on Water	12
4.6 Worst-Case Scenario	12
4.7 Procedure for Transferring, Storing, and Managing Spill-Related Wastes	13
4.8 Procedure for Restoring Affected Areas, Providing Regulatory Inspectors with Status Updates, and Cleanup Completion	13
5 Training and Exercises	13
6 Media and Public Enquiries	14
Closure	
References	
Appendix A – Safety Data Sheets for Spillable Materials	A-1
Appendix B – Marine Transportation Services Oil Spill Response Plan	B-1
Appendix C – Reportable Spill Quantities	C-1

Appendix D – NT-NU Spill Report Form

D-1

## LIST OF TABLES

	PAGE NO.
Table 1-1 Hazardous Material Storage	5
Table 2-1 Contractor Emergency Contacts	6
Table 2-2 Contact Information for Emergency Services	6
Table 2-3 Contact Information for Northwest Territory Regulatory Agencies	6
Table 2-4 GNWT-MTS Syncro Yard Spill Control Equipment	7
Table 2-5 Sea Barge Spill Control Equipment	7
Table 2-6 Spill Control Equipment at Temporary Soil Storage Locations	7

## LIST OF FIGURES

	PAGE NO.
Figure 1-1 Proposed Dredging Locations	2
Figure 1-2 Potential Spill Impact Locations	4
Figure 4-1 Spill Response Flow Chart	10

## LIST OF ABBREVIATIONS

Abbreviation	Definition
GNWT	Government of Northwest Territories
INF	Department of Infrastructure
MTS	Marine Transportation Services
OSC	on-scene commander
PPE	personal protective equipment
SCP	spill contingency plan
SDS	safety data sheet
TDG	Transportation of Dangerous Goods
WHMIS	Workplace Hazardous Materials Information System



# 1 INTRODUCTION

The Government of Northwest Territories (GNWT) – Department of Infrastructure (INF) retained Associated Environmental Consultants Inc. (Associated) to prepare a spill contingency plan (SCP) for dredging works taking place in the Hay River, near its outlet into Great Slave Lake (Dredge Area A, Figure 1-1), and within the three fingers in the East Channel of the river (Dredge Area B, Figure 1-1). The dredging is proposed to begin July 16, 2023, and continue until September 14, 2023. The SCP follows the Indian and Northern Affairs Canada's Guidelines for Spill Contingency Planning (2007). The SCP will guide the response to spills related to the dredging activities and will be implemented for the duration of the dredging project.

## 1.1 Corporate Contact Information

The GNWT-INF is the primary contact for this project and will be working closely with GNWT – Marine Transportation Services (MTS).

Applicant's Name:	Mark Cronk		
Position:	Director of Design and Technical Services		
Company Name:	Government of Northwest Territories – Department of Infrastructure		
Mailing Address:	4th floor, Tatsaot'ine Building PO Box 1320 5015 – 49th Street		
Community:	Yellowknife	Telephone:	867-767-9048 ext. 32060
Prov/Terr:	NT	Email:	<a href="mailto:Mark.Cronk@gov.nt.ca">Mark.Cronk@gov.nt.ca</a>
Postal Code:	X1A 2L9	Other:	

## 1.2 Effective Date of Plan

The SCP will be in effect when equipment is mobilized for the dredging activities. The specific effective date will be updated by the contractor after project award.

## 1.3 Distribution List


Manager, Environmental Affairs, Design and Technical Services, INF  
Director, Design and Technical Services, INF  
Contractor Project Manager  
Contractor Site Supervisor/Foreman  
Mackenzie Valley Land and Water Board Regulatory Specialist

## 1.4 Purpose and Scope of Plan

The purpose of the SCP is to have contingency planning in place for any potential spills caused during the dredging of the Hay River and the transportation and storage of sediment. The plan addresses the aspects of machinery working on water and on land, and the contingency if a spill occurs while fuelling, dredging, or transferring of sediment on land.

## 1.5 Health Safety and Environmental Policy

The health safety and environmental policy is the responsibility of the contractor.



C:\Users\CHENG\OneDrive - ASSOCIATED ENGINEERING GROUP LTD\Desktop\GIS\2023-8356\2023-8356-APR03-8356-APR03

SERVICE LAYER CREDITS: WORLD IMAGERY; MAXAR



LEGEND

- ▭ Dredging Areas
- ▭ Temporary Soil Storage (GNWT)
- ▭ Temporary Soil Storage (Town of Hay River)

AE PROJECT NO. 2023-8356  
SCALE 1:36,000  
COORD. SYSTEM NAD 1983 UTM ZONE 11N  
DATE 2023-03-28  
REV 03  
DRAWN BY SC  
CHECKED BY JB

FIGURE 1-1  
DREDGING AND PROJECT AREA

GOVERNMENT OF  
NORTHWEST TERRITORIES-  
DEPARTMENT OF INFRASTRUCTURE  
  
HAY RIVER HARBOUR  
RESTORATION

## 1.6 Project Description

In 2022, the Hay River experienced unusually high-water levels, resulting in increased sediment being deposited in the Hay River Harbour and Great Slave Lake at the river outfall. The sediment, which has not been regularly maintained since 1997, has begun to fill the Dredge Areas. This has caused an emergency scenario, since the shallow water in the navigation channel poses a risk to boats (i.e., sea barge, Coast Guard, fishing, and recreational vessels) getting stuck in the sediment deposit and not being able to enter or exit the Hay River Harbour. Removing sediment so that boats can travel along the navigation channel. If boats cannot enter or exit the harbour, the supply for essential goods, and fuel for power and heat could be interrupted for up to 12 communities who rely on the sea barge system.

The GNWT-INF has proposed dredging the navigation channel to mechanically excavate a 30 m wide and 2.4 m deep navigation channel for emergency use, to be completed by local contractors in coordination with GNWT-MTS. The excavated sediment from the navigation channel would be loaded onto a barge, allowed to passively dewater, and when the barge is at capacity, the sediment would be offloaded to haul trucks located on shore. The haul trucks would transfer the sediment to GNWT-INF property on Vale Island, using a sealed truck bed to mitigate further dewatering on roads. The sediment would be temporarily stored on Vale Island, contained with 1 m berms, for ongoing passive dewatering. Once moved from the barge to land, the sediment<sup>1</sup> will be considered soil (CCME 1999) and may be made available for public use, if appropriate, or would be transferred to a final management area.

This emergency dredging program will include removal and temporary storage of the following estimated volumes of sediment:

- Dredge Area A: the shipping lanes approaching the outfall to Great Slave Lake to a width of 30 m, dredging 16,000 m<sup>3</sup>; and
- Dredge Area B: the three fingers in the East Channel, dredging 68,000 m<sup>3</sup>.

## 1.7 Potentially Impacted Communities and Environments


The Hay River and Great Slave Lake are most at risk of impacts from spills, along with the local communities who depend on the lake for food, economic, and recreational purposes. On shore, the three fingers in the East Channel and the Hay River Territorial Park would be at risk from spills that may occur in the three fingers or at the outfall. If a spill were large and not contained, Sandy Creek Beach and other neighbouring lakeshore could be impacted. Figure 1-2 shows the potential spill impacted locations.

Spills that may occur at any of the temporary soil storage sites on Vale Island would likely be small enough that they would impact only the immediate area. The Hay River Harbour Restoration – Sediment and Erosion Control Plan (Associated 2023a) indicates that the soil stockpiles will be a minimum of 30 m from any watercourse and will have berms, drainage channels, and sumps established. Topsoil will also be removed and stored separately. As such, any smaller spills should remain contained to the temporary storage sites. Depending on its location, a large spill could contaminate the groundwater and permafrost (if present) and have impacts downstream (on the Hay River or Great Slave Lake).





---

<sup>1</sup> Sediment is unconsolidated material deposited on the bed of a waterbody or in a low spot or depression on land where the water velocity is insufficient to move the material (CCME 1999).





### LEGEND

-  Potential Spill Impacted Shoreline
-  Dredging Areas
-  Temporary Soil Storage (GNWT)
-  Temporary Soil Storage (Town of Hay River)

AE PROJECT NO.	2023-8356
SCALE	1:36,000
COORD. SYSTEM	NAD 1983 UTM ZONE 11N
DATE	2023-03-28
REV	03
DRAWN BY	SC
CHECKED BY	JB

**FIGURE 1-2**  
**FUELING, POTENTIAL SPILL,**  
**POTENTIAL IMPACT LOCATIONS**

GOVERNMENT OF  
NORTHWEST TERRITORIES-  
DEPARTMENT OF INFRASTRUCTURE

HAY RIVER HARBOUR  
RESTORATION

### 1.8 Site Description

There are three areas of operations that could result in a spill. The first is the GNWT-MTS Syncro Yard, where fuel is transferred to vehicles and equipment. The second is the on-water dredging sites, including the 500 m by 30 m dredge site on the outfall of the Hay River and the three fingers in the East Channel. The third site is the temporary soil storage sites on Vale Island.

### 1.9 Type, Amount, and Location of Main Hazardous Materials

The primary hazardous materials used will be diesel and gasoline for powering excavators, tugboats, and vehicles. Fuel will be sourced from the GNWT-MTS Syncro Yard; increased or new fuel storage is not intended as part of the dredging activities. The activity with the greatest likelihood of a spill is refuelling, which will occur at the GNWT-MTS Syncro Yard. While fuelling at this location, workers will follow the Marine Transportation Services Oil Spill Response Plan (Appendix B).

The hydraulic fluid and lubricants for the excavators are also at risk of being spilled via leaks. Table 1-1 lists the hazardous materials, storage volumes, storage methods, and locations. Safety data sheets (SDSs) for these materials are in Appendix A. Table 1-1 and the SDSs for biodegradable hydraulic fluids and lubricants in Appendix A will be updated by the contractor after project award.

Table 1-1 Hazardous Material Storage

Hazardous Material	Volume	Storage Method	Location
Biodegradable hydraulic fluid	To be determined by contractor	Tote tanks within hydraulic fluid container that has integrated secondary containment, or other authorized containers as determined by the contractor	To be determined by contractor
Biodegradable lubricant	To be determined by contractor	Tote tanks within lubricant container that has integrated secondary containment, or other authorized containers as determined by the contractor	To be determined by contractor

Spills are also possible during routine maintenance of the barge and excavator or if an accident occurs and a tank is spilled, or equipment is damaged and is leaking.

Leaks could also occur on the trucks and excavators responsible for hauling and depositing soil.

## 2 RESPONSE ORGANIZATION

If a spill is identified, the contractor project manager will be contacted immediately. The contractor is responsible for adhering to the SCP throughout the project. Communication between construction management, environmental

monitors, and site supervisors in the field will occur via cell phone and radio. Table 2-1 lists the contractor emergency contact list and Table 2-2 lists emergency services contact information. Table 2-3 contains the contact information for Northwest Territories regulatory agencies. Tables 2-1 to 2-3 will be updated by the contractor after project award.

**Table 2-1 Contractor Emergency Contacts**

Contact	Name	Office Phone Number	Cell Phone Number
Primary contact			
Secondary contact			

**Table 2-2 Contact Information for Emergency Services**

Emergency Services	Contact Number
NWT 24-hour spill report line	867-920-8130
Hay River Regional Health Centre	867-874-8000
Emergency (police, fire, medical)	9-1-1
Environment and Natural Resources wildlife emergencies (Hay River area office)	867-875-7640
Environmental Health Office (Yellowknife), GNWT	867-669-8979

**Table 2-3 Contact Information for Northwest Territory Regulatory Agencies**

Regulatory Agency	Contact
Workers' Safety and Compensation Commission 24-hour incident reporting line	1-800-661-0792
Department of Lands, GNWT: Norman McCowan (manager of resource management)	867-874-6995 ext. 24
Department of Environment and Natural Resources, GNWT	867-875-5550
Department of Infrastructure, GNWT	867-875-8032
Environment Climate Change Canada (Yellowknife)	867-669-4725
Mackenzie Valley Land and Water Board	867-669-0506
Fisheries and Oceans Canada	1-866-290-3731 or 867-669-4790
Marine Transportation Services Shipyard	844-574-2023

Spill equipment that can be found at the GNWT-MTS Syncro Yard is listed in Table 2-4. Equipment that should be available on the barge and at the temporary storage sites is listed in Tables 2-5 and 2-6. The number of pieces of equipment currently displayed as ## will be updated by the contractor.

**Table 2-4 GNWT-MTS Syncro Yard Spill Control Equipment**

Equipment in Container #20262
Four sections – 50' Bennett river boom
One boom connector sling
Two 50' hand lines
Two 12" Maker buoys
One 5' x 4" camlock Manta Ray skimmer head
One 4" x 25' suction hose
One 4" x 50' PVC hose
40 loose – 8" x 10' sorbent booms
Four bags – 8" x 10' x 4' sorbent booms
One bag – 3/8" x 38" x 144' sorbent roll
One bag – 18" x 18" Matasorb sorbent pads

**Table 2-5 Sea Barge Spill Control Equipment**

Equipment
ABC fire extinguisher
Sorbent booms
Drip trays
## loose – 8" x 10' sorbent booms
## bag – 8" x 10' x 4' sorbent booms
## bag – 3/8" x 38" x 144' sorbent roll
## bag – 18" x 18" Matasorb sorbent pads

**Table 2-6 Spill Control Equipment at Temporary Soil Storage Locations**

Equipment
Drip trays
ABC fire extinguisher



Equipment
## loose – 8" x 10' sorbent booms
## bag – 8" x 10' x 4' sorbent booms
## bag – 3/8" x 38" x 144' sorbent roll
## bag – 18" x 18" Matasorb sorbent pads

### 3 SPILL PREVENTION

Each vehicle, barge, and excavator will carry the required emergency spill kits to prevent fuel or hydraulic fluid from entering waterbodies. Immediately before project start-up, the environmental monitor and operators will inspect all machines, including the excavator, trucks used to transport dredged material, boats, and barges, for any possible fuel, lubricant, or hydraulic fluid leaks and excessive grease. Small boats and trucks will be inspected on land, above the high-water mark. Vegetable-based biodegradable hydraulic fluids will be used by the excavator as a precautionary measure in the event of a hydraulic fluid leak.

Refuelling of vehicles will be conducted more than 30 m from the nearest waterbody. Refuelling of sea barges and the excavator situated on a barge will be conducted carefully, with drip pans underneath and the spill kit containing absorbency pads at readiness.

The environmental monitor and machine operators will inspect all equipment, including any heavy equipment and boats, daily for leaks and proper operation. Any signs of leaks or excessive grease will result in a stoppage of work to contain the leak, grease, or spill. Work will not commence until the necessary cleanup and repairs are completed.

The GNWT-MTS Syncro Yard has its own preventive measures, which should be followed whenever fuelling (Appendix B).

When possible, any mechanical maintenance should be performed at the GNWT-MTS Syncro Yard, where spills are less likely to reach sensitive environments and plenty of equipment and experienced staff are present to mitigate leaks and spills from occurring.

Paper copies of the SCP will be distributed to the contractor, and a copy should be available in all vehicles. Copies should also be available at the GNWT-MTS Syncro Yard. For additional copies, contact the GNWT.



## 4 SPILL RESPONSE ACTION PLAN

When responding to any spill, personal protective equipment (PPE) should be used and must include:

- Tyvek coveralls;
- Plastic gloves;
- Safety goggles; and
- Leak-proof boots.


### 4.1 Procedure for Initial Actions

Take the following initial actions when responding to a spill:

- 1) Notify personnel in the immediate area of the spill. Advise the personnel to stay clear of the spill and any associated leaks, and have them monitor the spill so that the response team can best capture it and prevent its spread.
- 2) Identify any ignition sources and shut them off if it is safe to do so. An ignition source that is not safe to access could include one that requires an employee to cross a pool of the spilled liquid, one that is close enough to a leak that ignition could happen at any time, or one that was caused by damage to a vessel and could have resulted in unknown damage nearby.
- 3) Stop the spill at the source if it is safe to do so. This might include shutting off valves, righting containers, patching holes, or placing a spill tray.

If a spill occurs, follow the actions described in Figure 4-1.

Figure 4-1 Spill Response Flow Chart



## 4.2 Procedure for Reporting a Spill

Report all spills immediately to the site supervisor, who will determine whether the spill needs to be reported to the NWT 24-hour spill report line. Information that should be reported includes the approximate quantity, product, type, location, whether the spill is still in progress, product odour and colour, and the weather:

a. Immediately reportable spills

A spill is immediately reportable if it meets or exceeds the volumes outlined in Appendix C. A spill that meets or exceeds these volumes must be reported to the NWT 24-hour spill report line.

b. Minor spills

A spill is minor if it has a quantity less than that outlined in Appendix C. A minor spill does not need to be reported immediately to the NWT 24-hour spill report line, but it must be tracked and documented so that the relevant information can be submitted to the contractor project manager. These spills can be recorded and tracked in a non-reportable spill log for task and cleanup tracking. If there is any doubt whether the quantity spilled exceeds the reportable levels outlined in Appendix C, the spill should be reported to the NWT 24-hour spill report line.

Any spill that occurs during the project should be reported to the supervisors and project manager. For any spill, fill out an NT-NU spill report form (Appendix D) and email or fax it to the NWT 24-hour spill report line:

NWT 24-Hour Spill Report Line  
Phone: 867-920-8130  
Fax: 867-873-6924  
Email: [spills@gov.nt.ca](mailto:spills@gov.nt.ca)

## 4.3 Procedure for Containing and Controlling a Spill

Activate the spill response team. There should always be an on-scene commander (OSC) designated to respond to a potential spill. This person should be trained in spill response, Transportation of Dangerous Goods (TDG), and the Workplace Hazard Materials Information System (WHMIS). They should be familiar with the equipment and be knowledgeable about potential failures that could cause spills. They should also be familiar with the location of PPE required in cases of spill management and will be responsible for ensuring its use during the spill response protocols.

At the GNWT-MTS Syncro Yard, whoever discovers the spill first will be the OSC until an MTS employee arrives, at which point the MTS employee will take over.

The contractor for the barge and temporary storage sites should determine who will be designated as an OSC and should always have someone with adequate training and experience on site.

Determine the source of the spilled material. Using knowledge based on the source of the leak, colour, and smell, identify the spilled material. Check the SDS for hazards associated with any suspected materials.

Once the source and hazards have been identified, determine whether the spill can be stopped at the source and begin taking actions to clean up the spilled material.

#### 4.4 Containing a Spill on Land

Spills on land will primarily be on soil. Soil is a naturally absorbent material, so it will likely soak up most spilled material. Spills could also occur on a hard material, such as a road or parking lot; depending on the volume spilled, this could result in significant overland flow. Spills on land near water should be contained before they can reach the waterbody. The following are possible containment methods that can be used:

**Absorbents:** If the spill is small, use enough absorbent pads to soak up the liquid.

**Dykes:** Dykes can be built using soil to surround a spill on land. Dykes are constructed downslope and wider than the predicted flow path of the spill.

**Trenches:** Trenches can be dug out to contain spills if the top layer of soil is not rock. Shovels, axes, or an excavator can be used, depending on the size of the spill. A trench should be dug down deep enough to contain more than the expected volume of spilled material. Absorbents or a vacuum should be used to start collecting the spill material as soon as possible to prevent the contaminants from spreading.

#### 4.5 Containing a Spill on Water

Spills in the three fingers in the East Channel could get transported downstream quickly, and as such, any spills in these areas should be contained as quickly as possible. The following are possible containment methods that can be used:

**Absorbents:** A small spill, identified by an oily, rainbow-coloured sheen on the surface of the water, should be captured quickly using as many absorbent pads as it takes to remove the sheen.

**Oil spill containment boom:** For larger spills that cannot be absorbed immediately, use an oil spill containment boom. This floating, flexible boom can be used to surround the spill and prevent it from spreading while the spilled product is removed using a vacuum, if available, or using absorbent pads.

**Nets and absorbents:** If the spill occurs in moving water and cannot be surrounded easily with a boom, a floating net filled with absorbents can be used downstream to filter out surface spills as they flow through.

#### 4.6 Worst-Case Scenario

Dealing with a tank failure or other out-of-control leak at the GNWT-MTS Syncro Yard would present a possible worst-case scenario. In this case, follow the protocols in the GNWT-MTS Syncro Yard SCP (Appendix B).

A worst-case scenario at a soil storage area would be a punctured tank of fuel or other fluid. In this case, create a trench or collection pit downstream of the spill to contain the full volume of the tanks.

The most concerning in a worst-case scenario is a large spill on the river, in moving water. In this case, call an emergency response mobile unit to deal with the spill using appropriate equipment. In the interim, use absorbent booms and nets filled with absorbent pads to contain or slow down the spread of the leak over water.

#### **4.7 Procedure for Transferring, Storing, and Managing Spill-Related Wastes**

For disposing of contaminated materials related to any spills that occur at the GNWT-MTS Syncro Yard, follow the GNWT-MTS Syncro Yard SCP (Appendix B).

Contain sorbent pads and booms from spills on the barge and near the temporary storage sites in a leak-proof bag or other container and dispose of them at an approved facility. If small amounts of soil become contaminated from a leak, contain the soil, and dispose of it at an approved facility.

#### **4.8 Procedure for Restoring Affected Areas, Providing Regulatory Inspectors with Status Updates, and Cleanup Completion**

After a spill that is of a volume that is immediately reportable has been contained, the contractor will consult the lead agency inspector assigned to the file to determine the next steps and the level of required cleanup. The inspector may require a site-specific study to confirm that proposed cleanup levels are acceptable. Factors that may be considered are the replacement of soil and restoration of vegetation. The impacts from minor spills will be significantly harmful than that of an immediately reportable spill; however, depending on the size of spill, the spill reporting agency may require some extra steps or restoration effort after the spill has been contained, cleaned up, and reported.

### **5 TRAINING AND EXERCISES**

The contractor will be responsible for providing a qualified supervisor and for training employees in spill response. All on-site workers on the project will have their basic first aid and WHMIS training before working on the project. Any personnel involved in the handling or transportation of hazardous materials will receive TDG training and will maintain a valid TDG certificate. A training session on spill prevention and response will be held for all individuals before project start-up. Training seminars, including those on the proper use of spill kits on both land and water, will provide hands-on training for individuals on spill response procedures and equipment. The training seminars will cover:

- Individual roles and responsibilities regarding spill prevention, detection, response, and cleanup;
- Locations of paper copies of the SCP, maps, spill kits, and the types of kits at each working location;
- Equipment available for spill response;
- Content of spill kits;
- Initial spill response actions and spill reporting procedures;
- Spill response and cleanup actions; and
- Mock exercises: The contractor will conduct training sessions and mock exercises as part of worker orientation, which should cover spills on land and on water.

The contractor is responsible for keeping records of all attendees of the training session and exercises, as well as copies of their training certificates (e.g., first aid, WHMIS, spill response).

## 6 MEDIA AND PUBLIC ENQUIRIES

All enquiries from media or otherwise are to be directed to GNWT – Public Affairs and Communications. Environmental incidents, such as spills, attract local interest and media attention. Site workers will not make any statements on behalf of the contractor or GNWT-INF to the media or the public.

Employees will respond to any requests from local authorities or emergency workers, which will help to minimize the spill and its impacts. The project workers will refer all other requests for information to the GNWT – Public Affairs and Communications. This may include questions from reporters, environmental agencies, or local residents affected by a spill.

When questions are asked, employees should keep the response polite and professional; for example, “I’m sorry, I am not the spokesperson for the project. Please write down your name, media affiliation, and contact information. I will have the project spokesperson contact you as soon as possible.”

In the event that questions are persistent or if concerned local community members become aggressive, employees should remain calm and not engage; if necessary, apologize and make an excuse to exit the conversation. If the contractor is local, friends and family of the project workers may ask for information; employees should be reminded that they must keep the details of the spill confidential.

## CLOSURE

This spill contingency plan was prepared for the Government of Northwest Territories – Department of Infrastructure for the Hay River Harbour restoration project in 2023.

The services provided by Associated Environmental Consultants Inc. in the preparation of this report were conducted in a manner consistent with the level of skill ordinarily exercised by members of the profession currently practising under similar conditions. No other warranty expressed or implied is made.

Respectfully submitted,

Associated Environmental Consultants Inc.

Prepared by:

Reviewed by:

Jayden Gross, B.Sc., A.T.Ag.  
Environmental Scientist

Jennifer Brown, P.Eng., MEERL  
Project Manager

## REFERENCES

Associated Environmental Consultants Inc. (Associated). 2023a. Hay River Harbour Restoration – Sediment and Erosion Control Plan.

Canadian Council of Ministers of the Environment (CCME). 1999. Canadian Water Quality Guidelines for the Protection of Aquatic Life: Total Particulate Matter and Summary Tables.

Indian and Northern Affairs Canada. 2007. Guidelines for Spill Contingency Planning. Available at: <http://www.ainc-inac.gc.ca/ai/scr/nt/ntr/pubs/SCP-eng.asp>.



## APPENDIX A – SAFETY DATA SHEETS FOR SPILLABLE MATERIALS

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

### SECTION 1. IDENTIFICATION

Product name : ENVIRON<sup>TM/MC</sup> MV 32

Product code : ENVMV32P20, ENVMV32IBC, ENVMV32DRM, ENVMV32DCT, ENVMV32, ENVMV32BLK

#### Manufacturer or supplier's details

Petro-Canada Lubricants Inc.  
2310 Lakeshore Road West  
Mississauga ON L5J 1K2  
Canada  
Telephone : 1-905-403-6785

#### Emergency telephone number

Emergency telephone number : CHEMTREC: 1-800-424-9300;  
Poison Control Centre: Consult local telephone directory for emergency number(s).

#### Recommended use of the chemical and restrictions on use

Recommended use : ENVIRON MV is designed as heavy duty hydraulic power transmission fluids for use in equipment, which must operate over a wide range of temperatures. Typically, ENVIRON MV Oils are used in hydraulic systems, machine tools, hydraulic presses, rotary compressors, and centrifugal pumps. The ashless, or zinc-free, additive system used in ENVIRON MV oils makes them especially suitable for use in environmentally sensitive areas.

Prepared by : Product Safety: +1 905-491-0565

### SECTION 2. HAZARDS IDENTIFICATION

#### GHS classification in accordance with the Hazardous Products Regulations

Not a hazardous substance or mixture.

#### GHS label elements

Not a hazardous substance or mixture.

#### Other hazards

None known.

#### IARC

No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

### SECTION 3. COMPOSITION/INFORMATION ON INGREDIENTS

Substance / Mixture : Mixture

#### Components

Chemical name	CAS-No.	Concentration (% w/w)
Lubricating oils (petroleum), C15-30,	72623-86-0	50 - 70

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

hydrotreated neutral oil-based; Baseoil — unspecified		
Lubricating oils (petroleum), C20-50, hydrotreated neutral oil-based; Baseoil — unspecified	72623-87-1	20 - 30
2,6-di-tert-butylphenol	128-39-2	0.1 - 1

Actual concentration or concentration range is withheld as a trade secret

### SECTION 4. FIRST AID MEASURES

- If inhaled : Move to fresh air.  
Artificial respiration and/or oxygen may be necessary.  
Seek medical advice.
- In case of skin contact : In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes.  
Wash skin thoroughly with soap and water or use recognized skin cleanser.  
Wash clothing before reuse.  
Seek medical advice.
- In case of eye contact : Remove contact lenses.  
Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes.  
Obtain medical attention.
- If swallowed : Rinse mouth with water.  
DO NOT induce vomiting unless directed to do so by a physician or poison control center.  
Never give anything by mouth to an unconscious person.  
Seek medical advice.
- Most important symptoms and effects, both acute and delayed : First aider needs to protect himself.

### SECTION 5. FIREFIGHTING MEASURES

- Suitable extinguishing media : Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.
- Unsuitable extinguishing media : No information available.
- Specific hazards during firefighting : Cool closed containers exposed to fire with water spray.
- Hazardous combustion products : Carbon oxides (CO, CO<sub>2</sub>), sulphur oxides (SO<sub>x</sub>), hydrogen sulphide (H<sub>2</sub>S), alkyl mercaptans, sulfides, smoke and irritating vapours as products of incomplete combustion.
- Further information : Prevent fire extinguishing water from contaminating surface water or the ground water system.

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

### SECTION 6. ACCIDENTAL RELEASE MEASURES

- Personal precautions, protective equipment and emergency procedures : Use personal protective equipment.  
Ensure adequate ventilation.  
Evacuate personnel to safe areas.  
Material can create slippery conditions.  
Mark the contaminated area with signs and prevent access to unauthorized personnel.  
Only qualified personnel equipped with suitable protective equipment may intervene.
- Environmental precautions : Do not allow uncontrolled discharge of product into the environment.
- Methods and materials for containment and cleaning up : Prevent further leakage or spillage if safe to do so.  
Remove all sources of ignition.  
Soak up with inert absorbent material.  
Non-sparking tools should be used.  
Ensure adequate ventilation.  
Contact the proper local authorities.

### SECTION 7. HANDLING AND STORAGE

- Advice on protection against fire and explosion : None known.
- Advice on safe handling : For personal protection see section 8.  
Smoking, eating and drinking should be prohibited in the application area.  
Use only with adequate ventilation.  
In case of insufficient ventilation, wear suitable respiratory equipment.  
Avoid contact with skin, eyes and clothing.  
Do not ingest.  
Keep away from heat and sources of ignition.  
Keep container closed when not in use.
- Conditions for safe storage : Store in original container.  
Containers which are opened must be carefully resealed and kept upright to prevent leakage.  
Keep in a dry, cool and well-ventilated place.  
Keep in properly labelled containers.  
To maintain product quality, do not store in heat or direct sunlight.

### SECTION 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

#### Components with workplace control parameters

Components	CAS-No.	Value type (Form of exposure)	Control parameters / Permissible concentration	Basis
Lubricating oils (petroleum),	72623-86-0	TWA (Mist)	5 mg/m <sup>3</sup>	CA AB OEL

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

C15-30, hydrotreated neutral oil-based; Baseoil — unspecified				
		STEL (Mist)	10 mg/m3	CA AB OEL
		TWAEV (Mist)	5 mg/m3	CA QC OEL
		STEV (Mist)	10 mg/m3	CA QC OEL
		TWA (Mist)	1 mg/m3	CA BC OEL
		TWA (Inhalable particulate matter)	5 mg/m3	ACGIH
Lubricating oils (petroleum), C20-50, hydrotreated neutral oil-based; Baseoil — unspecified	72623-87-1	TWA (Mist)	5 mg/m3	CA AB OEL
		STEL (Mist)	10 mg/m3	CA AB OEL
		TWAEV (Mist)	5 mg/m3	CA QC OEL
		STEV (Mist)	10 mg/m3	CA QC OEL
		TWA (Mist)	1 mg/m3	CA BC OEL
		TWA (Inhalable particulate matter)	5 mg/m3	ACGIH

**Engineering measures** : No special ventilation requirements. Good general ventilation should be sufficient to control worker exposure to airborne contaminants.

### Personal protective equipment

**Respiratory protection** : Use respiratory protection unless adequate local exhaust ventilation is provided or exposure assessment demonstrates that exposures are within recommended exposure guidelines. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

**Filter type** : organic vapour filter

**Hand protection**  
**Material** : neoprene, nitrile, polyvinyl alcohol (PVA), Viton®.

**Remarks** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary.

**Eye protection** : Wear face-shield and protective suit for abnormal processing problems.

**Skin and body protection** : Choose body protection in relation to its type, to the concentration and amount of dangerous substances, and to the specific work-place.

**Protective measures** : Wash contaminated clothing before re-use.

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

Hygiene measures : Remove and wash contaminated clothing and gloves, including the inside, before re-use.  
Wash face, hands and any exposed skin thoroughly after handling.

### SECTION 9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance : viscous liquid

Colour : Pale, straw-yellow.

Odour : Mild petroleum oil like.

Odour Threshold : No data available

pH : No data available

Pour point : -48 °C (-54 °F)

Boiling point/boiling range : No data available

Flash point : 239 °C (462 °F)  
Method: Cleveland open cup

Fire Point : No data available

Evaporation rate : No data available

Flammability : Low fire hazard. This material must be heated before ignition will occur.

Auto-Ignition Temperature : No data available

Upper explosion limit / Upper flammability limit : No data available

Lower explosion limit / Lower flammability limit : No data available

Vapour pressure : No data available

Relative vapour density : No data available

Relative density : No data available

Density : 0.8462 kg/l (15 °C / 59 °F)

Solubility(ies)

Water solubility : insoluble

Partition coefficient: n-octanol/water : No data available

Viscosity

Viscosity, kinematic : 33.8 cSt (40 °C / 104 °F)

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

6.7 cSt (100 °C / 212 °F)

Explosive properties : Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition.

### SECTION 10. STABILITY AND REACTIVITY

Possibility of hazardous reactions : Hazardous polymerisation does not occur. Stable under normal conditions.

Conditions to avoid : No data available

Incompatible materials : Reactive with oxidising agents, reducing agents and acids.

Hazardous decomposition products : May release CO<sub>x</sub>, SO<sub>x</sub>, PO<sub>x</sub>, H<sub>2</sub>S, sulfides, alkyl mercaptans, methacrylate monomers, alkenes, diphenylamine, smoke and irritating vapours when heated to decomposition.

### SECTION 11. TOXICOLOGICAL INFORMATION

#### Information on likely routes of exposure

Eye contact  
Ingestion  
Inhalation  
Skin contact

#### Acute toxicity

##### Product:

Acute oral toxicity : Remarks: No data available

Acute inhalation toxicity : Assessment: The substance or mixture has no acute inhalation toxicity  
Remarks: No data available

Acute dermal toxicity : Assessment: The substance or mixture has no acute dermal toxicity  
Remarks: No data available

##### Components:

#### **Lubricating oils (petroleum), C15-30, hydrotreated neutral oil-based; Baseoil — unspecified:**

Acute oral toxicity : LD50 (Rat): > 5,000 mg/kg,

Acute inhalation toxicity : LC50 (Rat): > 5.2 mg/l  
Exposure time: 4 h  
Test atmosphere: dust/mist

Acute dermal toxicity : LD50 (Rabbit): > 2,000 mg/kg,

#### **Lubricating oils (petroleum), C20-50, hydrotreated neutral oil-based; Baseoil — unspecified:**

Acute oral toxicity : LD50 (Rat): > 5,000 mg/kg,

# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

Acute inhalation toxicity : LC50 (Rat): > 5.2 mg/l  
Exposure time: 4 h  
Test atmosphere: dust/mist

Acute dermal toxicity : LD50 (Rabbit): > 2,000 mg/kg,

### Skin corrosion/irritation

#### Product:

Remarks : No data available

### Serious eye damage/eye irritation

#### Product:

Remarks : No data available

### Respiratory or skin sensitisation

No data available

### Germ cell mutagenicity

No data available

### Carcinogenicity

No data available

### Reproductive toxicity

No data available

### STOT - single exposure

No data available

### STOT - repeated exposure

No data available

---

## SECTION 12. ECOLOGICAL INFORMATION

### Ecotoxicity

#### Product:

Toxicity to fish : LC50 (Oncorhynchus mykiss (rainbow trout)): > 1,000 mg/l  
Exposure time: 96 h  
Method: OECD Test Guideline 203

NOEC (Fish): > 100 mg/l  
Exposure time: 28 Days

Toxicity to daphnia and other : EC50 (Daphnia magna (Water flea)): > 10,000 mg/l  
aquatic invertebrates : Exposure time: 48 h  
Method: OECD Test Guideline 202

NOEC (Daphnia (water flea)): > 20 mg/l  
Exposure time: 21 Days



# SAFETY DATA SHEET

## ENVIRON<sup>TM/MC</sup> MV 32



000003000466

Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

Toxicity to algae/aquatic plants : EC50 (Pseudokirchneriella subcapitata (algae)): > 9,000 mg/l Exposure time: 72 h  
Method: OECD Test Guideline 201

NOEC (Pseudokirchneriella subcapitata (algae)): > 1 mg/l Exposure time: 72 h  
Remarks: No toxicity at the limit of solubility

Toxicity to microorganisms : Remarks: No data available

### Persistence and degradability

#### Product:

Biodegradability : Result: Inherently biodegradable.

### Bioaccumulative potential

No data available

### Mobility in soil

No data available

### Other adverse effects

No data available

---

## SECTION 13. DISPOSAL CONSIDERATIONS

### Disposal methods

Waste from residues : The product should not be allowed to enter drains, water courses or the soil.  
Offer surplus and non-recyclable solutions to a licensed disposal company.  
Waste must be classified and labelled prior to recycling or disposal.  
Send to a licensed waste management company.  
Dispose of product residue in accordance with the instructions of the person responsible for waste disposal.

---

## SECTION 14. TRANSPORT INFORMATION

### International Regulations

#### IATA-DGR

Not regulated as a dangerous good

#### IMDG-Code

Not regulated as a dangerous good

### Transport in bulk according to Annex II of MARPOL 73/78 and the IBC Code

### National Regulations

#### TDG

Not regulated as a dangerous good

# SAFETY DATA SHEET

**ENVIRON<sup>TM/MC</sup> MV 32**

000003000466



Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

## SECTION 15. REGULATORY INFORMATION

**The components of this product are reported in the following inventories:**

DSL	: On the inventory, or in compliance with the inventory
TSCA	: All chemical substances in this product are either listed on the TSCA Inventory or are in compliance with a TSCA Inventory exemption.
IECSC	: On the inventory, or in compliance with the inventory

## SECTION 16. OTHER INFORMATION

### Full text of other abbreviations

ACGIH	: USA. ACGIH Threshold Limit Values (TLV)
CA AB OEL	: Canada. Alberta, Occupational Health and Safety Code (table 2: OEL)
CA BC OEL	: Canada. British Columbia OEL
CA QC OEL	: Québec. Regulation respecting occupational health and safety, Schedule 1, Part 1: Permissible exposure values for airborne contaminants
ACGIH / TWA	: 8-hour, time-weighted average
CA AB OEL / TWA	: 8-hour Occupational exposure limit
CA AB OEL / STEL	: 15-minute occupational exposure limit
CA BC OEL / TWA	: 8-hour time weighted average
CA QC OEL / TWA EV	: Time-weighted average exposure value
CA QC OEL / STEV	: Short-term exposure value

AIIC - Australian Inventory of Industrial Chemicals; ANTT - National Agency for Transport by Land of Brazil; ASTM - American Society for the Testing of Materials; bw - Body weight; CMR - Carcinogen, Mutagen or Reproductive Toxicant; DIN - Standard of the German Institute for Standardisation; DSL - Domestic Substances List (Canada); ECx - Concentration associated with x% response; ELx - Loading rate associated with x% response; EmS - Emergency Schedule; ENCS - Existing and New Chemical Substances (Japan); ErCx - Concentration associated with x% growth rate response; ERG - Emergency Response Guide; GHS - Globally Harmonized System; GLP - Good Laboratory Practice; IARC - International Agency for Research on Cancer; IATA - International Air Transport Association; IBC - International Code for the Construction and Equipment of Ships carrying Dangerous Chemicals in Bulk; IC50 - Half maximal inhibitory concentration; ICAO - International Civil Aviation Organization; IECSC - Inventory of Existing Chemical Substances in China; IMDG - International Maritime Dangerous Goods; IMO - International Maritime Organization; ISHL - Industrial Safety and Health Law (Japan); ISO - International Organisation for Standardization; KECI - Korea Existing Chemicals Inventory; LC50 - Lethal Concentration to 50 % of a test population; LD50 - Lethal Dose to 50% of a test population (Median Lethal Dose); MARPOL - International Convention for the Prevention of Pollution from Ships; n.o.s. - Not Otherwise Specified; Nch - Chilean Norm; NO(A)EC - No Observed (Adverse) Effect Concentration; NO(A)EL - No Observed (Adverse) Effect Level; NOELR - No Observable Effect Loading Rate; NOM - Official Mexican Norm; NTP - National Toxicology Program; NZIoC - New Zealand Inventory of Chemicals; OECD - Organization for Economic Co-operation and Development; OPPTS - Office of Chemical Safety and Pollution Prevention; PBT - Persistent, Bioaccumulative and Toxic substance; PICCS - Philippines Inventory of Chemicals and Chemical Substances; (Q)SAR - (Quantitative) Structure Activity Relationship; REACH - Regulation (EC) No 1907/2006 of the European Parliament and of the Council concerning the Registration, Evaluation, Authorisation and Restriction of Chemicals;

# SAFETY DATA SHEET

**ENVIRON<sup>TM/MC</sup> MV 32**

**000003000466**



Version 4.6

Revision Date 2022/07/12

Print Date 2022/07/12

SADT - Self-Accelerating Decomposition Temperature; SDS - Safety Data Sheet; TCSI - Taiwan Chemical Substance Inventory; TDG - Transportation of Dangerous Goods; TECI - Thailand Existing Chemicals Inventory; TSCA - Toxic Substances Control Act (United States); UN - United Nations; UNRTDG - United Nations Recommendations on the Transport of Dangerous Goods; vPvB - Very Persistent and Very Bioaccumulative; WHMIS - Workplace Hazardous Materials Information System

For Copy of SDS : Internet: [lubricants.petro-canada.com/sds](http://lubricants.petro-canada.com/sds)  
Western Canada, telephone: 1-800-661-1199; fax: 1-800-378-4518  
Ontario & Central Canada, telephone: 1-800-268-5850; fax: 1-800-201-6285  
Quebec & Eastern Canada, telephone: 1-800-576-1686; fax: 1-800-201-6285  
For Product Safety Information: 1 905-491-0565

Prepared by : Product Safety: +1 905-491-0565

Revision Date : 2022/07/12  
Date format : yyyy/mm/dd

The information is considered as correct, but not exhaustive, and will be used only as a guide, which is based in the current knowledge of the substance or mixture, and is applicable to proper safety precautions for the product.

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

CA / EN

# Safety Data Sheet

OSHA Hazard Communication Standard 29 CFR 1910.1200. Prepared to GHS Rev 3.

Revision date: Initial version

Date of issue: Feb.11, 2015

<b>Product name:</b> Biodegradable Hydraulic Fluid
--

## SECTION 1: Identification

<b>Product identifier:</b>	<b>Biodegradable Hydraulic Fluid.</b>
<b>Synonyms:</b>	None.
<b>Product Code:</b>	9645,9646.
<b>SDS number:</b>	CGF003
<b>Recommended use:</b>	Hydraulic Lubrication.
<b>Recommended restrictions:</b>	None known.

### Manufacturer/Importer/Supplier/Distributor information:

<b>Company Name:</b>	SPX Hydraulic Technologies.
<b>Company Address:</b>	5885 11th Street Rockford, IL 61109
<b>Company Telephone:</b>	Office hours (Mon – Fri) 8.00am – 5:00pm (CST) (815) 874-5556
<b>Company Contact Name:</b>	EH&S Department.
<b>Emergency phone number:</b>	INFOTRAC 24 Hour Emergency Numbers: USA, Canada, Puerto Rico (800) 535-5053. International (352) 323-3500.

## SECTION 2: Hazard(s) identification

### Classification of the chemical in accordance with paragraph (d) of §1910.1200:

This material is not hazardous under the criteria of the Federal OSHA Hazard Communication Standard 29CFR 1910.1200.

#### *Physical hazards*

Not classified as a physical hazard under GHS criteria..

#### *Health hazards*

Not classified as a health hazard under GHS criteria.

#### *Environmental hazards*

Not classified as an environmental hazard under GHS criteria.

<b>GHS Signal word:</b>	<b>Not applicable.</b>
-------------------------	------------------------

<b>GHS Hazard statement(s):</b>	Not applicable.
---------------------------------	-----------------

<b>GHS Hazard symbol(s):</b>	Not applicable.
------------------------------	-----------------

**GHS Precautionary statement(s):**

**Prevention:** No prevention precautionary phrases.

**Response:** No response precautionary phrases.

**Storage:** No storage precautionary phrases.

**Disposal:** No disposal precautionary phrases.

**Hazard(s) not otherwise**

**Classified (HNOC):**

Not classified as flammable but will burn.  
Prolonged or repeated skin contact without proper cleaning can clog the pores of the skin resulting in disorders such as oil acne/folliculitis. Used oil may contain harmful impurities.

**Percentage of ingredient(s) of unknown acute toxicity:**

Not applicable.

**SECTION 3: Composition/information on ingredients**

**Substance**

Chemical name	Concentration (weight %)	CAS#
Distillates, petroleum, hydrotreated heavy paraffinic	> 95	64742-54-7
Non-Hazardous Materials	< 5	Various

**SECTION 4: First-aid Measures**

**Inhalation:** First aid is not normally required. If breathing difficulties develop, move victim away from source of exposure and into fresh air in a position comfortable for breathing. Seek immediate medical attention.

**Skin contact:** Remove contaminated shoes and clothing and cleanse affected area(s) thoroughly by washing with mild soap and water or a waterless hand cleaner. If irritation or redness develops and persists, seek medical attention. If product is injected into or under the skin, or into any part of the body, regardless of the appearance of the wound or its size, the individual should be evaluated immediately by a physician (see Indication of immediate medical attention below).

**Eye contact:** If irritation or redness develops from exposure, flush eyes with clean water. If symptoms persist, seek medical attention.

**Ingestion:** First aid is not normally required; however, if swallowed and symptoms develop, seek medical attention.

**Most important symptoms/effects, acute and delayed:** Most important symptoms and effects, both acute and delayed: Inhalation of oil mists or vapors generated at elevated temperatures may cause respiratory irritation. Accidental ingestion can result in minor irritation of the digestive tract, nausea and diarrhea. Dry skin and possible irritation with repeated or prolonged exposure.

**Indication of immediate medical attention and special treatment needed:** Acute aspirations of large amounts of oil-laden material may produce a serious aspiration pneumonia. Patients who aspirate these oils should be followed for the development of long-term sequelae. Inhalation exposure to oil mists below current workplace exposure limits is unlikely to cause pulmonary abnormalities. When using high-pressure equipment, injection of product under the skin can occur. In this case, the casualty should be sent immediately to the hospital. Do not wait for symptoms to develop. High-pressure hydrocarbon injection injuries may produce substantial necrosis of underlying tissue despite an innocuous appearing external wound. These injuries often require extensive emergency surgical debridement and all injuries should be evaluated by a specialist in order to assess the extent of injury. Early surgical treatment within the first few hours may significantly reduce the ultimate extent of injury.

#### **SECTION 5: Fire-fighting measures**

**Suitable extinguishing media:** Dry chemical, carbon dioxide, foam, or water spray is recommended. Water or foam may cause frothing of materials heated above 212°F / 100°C. Carbon dioxide can displace oxygen. Use caution when applying carbon dioxide in confined spaces.

**Unsuitable extinguishing media:** Simultaneous use of foam and water on the same surface is to be avoided as water destroys the foam.

#### **Specific hazards arising from the chemical:**

**Unusual Fire & Explosion Hazards:** This material may burn, but will not ignite readily. If container is not properly cooled, it can rupture in the heat of a fire.

**Hazardous Combustion Products:** Combustion may yield smoke, carbon monoxide, and other products of incomplete combustion. Oxides of sulfur, nitrogen or phosphorus may also be formed.

**Special protective equipment and precautions for fire-fighters:** Special protective actions for firefighters: For fires beyond the initial stage, emergency responders in the immediate hazard area should wear protective clothing. When the potential chemical hazard is unknown, in enclosed or confined spaces, a self contained breathing apparatus should be worn. In addition, wear other appropriate protective equipment as conditions warrant (see Section 8). Isolate immediate hazard area and keep unauthorized personnel out. Stop spill/release if it can be done safely. Move undamaged containers from immediate hazard area if it can be done safely. Water spray may be useful in minimizing or dispersing vapors and to protect personnel. Cool equipment exposed to fire with water, if it can be done safely. Avoid spreading burning liquid with water used for cooling purposes.

## **SECTION 6: Accidental release measures**

### **Personal precautions, protective equipment and emergency procedures:**

Personal precautions, protective equipment and emergency procedures: This material may burn, but will not ignite readily. Keep all sources of ignition away from spill/release. Stay upwind and away from spill/release. Avoid direct contact with material. For large spillages, notify persons down wind of the spill/release, isolate immediate hazard area and keep unauthorized personnel out. Wear appropriate protective equipment, including respiratory protection, as conditions warrant (see Section 8). See Sections 2 and 7 for additional information on hazards and precautionary measures.

**Environmental Precautions:** Stop spill/release if it can be done safely. Prevent spilled material from entering sewers, storm drains, other unauthorized drainage systems, and natural waterways. Use water sparingly to minimize environmental contamination and reduce disposal requirements. If spill occurs on water notify appropriate authorities and advise shipping of any hazard. Spills into or upon navigable waters, the contiguous zone, or adjoining shorelines that cause a sheen or discoloration on the surface of the water, may require notification of the National Response Center.

### **Methods and materials for containment and cleaning up:**

Notify relevant authorities in accordance with all applicable regulations. Immediate cleanup of any spill is recommended. Dike far ahead of spill for later recovery or disposal. Absorb spill with inert material such as sand or vermiculite, and place in suitable container for disposal. If spilled on water remove with appropriate methods (e.g. skimming, booms or absorbents). In case of soil contamination, remove contaminated soil for remediation or disposal, in accordance with local regulations.

Recommended measures are based on the most likely spillage scenarios for this material; however local conditions and regulations may influence or limit the choice of appropriate actions to be taken. See Section 13 for information on appropriate disposal.

## **SECTION 7: Handling and Storage**

**Precautions for safe handling:** Precautions for safe handling: Keep away from flames and hot surfaces. Wash thoroughly after handling. Use good personal hygiene practices and wear appropriate personal protective equipment (see section 8). Spills will produce very slippery surfaces. High pressure injection of hydrocarbon fuels, hydraulic oils or greases under the skin may have serious consequences even though no symptoms or injury may be apparent. This can happen accidentally when using high pressure equipment such as high pressure grease guns, fuel injection apparatus or from pinhole leaks in tubing of high pressure hydraulic oil equipment.

Do not enter confined spaces such as tanks or pits without following proper entry procedures such as ASTM D-4276 and 29CFR 1910.146. Do not wear contaminated clothing or shoes.

**Conditions for safe storage, including any incompatibles:** Keep container(s) tightly closed and properly labeled. Use and store this material in cool, dry, well-ventilated area away from heat and all sources of ignition. Store only in approved containers. Keep away from any

incompatible material (see Section 10). Protect container(s) against physical damage. "Empty" containers retain residue and may be dangerous. Do not pressurize, cut, weld, braze, solder, drill, grind, or expose such containers to heat, flame, sparks, or other sources of ignition. They may explode and cause injury or death. "Empty" drums should be completely drained, properly bunged, and promptly shipped to the supplier or a drum reconditioner. All containers should be disposed of in an environmentally safe manner and in accordance with governmental regulations. Before working on or in tanks which contain or have contained this material, refer to OSHA regulations, ANSI Z49.1, and other references pertaining to cleaning, repairing, welding, or other contemplated operations.

## **SECTION 8: Exposure controls/personal protection**

### **Control Parameters:**

### **Occupational exposure limits:**

<b>US OSHA HAZARDOUS COMPONENTS (29 CFR 1910.1200): Permissible Exposure Limits</b>		
<b>Substance</b>	<b>PEL-TWA (8 hour)</b>	<b>PEL-STEL (15 min)</b>
Distillates, petroleum, hydrotreated heavy paraffinic	5 mg/m <sup>3</sup> (as Oil Mist, if generated)	No data available

<b>US ACGIH Threshold Limit Values</b>		
<b>Substance</b>	<b>TLV-TWA (8 hour)</b>	<b>TLV-STEL (15 min)</b>
Distillates, petroleum, hydrotreated heavy paraffinic	5 mg/m <sup>3</sup> (as Oil Mist, if generated)	10 mg/m <sup>3</sup> (as Oil Mist, if generated)

<b>US NIOSH Guidelines</b>		
<b>Substance</b>	<b>REL - TWA</b>	<b>STEL</b>
Distillates, petroleum, hydrotreated heavy paraffinic	No data available	No data available

Note: State, local or other agencies or advisory groups may have established more stringent limits. Consult an industrial hygienist or similar professional, or your local agencies, for further information.

**Appropriate engineering controls:** If current ventilation practices are not adequate to maintain airborne concentrations below the established exposure limits, additional engineering controls may be required.

**Environmental exposure controls:** Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection



legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

**Individual protection measures, such as personal protective equipment:**

**Eye/face protection:** The use of eye/face protection is not normally required; however, good industrial hygiene practice suggests the use of eye protection that meets or exceeds ANSI Z.87.1 whenever working with chemicals.

**Skin and Hand protection:** The use of skin protection is not normally required; however, good industrial hygiene practice suggests the use of gloves or other appropriate skin protection whenever working with chemicals. Suggested protective materials: Nitrile.

**Respiratory protection:** Where there is potential for airborne exposure above the exposure limit a NIOSH certified air purifying respirator equipped with R or P95 filters may be used.

A respiratory protection program that meets or is equivalent to OSHA 29 CFR 1910.134 and ANSI Z88.2 should be followed whenever workplace conditions warrant a respirator's use. Air purifying respirators provide limited protection and cannot be used in atmospheres that exceed the maximum use concentration (as directed by regulation or the manufacturer's instructions), in oxygen deficient (less than 19.5 percent oxygen) situations, or under conditions that are immediately dangerous to life and health (IDLH).

**Other:** Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

**Thermal hazards:** No data available.

Suggestions provided in this section for exposure control and specific types of protective equipment are based on readily available information. Users should consult with the specific manufacturer to confirm the performance of their protective equipment. Specific situations may require consultation with industrial hygiene, safety, or engineering professionals.

## SECTION 9: Physical and chemical properties

### Appearance

**Physical state:**

Liquid.

**Form:**

Liquid.

**Color:**

Amber, Transparent.

**Odor:**

Petroleum.

<b>Odor threshold:</b>	Not available
<b>pH:</b>	Not available
<b>Melting point/freezing point:</b>	< -11°F / < -24°C
<b>Boiling point:</b>	Not available
<b>Flash point:</b>	> 320°F / >160°C (Test Method: Pensky-Martens Closed Cup (PMCC), ASTM D93, EPA 1010)
<b>Evaporation rate:</b>	Not available
<b>Flammability (solid, gas):</b>	May ignite
<b>Upper/lower flammability or explosive limits</b>	
<b>Flammability limit – lower (%):</b>	Not available
<b>Flammability limit – upper (%):</b>	Not available
<b>Explosive limit – lower (%):</b>	Not available
<b>Explosive limit – upper (%):</b>	Not available
<b>Vapor pressure:</b>	< 1 mm Hg
<b>Vapor density:</b>	> 1 (air=1)
<b>Specific gravity:</b>	0.86 - 0.88 @ 60°F (15.6°C)
<b>Solubility in water:</b>	Insoluble.
<b>Partition coefficient (n-octanol/water):</b>	Not available
<b>Auto-ignition temperature:</b>	Not available
<b>Decomposition temperature:</b>	Not available
<b>Viscosity:</b>	5 - 9 cSt @ 100°C; 30 - 73 cSt @ 40°C
<b>Other information</b>	
<b>Bulk density:</b>	7.18 - 7.28 lbs/gal
<b>Pour point:</b>	< -11°F / < -24°C

#### SECTION 10: Stability and Reactivity

<b>Reactivity:</b>	Not chemically reactive.
<b>Chemical stability:</b>	Stable under normal ambient and anticipated conditions of use.
<b>Possibility of hazardous reactions:</b>	Hazardous reactions not anticipated.
<b>Conditions to avoid:</b>	Extended exposure to high temperatures can cause decomposition. Avoid all possible sources of ignition.
<b>Incompatible materials:</b>	Avoid contact with strong oxidizing agents and strong reducing agents.
<b>Hazardous decomposition Products:</b>	Not anticipated under normal conditions of use.

#### SECTION 11: Toxicological information

##### Information on likely routes of exposure:

<b>Inhalation:</b>	Inhalation is not a likely route of exposure.
<b>Ingestion:</b>	Ingestion is not a likely route of exposure.
<b>Skin:</b>	Skin contact is a likely route of exposure.
<b>Eye:</b>	Eye contact is a likely route of exposure.

**Symptoms related to the physical, chemical, and toxicological characteristics:**

None known.

**Delayed and immediate effects and chronic effects from short or long-term exposure:**

None known.

**Acute toxicity:**

**Product/Ingredient Information:**

Substance	Test Type (species)	Value
Distillates, petroleum, hydrotreated heavy paraffinic	LD <sub>50</sub> Oral (Rat)	>5000 mg/kg
	LD <sub>50</sub> Dermal (Rabbit)	>2000 mg/kg
	LC <sub>50</sub> Inhalation (Rat)	> 5 mg/L (4h)

**Skin corrosion/irritation:**

Based upon information available on the known components, the product is may be slightly irritation. Prolonged or repeated skin contact without proper cleaning can clog the pores of the skin resulting in disorders such as oil acne/folliculitis.

**Serious eye damage/eye irritation:**

Based upon information available on the known components, the product may cause slight eye irritation.

**Respiratory sensitization:**

Based upon information available on the known components, the product is not expected to cause respiratory sensitization.

**Skin sensitization:**

Based upon information available on the known components, the product is not expected to cause skin sensitization.

**Germ cell mutagenicity:**

Based upon information available on the known components, the product is not anticipated to be a mutagen.

**Carcinogenicity:**

Based upon information available on the known components, the product is not anticipated to be a carcinogen.

**Reproductive toxicity:**

Based upon information available on the known components, the product is not anticipated to cause reproductive toxicity.

**Specific target organ toxicity-  
Single exposure:**

Based upon information available on the known components, the product is not anticipated to cause specific target organ toxicity after single exposure.

**Specific target organ toxicity-  
Repeat exposure:**

Based upon information available on the known components, the product is not anticipated to cause specific target organ toxicity after repeated or prolonged exposure.

**Aspiration hazard:**

Based upon information available, the product is not anticipated to be an aspiration hazard.

**Further information:**

No data available

**SECTION 12: Ecological information**

**Ecotoxicity:**

**Ingredient Information:**

Substance	Test Type	Species	Value
Distillates, petroleum, hydrotreated heavy paraffinic	LL/EL/IL50 (acute) NOEC/NOEL (chronic)	Fish	Practically non toxic: LL/EL/IL50 > 100 mg/l NOEC/NOEL > 100 mg/l (based on test data)
	LL/EL/IL50 (acute) NOEC/NOEL (chronic)	Invertebrate	Practically non toxic: LL/EL/IL50 > 100 mg/l NOEC/NOEL > 1.0 - <=10 mg/l (based on test data)
	LL/EL/IL50	Algae	Practically non toxic: LL/EL/IL50 > 100 mg/l

**Persistence and degradability:**

The hydrocarbons in this material are not readily biodegradable, but since they can be degraded by microorganisms, they are regarded as inherently biodegradable.

**Bioaccumulative potential:**

Log Kow values measured for the hydrocarbon components of this material are greater than 5.3, and therefore regarded as having the potential to bioaccumulate. In practice, metabolic processes may reduce bioconcentration.

<b>Mobility in soil:</b>	Volatilization to air is not expected to be a significant fate process due to the low vapor pressure of this material.
<b>Mobility in general:</b>	In water, base oils will float and spread over the surface at a rate dependent upon viscosity. There will be significant removal of hydrocarbons from the water by sediment adsorption. In soil and sediment, hydrocarbon components will show low mobility with adsorption to sediments being the predominant physical process. The main fate process is expected to be slow biodegradation of the hydrocarbon constituents in soil and sediment.
<b>Other adverse effects:</b>	Product is a mixture of non-volatile components, which are not expected to be released to air in any significant quantities. Not expected to have ozone depletion potential, photochemical ozone creation potential or global warming potential.

### **SECTION 13: Disposal considerations**

#### **Disposal instructions:**

The generator of a waste is always responsible for making proper hazardous waste determinations and needs to consider state and local requirements in addition to federal regulations.

This material, if discarded as produced, would not be a federally regulated RCRA "listed" hazardous waste and is not believed to exhibit characteristics of hazardous waste. See Sections 7 and 8 for information on handling, storage and personal protection and Section 9 for physical/chemical properties. It is possible that the material as produced contains constituents which are not required to be listed in the MSDS but could affect the hazardous waste determination. Additionally, use which results in chemical or physical change of this material could subject it to regulation as a hazardous waste.

This material under most intended uses would become "Used Oil" due to contamination by physical or chemical impurities. Whenever possible, Recycle used oil in accordance with applicable federal and state or local regulations. Container contents should be completely used and containers should be emptied prior to discard.

### **SECTION 14: Transport Information**

<b>Land Transport DOT:</b>	Not regulated. If shipped by land in a packaging having a capacity of 3,500 gallons or more, the provisions of 49 CFR, Part 130 apply. (Contains oil)
<b>Air Transport IATA:</b>	Not regulated. U.S. DOT compliance requirements may apply. See 49 CFR 171.22, 23 & 25.

**Sea Transport IMDG:** Not regulated.  
U.S. DOT compliance requirements may apply. See  
49 CFR 171.22, 23 & 25.

**Environmental Hazards:** No.

#### SECTION 15: Regulatory Information

##### USA:

**United States Federal Regulations:** This SDS complies with the OSHA, 29 CFR 1910.1200. The product is not classified as hazardous under OSHA.

**Toxic Substances Control Act (TSCA)** – All components are either listed on the US TSCA Inventory, or are not regulated under TSCA.

**SARA Superfund and Reauthorization Act of 1986 Title III sections 302, 311, 312 and 313:**

Section 302 – No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

**CERCLA Hazardous Substance List, 40 CFR 302.4:** This product does not contain chemicals listed on CERCLA.

**Clean Air Act (CAA) Section 112(r) Accidental Release Prevention (40 CFR 68.130):**  
Not listed.

**Clean Water Act Section 311 Hazardous Substances (40 CFR 117.3):** Not listed.

**SARA Title III**

**Section 302 Extremely Hazardous Substance (40 CFR 355, Appendix A):** Not listed.

**Section 311/312 (40 CFR 370):**

**Immediate Hazard:** No

**Delayed Hazard:** No

**Fire Hazard:** No

**Pressure Hazard:** No

**Reactivity Hazard:** No

**Section 313 Toxic Release Inventory (40 CFR 372):**  
Not listed.

**U.S. Export Control Classification Number:** EAR99

## STATE REGULATIONS:

This SDS contains specific health and safety data is applicable for state requirements. For details on your regulatory requirements you should contact the appropriate agency in your state.

**California Proposition 65 (California Safe Drinking Water and Toxic Enforcement Act of 1986):** Warning: This material may contain detectable quantities of the following chemicals, known to the State of California to cause cancer, birth defects or other reproductive harm, and which may be subject to the warning requirements of California Proposition 65 (CA Health & Safety Code Section 25249.5): Naphthalene (cancer), 1-Naphthylamine (cancer).

**Massachusetts Oil and Hazardous Materials List:** Mineral oil is listed on the Massachusetts Oil and Hazardous Materials List.

**Minnesota Hazardous Substance List:** Mineral oil mist is listed on the Minnesota HSL.

**New Jersey Environmental Hazardous Substances List:** Petroleum oil is listed on the New Jersey HSL.

**Pennsylvania Hazardous Substance List:** Mineral oil mist is listed on the Pennsylvania HSL.

### Canada

**WHMIS (Canada)** Not controlled under WHMIS (Canada).

**CANADA INVENTORY (DSL):** All components are either on the DSL, or are exempt from DSL listing requirements.

## SECTION 16: Other Information

**Revision Date:** February 11, 2015

### **Key to abbreviations:**

ACGIH American Conference of Governmental Industrial Hygienists;  
CAS# Chemical Abstracts Service Registry Number;  
CERCLA The Comprehensive Environmental Response, Compensation, and Liability Act;  
GHS Globally Harmonized System;  
LEL Lower Explosive Limit;  
NE Not Established;  
OSHA Occupational Safety and Health Administration;  
PEL Permissible Exposure Limit (OSHA);  
SARA Superfund Amendments and Reauthorization Act;  
STEL Short Term Exposure Limit (15 minutes);  
TLV Threshold Limit Value (ACGIH);  
TWA Time Weighted Average (8 hours);  
UEL Upper Explosive Limit;  
WHMIS Worker Hazardous Materials Information System (Canada)

**DISCLAIMER**

To the best of our knowledge, the information contained herein is accurate. However SPX Hydraulic Technologies does not assume any liability whatsoever for the accuracy or completeness of the information contained herein.

Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards which exist.



Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 1 of 14

## SAFETY DATA SHEET

**SECTION 1****PRODUCT AND COMPANY IDENTIFICATION****PRODUCT****Product Name:** NO. 2 DIESEL FUEL**Product Description:** Hydrocarbons and Additives**Product Code:** 123455-22, 123455-29, 152017-00**Intended Use:** Diesel engine fuel, Heating Oil**COMPANY IDENTIFICATION****Supplier:** EXXON MOBIL CORPORATION

22777 Springwoods Village Parkway

Spring, TX 77389 USA

**24 Hour Health Emergency**

609-737-4411

**Transportation Emergency Phone**

800-424-9300 or 703-527-3887 CHEMTREC

**Product Technical Information**

800-662-4525

**MSDS Internet Address**[www.exxon.com](http://www.exxon.com), [www.mobil.com](http://www.mobil.com)**SECTION 2****HAZARDS IDENTIFICATION**

This material is hazardous according to regulatory guidelines (see (M)SDS Section 15).

**CLASSIFICATION:**

Flammable liquid: Category 3.

Acute inhalation toxicant: Category 4. Skin irritation: Category 2. Carcinogen: Category 2. Specific target organ toxicant (repeated exposure): Category 2. Aspiration toxicant: Category 1.

**LABEL:****Pictogram:****Signal Word:** Danger**Hazard Statements:**

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 2 of 14

H226: Flammable liquid and vapor. H304: May be fatal if swallowed and enters airways. H315: Causes skin irritation. H332: Harmful if inhaled. H351: Suspected of causing cancer. H373: May cause damage to organs through prolonged or repeated exposure. Bone marrow, Liver, Thymus

#### Precautionary Statements:

P101: If medical advice is needed, have product container or label at hand. P102: Keep out of reach of children. P103: Read label before use. P201: Obtain special instructions before use. P202: Do not handle until all safety precautions have been read and understood. P210: Keep away from heat/sparks/open flames/hot surfaces. -- No smoking. P233: Keep container tightly closed. P240: Ground / bond container and receiving equipment. P241: Use explosion-proof electrical, ventilating, and lighting equipment. P242: Use only non-sparking tools. P243: Take precautionary measures against static discharge. P260: Do not breathe mist / vapours. P264: Wash skin thoroughly after handling. P271: Use only outdoors or in a well-ventilated area. P273: Avoid release to the environment. P280: Wear protective gloves/protective clothing/eye protection/face protection. P301 + P310: IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician. P302 + P352: IF ON SKIN: Wash with plenty of soap and water. P304 + P340: IF INHALED: Remove person to fresh air and keep comfortable for breathing. P308 + P313: IF exposed or concerned: Get medical advice/ attention. P312: Call a POISON CENTER or doctor/physician if you feel unwell. P331: Do NOT induce vomiting. P332 + P313: If skin irritation occurs: Get medical advice/ attention. P362 + P364: Take off contaminated clothing and wash it before reuse. P370 + P378: In case of fire: Use water fog, foam, dry chemical or carbon dioxide (CO2) to extinguish. P391: Collect spillage. P403 + P235: Store in a well-ventilated place. Keep cool. P405: Store locked up. P501: Dispose of contents and container in accordance with local regulations.

**Contains:** DIESEL OIL..C9-20

#### Other hazard information:

**HAZARD NOT OTHERWISE CLASSIFIED (HNOC):** None as defined under 29 CFR 1910.1200.

#### PHYSICAL / CHEMICAL HAZARDS

Material can accumulate static charges which may cause an ignition. Material can release vapors that readily form flammable mixtures. Vapor accumulation could flash and/or explode if ignited.

#### HEALTH HAZARDS

May cause central nervous system depression. High-pressure injection under skin may cause serious damage. Under conditions of poor personal hygiene and prolonged repeated contact, some polycyclic aromatic compounds (PACs) have been suspected as a cause of skin cancer in humans. May be irritating to the eyes, nose, throat, and lungs.

#### ENVIRONMENTAL HAZARDS

Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

<b>NFPA Hazard ID:</b>	Health: 2	Flammability: 2	Reactivity: 0
<b>HMIS Hazard ID:</b>	Health: 2*	Flammability: 2	Reactivity: 0

**NOTE:** This material should not be used for any other purpose than the intended use in Section 1 without expert advice. Health studies have shown that chemical exposure may cause potential human health risks which may vary from person to person.

### SECTION 3

### COMPOSITION / INFORMATION ON INGREDIENTS

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 3 of 14

This material is defined as a mixture.

**Hazardous Substance(s) or Complex Substance(s) required for disclosure**

Name	CAS#	Concentration*	GHS Hazard Codes
DIESEL OIL..C9-20	68334-30-5	80 - > 99%	H226, H304, H332, H351, H315, H373, H401, H411

**Hazardous Constituent(s) Contained in Complex Substance(s) required for disclosure**

Name	CAS#	Concentration*	GHS Hazard Codes
ETHYL BENZENE	100-41-4	0.1 - 1%	H225, H304, H332, H373, H401, H412
NAPHTHALENE	91-20-3	0.1 - 1%	H228(2), H302, H351, H400(M factor 1), H410(M factor 1)

\* All concentrations are percent by weight unless material is a gas. Gas concentrations are in percent by volume.

NOTE: Composition may contain up to 0.5% performance additives and / or dyes.

As per paragraph (i) of 29 CFR 1910.1200, formulation is considered a trade secret and specific chemical identity and exact percentage (concentration) of composition may have been withheld. Specific chemical identity and exact percentage composition will be provided to health professionals, employees, or designated representatives in accordance with applicable provisions of paragraph (i).

**SECTION 4 FIRST AID MEASURES**

**INHALATION**

Remove from further exposure. For those providing assistance, avoid exposure to yourself or others. Use adequate respiratory protection. If respiratory irritation, dizziness, nausea, or unconsciousness occurs, seek immediate medical assistance. If breathing has stopped, assist ventilation with a mechanical device or use mouth-to-mouth resuscitation.

**SKIN CONTACT**

Remove contaminated clothing. Dry wipe exposed skin and cleanse with waterless hand cleaner and follow by washing thoroughly with soap and water. For those providing assistance, avoid further skin contact to yourself or others. Wear impervious gloves. Launder contaminated clothing separately before reuse. Discard contaminated articles that cannot be laundered. If product is injected into or under the skin, or into any part of the body, regardless of the appearance of the wound or its size, the individual should be evaluated immediately by a physician as a surgical emergency. Even though initial symptoms from high pressure injection may be minimal or absent, early surgical treatment within the first few hours may significantly reduce the ultimate extent of injury.

**EYE CONTACT**

Flush thoroughly with water. If irritation occurs, get medical assistance.

**INGESTION**

Seek immediate medical attention. Do not induce vomiting.

**NOTE TO PHYSICIAN**

If ingested, material may be aspirated into the lungs and cause chemical pneumonitis. Treat appropriately.

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 4 of 14

## PRE-EXISTING MEDICAL CONDITIONS WHICH MAY BE AGGRAVATED BY EXPOSURE

Contains hydrocarbon solvent/petroleum hydrocarbons; skin contact may aggravate an existing dermatitis.

## SECTION 5

## FIRE FIGHTING MEASURES

### EXTINGUISHING MEDIA

**Appropriate Extinguishing Media:** Use water fog, foam, dry chemical or carbon dioxide (CO<sub>2</sub>) to extinguish flames.

**Inappropriate Extinguishing Media:** Straight Streams of Water

### FIRE FIGHTING

**Fire Fighting Instructions:** Flammable. Evacuate area. Prevent runoff from fire control or dilution from entering streams, sewers, or drinking water supply. Firefighters should use standard protective equipment and in enclosed spaces, self-contained breathing apparatus (SCBA). Use water spray to cool fire exposed surfaces and to protect personnel.

**Unusual Fire Hazards:** Vapors are flammable and heavier than air. Vapors may travel across the ground and reach remote ignition sources causing a flashback fire danger. Hazardous material. Firefighters should consider protective equipment indicated in Section 8.

**Hazardous Combustion Products:** Aldehydes, Incomplete combustion products, Oxides of carbon, Smoke, Fume, Sulfur oxides

### FLAMMABILITY PROPERTIES

**Flash Point [Method]:** >38°C (100°F) [ASTM D-93]

**Flammable Limits (Approximate volume % in air):** LEL: 0.6 UEL: 7.0

**Autoignition Temperature:** >200°C (392°F)

## SECTION 6

## ACCIDENTAL RELEASE MEASURES

### NOTIFICATION PROCEDURES

In the event of a spill or accidental release, notify relevant authorities in accordance with all applicable regulations. US regulations require reporting releases of this material to the environment which exceed the applicable reportable quantity or oil spills which could reach any waterway including intermittent dry creeks. The National Response Center can be reached at (800)424-8802.

### PROTECTIVE MEASURES

Avoid contact with spilled material. Warn or evacuate occupants in surrounding and downwind areas if required due to toxicity or flammability of the material. See Section 5 for fire fighting information. See the Hazard Identification Section for Significant Hazards. See Section 4 for First Aid Advice. See Section 8 for advice on the minimum requirements for personal protective equipment. Additional protective measures may be necessary, depending on the specific circumstances and/or the expert judgment of the emergency responders.

For emergency responders: Respiratory protection: half-face or full-face respirator with filter(s) for organic vapor and, when applicable, H<sub>2</sub>S, or Self Contained Breathing Apparatus (SCBA) can be used depending on the size of spill and potential level of exposure. If the exposure cannot be completely characterized or an oxygen deficient atmosphere is possible or anticipated, SCBA is recommended. Work gloves that are resistant to aromatic hydrocarbons are recommended. Note: gloves made of polyvinyl acetate (PVA) are not water-resistant and are not suitable for emergency use. Chemical goggles are recommended if splashes or contact

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 5 of 14

with eyes is possible. Small spills: normal antistatic work clothes are usually adequate. Large spills: full body suit of chemical resistant, antistatic material is recommended.

## SPILL MANAGEMENT

**Land Spill:** Eliminate all ignition sources (no smoking, flares, sparks or flames in immediate area). Stop leak if you can do it without risk. All equipment used when handling the product must be grounded. Do not touch or walk through spilled material. Prevent entry into waterways, sewer, basements or confined areas. A vapor suppressing foam may be used to reduce vapors. Use clean non-sparking tools to collect absorbed material. Absorb or cover with dry earth, sand or other non-combustible material and transfer to containers. Large Spills: Water spray may reduce vapor; but may not prevent ignition in closed spaces.

**Water Spill:** Stop leak if you can do it without risk. Eliminate sources of ignition. Warn other shipping. If the Flash Point exceeds the Ambient Temperature by 10 degrees C or more, use containment booms and remove from the surface by skimming or with suitable absorbents when conditions permit. If the Flash Point does not exceed the Ambient Air Temperature by at least 10C, use booms as a barrier to protect shorelines and allow material to evaporate. Seek the advice of a specialist before using dispersants.

Water spill and land spill recommendations are based on the most likely spill scenario for this material; however, geographic conditions, wind, temperature, (and in the case of a water spill) wave and current direction and speed may greatly influence the appropriate action to be taken. For this reason, local experts should be consulted. Note: Local regulations may prescribe or limit action to be taken.

## ENVIRONMENTAL PRECAUTIONS

Large Spills: Dike far ahead of liquid spill for later recovery and disposal. Prevent entry into waterways, sewers, basements or confined areas.

## SECTION 7

## HANDLING AND STORAGE

### HANDLING

Avoid all personal contact. Do not siphon by mouth. Do not use as a cleaning solvent or other non-motor fuel uses. For use as a motor fuel only. It is dangerous and/or unlawful to put fuel into unapproved containers. Do not fill container while it is in or on a vehicle. Static electricity may ignite vapors and cause fire. Place container on ground when filling and keep nozzle in contact with container. Do not use electronic devices (including but not limited to cellular phones, computers, calculators, pagers or other electronic devices, etc.) during safety critical tasks, such as bulk fuel loading or unloading operations, or in storage areas where vapors may be present, unless the devices are certified intrinsically safe by an approved national testing agency and to the safety standards required by national and/or local laws and regulations. Prevent small spills and leakage to avoid slip hazard. Material can accumulate static charges which may cause an electrical spark (ignition source). Use proper bonding and/or ground procedures. However, bonding and grounds may not eliminate the hazard from static accumulation. Consult local applicable standards for guidance. Additional references include American Petroleum Institute 2003 (Protection Against Ignitions Arising out of Static, Lightning and Stray Currents) or National Fire Protection Agency 77 (Recommended Practice on Static Electricity) or CENELEC CLC/TR 50404 (Electrostatics - Code of practice for the avoidance of hazards due to static electricity).

**Static Accumulator:** This material is a static accumulator. A liquid is typically considered a nonconductive, static accumulator if its conductivity is below 100 pS/m ( $100 \times 10^{-12}$  Siemens per meter) and is considered a semiconductive, static accumulator if its conductivity is below 10,000 pS/m. Whether a liquid is nonconductive or semiconductive, the precautions are the same. A number of factors, for example liquid temperature, presence of contaminants, anti-static additives and filtration can greatly influence the conductivity of a liquid.

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 6 of 14

## STORAGE

The type of container used to store the material may affect static accumulation and dissipation. Keep container closed. Handle containers with care. Open slowly in order to control possible pressure release. Store in a cool, well-ventilated area. Storage containers should be grounded and bonded. Fixed storage containers, transfer containers and associated equipment should be grounded and bonded to prevent accumulation of static charge. Keep away from incompatible materials.

## SECTION 8 EXPOSURE CONTROLS / PERSONAL PROTECTION

### EXPOSURE LIMIT VALUES

Exposure limits/standards (Note: Exposure limits are not additive)

Substance Name	Form	Limit / Standard			NOTE	Source
DIESEL OIL..C9-20	Stable Aerosol.	TWA	5 mg/m3		Skin	ExxonMobil
DIESEL OIL..C9-20	Vapor.	TWA	200 mg/m3		Skin	ExxonMobil
DIESEL OIL..C9-20 [total hydrocarb, vapor&aerosol]	Inhalable fraction and vapor	TWA	100 mg/m3		Skin	ACGIH
ETHYL BENZENE		TWA	435 mg/m3	100 ppm	N/A	OSHA Z1
ETHYL BENZENE		TWA	20 ppm		N/A	ACGIH
NAPHTHALENE		TWA	50 mg/m3	10 ppm	N/A	OSHA Z1
NAPHTHALENE		TWA	10 ppm		Skin	ACGIH

NOTE: Limits/standards shown for guidance only. Follow applicable regulations.

### Biological limits

Substance	Specimen	Sampling Time	Limit	Determinant	Source
ETHYL BENZENE	Creatinine in urine	End of shift	0.15 g/g	Sum of mandelic acid and phenylglyoxylic acid	ACGIH BELs (BEIs)
NAPHTHALENE	No Biological Specimen provided	End of shift	Not Assigned	1-Naphthol, with hydrolysis + 2-Naphthol, with hydrolysis	ACGIH BELs (BEIs)

## ENGINEERING CONTROLS

The level of protection and types of controls necessary will vary depending upon potential exposure conditions. Control measures to consider:

Use explosion-proof ventilation equipment to stay below exposure limits.

## PERSONAL PROTECTION

Personal protective equipment selections vary based on potential exposure conditions such as applications, handling practices, concentration and ventilation. Information on the selection of protective equipment for use

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 7 of 14

---

with this material, as provided below, is based upon intended, normal usage.

**Respiratory Protection:** If engineering controls do not maintain airborne contaminant concentrations at a level which is adequate to protect worker health, an approved respirator may be appropriate. Respirator selection, use, and maintenance must be in accordance with regulatory requirements, if applicable. Types of respirators to be considered for this material include:

Half-face filter respirator

For high airborne concentrations, use an approved supplied-air respirator, operated in positive pressure mode. Supplied air respirators with an escape bottle may be appropriate when oxygen levels are inadequate, gas/vapor warning properties are poor, or if air purifying filter capacity/rating may be exceeded.

**Hand Protection:** Any specific glove information provided is based on published literature and glove manufacturer data. Glove suitability and breakthrough time will differ depending on the specific use conditions. Contact the glove manufacturer for specific advice on glove selection and breakthrough times for your use conditions. Inspect and replace worn or damaged gloves. The types of gloves to be considered for this material include:

Chemical resistant gloves are recommended. If contact with forearms is likely wear gauntlet style gloves.

**Eye Protection:** If contact with material is likely, chemical goggles are recommended.

**Skin and Body Protection:** Any specific clothing information provided is based on published literature or manufacturer data. The types of clothing to be considered for this material include:

Chemical/oil resistant clothing is recommended.

**Specific Hygiene Measures:** Always observe good personal hygiene measures, such as washing after handling the material and before eating, drinking, and/or smoking. Routinely wash work clothing and protective equipment to remove contaminants. Discard contaminated clothing and footwear that cannot be cleaned. Practice good housekeeping.

## ENVIRONMENTAL CONTROLS

Comply with applicable environmental regulations limiting discharge to air, water and soil. Protect the environment by applying appropriate control measures to prevent or limit emissions.

## SECTION 9

## PHYSICAL AND CHEMICAL PROPERTIES

**Note:** Physical and chemical properties are provided for safety, health and environmental considerations only and may not fully represent product specifications. Contact the Supplier for additional information.

## GENERAL INFORMATION

**Physical State:** Liquid

**Color:** Clear (May Be Dyed)

**Odor:** Petroleum/Solvent

**Odor Threshold:** N/D

## IMPORTANT HEALTH, SAFETY, AND ENVIRONMENTAL INFORMATION

**Relative Density (at 15 °C):** 0.81 - 0.87

**Density (at 15 °C):** 810 kg/m<sup>3</sup> (6.76 lbs/gal, 0.81 kg/dm<sup>3</sup>) - 876 kg/m<sup>3</sup> (7.31 lbs/gal, 0.88 kg/dm<sup>3</sup>)

**Flammability (Solid, Gas):** N/A



Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 8 of 14

**Flash Point [Method]:** >38°C (100°F) [ASTM D-93]  
**Flammable Limits (Approximate volume % in air):** LEL: 0.6 UEL: 7.0  
**Autoignition Temperature:** >200°C (392°F)  
**Boiling Point / Range:** 145°C (293°F) - 370°C (698°F)  
**Decomposition Temperature:** N/D  
**Vapor Density (Air = 1):** > 2 at 101 kPa  
**Vapor Pressure:** 0.067 kPa (0.5 mm Hg) at 20 °C  
**Evaporation Rate (n-butyl acetate = 1):** N/D  
**pH:** N/A  
**Log Pow (n-Octanol/Water Partition Coefficient):** > 3.5  
**Solubility in Water:** Negligible  
**Viscosity:** 1.7 cSt (1.7 mm<sup>2</sup>/sec) at 40 °C - 4.1 cSt (4.1 mm<sup>2</sup>/sec) at 40 °C  
**Oxidizing Properties:** See Hazards Identification Section.

#### OTHER INFORMATION

**Freezing Point:** N/D  
**Melting Point:** N/A  
**Pour Point:** < -6°C (21°F)

### SECTION 10 STABILITY AND REACTIVITY

**REACTIVITY:** See sub-sections below.

**STABILITY:** Material is stable under normal conditions.

**CONDITIONS TO AVOID:** Avoid heat, sparks, open flames and other ignition sources.

**MATERIALS TO AVOID:** Halogens, Strong Acids, Strong Bases, Strong oxidizers

**HAZARDOUS DECOMPOSITION PRODUCTS:** Material does not decompose at ambient temperatures.

**POSSIBILITY OF HAZARDOUS REACTIONS:** Hazardous polymerization will not occur.

### SECTION 11 TOXICOLOGICAL INFORMATION

#### INFORMATION ON TOXICOLOGICAL EFFECTS

Hazard Class	Conclusion / Remarks
<b>Inhalation</b>	
Acute Toxicity (Rat) 4 hour(s) LC50 4100 mg/m <sup>3</sup> (Vapor and aerosol)	Moderately toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 403
Irritation: No end point data for material.	Elevated temperatures or mechanical action may form vapors, mist, or fumes which may be irritating to the eyes, nose, throat, or lungs.
<b>Ingestion</b>	
Acute Toxicity (Rat): LD50 > 5000 mg/kg	Minimally Toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 401
<b>Skin</b>	
Acute Toxicity (Rabbit): LD50 > 5000 mg/kg	Minimally Toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 434
Skin Corrosion/Irritation (Rabbit): Data	Irritating to the skin. Based on test data for structurally similar



Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 9 of 14

available.	materials. Test(s) equivalent or similar to OECD Guideline 404
<b>Eye</b>	
Serious Eye Damage/Irritation (Rabbit): Data available.	May cause mild, short-lasting discomfort to eyes. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 405
<b>Sensitization</b>	
Respiratory Sensitization: No end point data for material.	Not expected to be a respiratory sensitizer.
Skin Sensitization: Data available.	Not expected to be a skin sensitizer. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 406
<b>Aspiration:</b> Data available.	May be fatal if swallowed and enters airways. Based on physico-chemical properties of the material.
<b>Germ Cell Mutagenicity:</b> Data available.	Not expected to be a germ cell mutagen. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 471 475
<b>Carcinogenicity:</b> Data available.	Caused cancer in laboratory animals, but the relevance to humans is uncertain. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 451
<b>Reproductive Toxicity:</b> Data available.	Not expected to be a reproductive toxicant. Test(s) equivalent or similar to OECD Guideline 414
<b>Lactation:</b> No end point data for material.	Not expected to cause harm to breast-fed children.
<b>Specific Target Organ Toxicity (STOT)</b>	
Single Exposure: No end point data for material.	Not expected to cause organ damage from a single exposure.
Repeated Exposure: Data available.	Concentrated, prolonged or deliberate exposure may cause organ damage. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 410 413

## TOXICITY FOR SUBSTANCES

NAME	ACUTE TOXICITY
ETHYL BENZENE	Inhalation Lethality: 4 hour(s) LC50 17.8 mg/l (Vapor) (Rat); Oral Lethality: LD50 3.5 g/kg (Rat)
NAPHTHALENE	Inhalation Lethality: 4 hour(s) LC50 > 0.4 mg/l (Max attainable vapor conc.) (Rat); Oral Lethality: LD50 533 mg/kg (Mouse)

## OTHER INFORMATION

### For the product itself:

Target Organs Repeated Exposure: Bone marrow, Liver, Thymus

Vapor concentrations above recommended exposure levels are irritating to the eyes and the respiratory tract, may cause headaches and dizziness, are anesthetic and may have other central nervous system effects.

Small amounts of liquid aspirated into the lungs during ingestion or from vomiting may cause chemical pneumonitis or pulmonary edema.

Diesel fuel: Caused cancer in animal tests. Caused mutations in vitro. Repeated dermal exposures to high concentrations in test animals resulted in reduced litter size and litter weight, and increased fetal resorptions at maternally toxic doses. Dermal exposure to high concentrations resulted in severe skin irritation with weight loss and some mortality. Inhalation exposure to high concentrations resulted in respiratory tract irritation, lung changes/infiltration/accumulation, and reduction in lung function.

Diesel exhaust fumes: Carcinogenic in animal tests. Inhalation exposures to exhaust for 2 years in test animals resulted in lung tumors and lymphoma. Extract of particulate produced skin tumors in test animals. Caused mutations

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 10 of 14

in vitro.

**Contains:**

**NAPHTHALENE:** Exposure to high concentrations of naphthalene may cause destruction of red blood cells, anemia, and cataracts. Naphthalene caused cancer in laboratory animal studies, but the relevance of these findings to humans is uncertain.

**ETHYLBENZENE:** Caused cancer in laboratory animal studies. The relevance of these findings to humans is uncertain.

The following ingredients are cited on the lists below:

Chemical Name	CAS Number	List Citations
ETHYL BENZENE	100-41-4	5
NAPHTHALENE	91-20-3	2, 5

--REGULATORY LISTS SEARCHED--

1 = NTP CARC

2 = NTP SUS

3 = IARC 1

4 = IARC 2A

5 = IARC 2B

6 = OSHA CARC

**SECTION 12**

**ECOLOGICAL INFORMATION**

The information given is based on data for the material, components of the material, or for similar materials, through the application of bridging principals.

**ECOTOXICITY**

Material -- Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

**MOBILITY**

More volatile component -- Highly volatile, will partition rapidly to air. Not expected to partition to sediment and wastewater solids.

High molecular wt. component -- Low solubility and floats and is expected to migrate from water to the land. Expected to partition to sediment and wastewater solids.

**PERSISTENCE AND DEGRADABILITY**

**Biodegradation:**

Material -- Expected to be inherently biodegradable

**Atmospheric Oxidation:**

More volatile component -- Expected to degrade rapidly in air

**ECOLOGICAL DATA**

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 11 of 14

#### Ecotoxicity

Test	Duration	Organism Type	Test Results
Aquatic - Acute Toxicity	48 hour(s)	Daphnia magna	EL50 1 - 1000 mg/l: data for similar materials
Aquatic - Acute Toxicity	96 hour(s)	Fish	LL50 1 - 100 mg/l: data for similar materials
Aquatic - Acute Toxicity	72 hour(s)	Pseudokirchneriella subcapitata	EL50 1 - 100 mg/l: data for similar materials
Aquatic - Chronic Toxicity	72 hour(s)	Pseudokirchneriella subcapitata	NOELR 1 - 10 mg/l: data for similar materials

#### Persistence, Degradability and Bioaccumulation Potential

Media	Test Type	Duration	Test Results
Water	Ready Biodegradability	28 day(s)	Percent Degraded < 60 : similar material

### SECTION 13 DISPOSAL CONSIDERATIONS

Disposal recommendations based on material as supplied. Disposal must be in accordance with current applicable laws and regulations, and material characteristics at time of disposal.

#### DISPOSAL RECOMMENDATIONS

Product is suitable for burning in an enclosed controlled burner for fuel value or disposal by supervised incineration at very high temperatures to prevent formation of undesirable combustion products.

#### REGULATORY DISPOSAL INFORMATION

RCRA Information: Disposal of unused product may be subject to RCRA regulations (40 CFR 261). Disposal of the used product may also be regulated due to ignitability, corrosivity, reactivity or toxicity as determined by the Toxicity Characteristic Leaching Procedure (TCLP). Potential RCRA characteristics: IGNITABILITY.

**Empty Container Warning** Empty Container Warning (where applicable): Empty containers may contain residue and can be dangerous. Do not attempt to refill or clean containers without proper instructions. Empty drums should be completely drained and safely stored until appropriately reconditioned or disposed. Empty containers should be taken for recycling, recovery, or disposal through suitably qualified or licensed contractor and in accordance with governmental regulations. DO NOT PRESSURISE, CUT, WELD, BRAZE, SOLDER, DRILL, GRIND, OR EXPOSE SUCH CONTAINERS TO HEAT, FLAME, SPARKS, STATIC ELECTRICITY, OR OTHER SOURCES OF IGNITION. THEY MAY EXPLODE AND CAUSE INJURY OR DEATH.

### SECTION 14 TRANSPORT INFORMATION

#### LAND (DOT)

**Proper Shipping Name:** DIESEL FUEL  
**Hazard Class & Division:** COMBUSTIBLE LIQUID  
**ID Number:** NA1993  
**Packing Group:** III  
**Marine Pollutant:** Yes  
**ERG Number:** 128  
**Label(s):** NONE

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 12 of 14

---

**Transport Document Name:** NA1993, DIESEL FUEL, COMBUSTIBLE LIQUID, PG III, MARINE POLLUTANT

Footnote: The flash point of this material is greater than 100 F. Regulatory classification of this material varies. DOT: Flammable liquid or combustible liquid. OSHA: Combustible liquid. IATA/IMO: Flammable liquid. This material is not regulated under 49 CFR in a container of 119 gallon capacity or less when transported solely by land, as long as the material is not a hazardous waste, a marine pollutant, or specifically listed as a hazardous substance.

**LAND (TDG)**

**Proper Shipping Name:** GAS OIL

**Hazard Class & Division:** 3

**UN Number:** 1202

**Packing Group:** III

**Special Provisions:** 88, 150

**SEA (IMDG)**

**Proper Shipping Name:** GAS OIL

**Hazard Class & Division:** 3

**EMS Number:** F-E, S-E

**UN Number:** 1202

**Packing Group:** III

**Marine Pollutant:** Yes

**Label(s):** 3

**Transport Document Name:** UN1202, GAS OIL, 3, PG III, (>38°C c.c.), MARINE POLLUTANT

**AIR (IATA)**

**Proper Shipping Name:** GAS OIL

**Hazard Class & Division:** 3

**UN Number:** 1202

**Packing Group:** III

**Label(s) / Mark(s):** 3

**Transport Document Name:** UN1202, GAS OIL, 3, PG III

<b>SECTION 15</b>
-------------------

<b>REGULATORY INFORMATION</b>
-------------------------------

**OSHA HAZARD COMMUNICATION STANDARD:** This material is considered hazardous in accordance with OSHA HazCom 2012, 29 CFR 1910.1200.

**Listed or exempt from listing/notification on the following chemical inventories:** AICS, DSL, IECSC, KECI, PICCS, TSCA

**SARA 302:** No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302

**CERCLA:** This material is not subject to any special reporting under the requirements of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA). Contact local authorities to determine if other reporting requirements apply.

Product Name: NO. 2 DIESEL FUEL  
 Revision Date: 22 Oct 2019  
 Page 13 of 14

**SARA (311/312) REPORTABLE GHS HAZARD CLASSES:** Acute Toxicity (any route of exposure), Aspiration Hazard, Carcinogenicity, Flammable (gases, aerosols, liquids, or solids), Skin Corrosion or Irritation, Specific Target Organ toxicity (single or repeated exposure)

**SARA (313) TOXIC RELEASE INVENTORY:**

Chemical Name	CAS Number	Typical Value
ETHYL BENZENE	100-41-4	0.1 - 1%
NAPHTHALENE	91-20-3	0.1 - 1%

The following ingredients are cited on the lists below:

Chemical Name	CAS Number	List Citations
DIESEL OIL..C9-20	68334-30-5	1, 18
ETHYL BENZENE	100-41-4	1, 4, 10, 17, 19
NAPHTHALENE	91-20-3	1, 4, 10, 17, 19

--REGULATORY LISTS SEARCHED--

1 = ACGIH ALL	6 = TSCA 5a2	11 = CA P65 REPRO	16 = MN RTK
2 = ACGIH A1	7 = TSCA 5e	12 = CA RTK	17 = NJ RTK
3 = ACGIH A2	8 = TSCA 6	13 = IL RTK	18 = PA RTK
4 = OSHA Z	9 = TSCA 12b	14 = LA RTK	19 = RI RTK
5 = TSCA 4	10 = CA P65 CARC	15 = MI 293	

Code key: CARC=Carcinogen; REPRO=Reproductive

SECTION 16	OTHER INFORMATION
------------	-------------------



**WARNING:** Cancer and Reproductive Harm - [www.P65Warnings.ca.gov](http://www.P65Warnings.ca.gov). Chemicals known to the State of California to cause cancer, birth defects, or other reproductive harm are created by the combustion of this product.

This warning is given to comply with California Health and Safety Code 25249.6 and does not constitute an admission or a waiver of rights.

N/D = Not determined, N/A = Not applicable

**KEY TO THE H-CODES CONTAINED IN SECTION 3 OF THIS DOCUMENT (for information only):**

H225: Highly flammable liquid and vapor; Flammable Liquid, Cat 2  
 H226: Flammable liquid and vapor; Flammable Liquid, Cat 3  
 H302: Harmful if swallowed; Acute Tox Oral, Cat 4  
 H304: May be fatal if swallowed and enters airways; Aspiration, Cat 1  
 H315: Causes skin irritation; Skin Corr/Irritation, Cat 2  
 H332: Harmful if inhaled; Acute Tox Inh, Cat 4  
 H351: Suspected of causing cancer; GHS Carcinogenicity, Cat 2  
 H373: May cause damage to organs through prolonged or repeated exposure; Target Organ, Repeated, Cat 2  
 H400: Very toxic to aquatic life; Acute Env Tox, Cat 1  
 H401: Toxic to aquatic life; Acute Env Tox, Cat 2

Product Name: NO. 2 DIESEL FUEL

Revision Date: 22 Oct 2019

Page 14 of 14

---

H410: Very toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 1

H411: Toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 2

H412: Harmful to aquatic life with long lasting effects; Chronic Env Tox, Cat 3

**THIS SAFETY DATA SHEET CONTAINS THE FOLLOWING REVISIONS:**

Composition: Component Table information was modified.

Section 07: Handling and Storage - Handling information was modified.

Section 12: information was modified.

Section 14: Special Provisions information was added.

**THIS MSDS COVERS THE FOLLOWING MATERIALS:** DIESEL EFFICIENT | DIESEL NO. 2 | ESSO DIESEL FUEL | EXXON DIESEL FUEL | EXXON SYNERGY DIESEL EFFICIENT | LOW SULFUR DIESEL | MARINE DIESEL FUEL | MOBIL DIESEL EFFICIENT | MOBIL DIESEL FUEL | MOBIL SYNERGY DIESEL EFFICIENT | ULTRA LOW SULFUR DIESEL | WINTERIZED DIESEL FUEL

-----

The information and recommendations contained herein are, to the best of ExxonMobil's knowledge and belief, accurate and reliable as of the date issued. You can contact ExxonMobil to insure that this document is the most current available from ExxonMobil. The information and recommendations are offered for the user's consideration and examination. It is the user's responsibility to satisfy itself that the product is suitable for the intended use. If buyer repackages this product, it is the user's responsibility to insure proper health, safety and other necessary information is included with and/or on the container. Appropriate warnings and safe-handling procedures should be provided to handlers and users. Alteration of this document is strictly prohibited. Except to the extent required by law, republication or retransmission of this document, in whole or in part, is not permitted. The term, "ExxonMobil" is used for convenience, and may include any one or more of ExxonMobil Chemical Company, Exxon Mobil Corporation, or any affiliates in which they directly or indirectly hold any interest.

-----

Internal Use Only

MHC: 1A, 0B, 2, 0, 4, 1

PPEC: C

DGN: 7079307XUS (1012398)

-----

Copyright 2002 Exxon Mobil Corporation, All rights reserved



## Safety Data Sheet

### Gasoline

#### SECTION 1 IDENTIFICATION

**Product Name:** Gasoline

**Synonyms:** Unleaded Gasoline, Regular Gasoline, Motor Fuel, 85 Octane Gasoline, 87 Octane Gasoline

**SDS #:** F1

**Product Use:** Motor Fuel

**Restrictions on Use:** Use only as directed

**Manufacturer:**

Sinclair Oil Company  
P.O. Box 30825  
Salt Lake City, Utah 84130

**Telephone:**    **General Information:** (801) 524-2777    **Fax:** (801) 524-2740

**Contact person:** Jeremiah Webster

Emergency Telephone: 800-424-9300 (CHEMTREC) or (703) 527-3887

**SDS Date of Preparation:** January 23, 2015

#### SECTION 2: HAZARDS IDENTIFICATION

**Classification:**

Physical	Health
Flammable Liquid Category 2	Aspiration Toxicity Category 1 Skin Irritation Category 2 Specific Target Organ Toxicity Single Exposure Category 3 (Nervous System) Carcinogen Category 1A Germ Cell Mutagenicity Category 1B

**Label Elements:**

Danger!



**Hazard Phrases:**

Highly flammable liquid and vapor.  
May be fatal if swallowed and enters airways.  
Causes skin irritation.  
May cause drowsiness or dizziness.  
May cause cancer.  
May cause genetic defects.

**Precautionary Phrases:**

**Prevention**

Obtain special instructions before use.  
Do not handle until all safety precautions have been read and understood  
Keep away from heat, sparks, open flames, and hot surfaces. No smoking.  
Keep container tightly closed.  
Ground and bond container and receiving equipment  
Use explosion-proof electrical, ventilating and lighting equipment.  
Use only non-sparking tools.  
Take precautionary measures against static discharge.  
Avoid breathing vapors.  
Wash thoroughly after handling.  
Use only outdoors or in a well-ventilated area.  
Wear protective gloves, skin protection and eye protection.

#### Response

IF SWALLOWED: Immediately call a POISON CENTER or doctor.  
Do NOT induce vomiting.  
IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water.  
If skin irritation occurs: Get medical attention.  
Take off contaminated clothing and wash it before reuse.  
IF INHALED: Remove person to fresh air and keep comfortable for breathing.  
Call a POISON CENTER or doctor if you feel unwell.  
IF exposed or concerned: Get medical attention.  
In case of fire: Use water fog, carbon dioxide, dry chemical and foam to extinguish.

#### Storage and Disposal

Store in a well-ventilated place. Keep cool. Keep container tightly closed.  
Store locked up.  
Dispose of contents and container in accordance with local and national regulations.

### SECTION 3 COMPOSITION / INFORMATION ON INGREDIENTS

Chemical name	CAS No.	Concentration
Gasoline	8006-61-9	95-100%
Naphthalene	91-20-3	0-3%
Benzene	71-43-2	0-0.5%

### SECTION 4 EMERGENCY and FIRST AID PROCEDURES

**Eye Contact:** Immediately flush eyes with water for several minutes. Get medical attention if irritation persists.

**Skin Contact:** Remove contaminated clothing and flush skin with water for several minutes. Wash thoroughly with soap and water. Get medical attention if irritation develops or persists. Launder clothing before reuse. Discard contaminated shoes.

**Inhalation:** Remove to fresh air. If breathing is difficult have qualified personnel administer oxygen. If breathing has stopped, administer artificial respiration. Get medical attention.

**Ingestion:** Do not induce vomiting. Rinse mouth with water. Never give anything by mouth to an unconsciousness person. If vomiting occurs spontaneously, keep head below hips to prevent aspiration into the lungs. Get immediate medical attention.



**Most important symptoms/effects, acute and delayed:** May cause eye irritation. Causes skin irritation with redness and drying. Inhalation may cause respiratory irritation and central nervous system effects. Harmful or fatal if swallowed. Aspiration during swallowing or vomiting may cause lung damage. May cause cancer. May cause genetic defects.

**Indication of immediate medical attention and special treatment, if necessary:** Immediate medical attention is required for ingestion.

#### SECTION 5 FIRE and EXPLOSION HAZARD DATA

**Suitable extinguishing media:** Use water fog, foam, carbon dioxide, or dry chemical. Do not use a steady stream of water. Product may float on the surface of water and create a floating fire hazard.

**Specific hazards arising from the chemical:** This product is highly flammable and forms explosive mixtures with air. Vapors are heavier than air and will travel along surfaces to remote ignition sources and flash back. Closed containers may explode if exposed to extreme heat. Combustion may produce carbon oxides and other products of incomplete combustion.

**Special protective equipment and precautions for fire-fighters:** Firefighters should wear full emergency equipment and a NIOSH approved positive pressure self-contained breathing apparatus. Cool fire exposed container with water. Do not allow run-off from firefighting to enter drains or water courses.

#### SECTION 6 ACCIDENTAL RELEASE MEASURES

**Personal precautions, protective equipment, and emergency procedures:** Wear appropriate protective equipment. Eliminate ignition sources and ventilate the area with explosion proof equipment. Wash thoroughly after handling.

**Environmental hazards:** Avoid release into the environment. Report spill as required by local and federal regulations.

**Methods and materials for containment and cleaning up:** Contain with an inert absorbent and place into a closable container for disposal. Use non-sparking tools and equipment. If spill has not ignited, use water spray to disperse the vapors and protect personnel attempting to stop leak. Prevent entry in storm sewers and waterways. Runoff can cause a fire or explosion hazard in sewers.

#### SECTION 7 HANDLING and STORAGE

**Precautions for safe handling:** Avoid contact with eyes, skin and clothing. Avoid breathing vapors. Wash thoroughly after handling. Use only with adequate ventilation. Wash thoroughly with soap and water after handling. Keep containers closed when not in use. Keep product away from heat, sparks, flames and all other sources of ignition. Do not permit smoking in use or storage areas. Use with non-sparking tools and explosion proof equipment. Electrically bond and ground containers for transfer.

Do not cut, drill, grind or weld on or near containers, even empty containers. Empty containers retain product residues can be hazardous. Follow all SDS precautions when handling empty containers.

Improper filling of portable gasoline containers creates a fire hazard. Only dispense gasoline into an approved and properly labeled gasoline container. Always place portable containers on the ground while filling. Ensure pump nozzle is in contact with the container while filling. Do not use the nozzle's lock open device. Do not fill portable containers that are inside a vehicle or trailer/truck bed.

Do not use as a cleaner or solvent. Use only as a motor fuel. Do not siphon by mouth.

Refer to OSHA 1910.1028 for requirements for handling and use of benzene.

**Conditions for safe storage, including any incompatibilities:** S Store in accordance with regulations for the storage of flammable liquids. Store in a dry, well ventilated area away from heat, direct sunlight and all sources of ignition. Store away from oxidizers and other incompatible materials. Protect containers from physical damage.

## SECTION 8 EXPOSURE CONTROLS and PERSONAL PROTECTION

### Exposure Guidelines:

#### INGREDIENTS

Gasoline  
Naphthalene

Benzene

#### EXPOSURE LIMITS

300 ppm TWA , 500 ppm STEL ACGIH TLV  
10 ppm TWA OSHA PEL  
10 ppm, skin TWA ACGIH TLV  
1 ppm TWA, 5 ppm STEL OSHA PEL  
0.5 ppm TWA, 2.5 ppm STEL ACGIH TLV

29 CFR 1910.1028 is the OSHA regulation on Occupational Exposure to Benzene. Assure compliance with these regulations.

**Appropriate engineering controls:** Use with local exhaust ventilation to maintain exposures below the occupational exposure limits. Use explosion proof equipment where required

**Respiratory protection:** If exposures are exceeded, use a NIOSH approved organic vapor respirator appropriate for the form and concentration of the contaminants should be used. Selection of respiratory protection depends on the contaminant type, form and concentration. Select in accordance with OSHA 1910.134 and good Industrial Hygiene practice.

**Skin protection:** Impervious gloves such as viton recommended to prevent skin contact.

**Eye protection:** Wear chemical safety goggles to avoid eye contact.

**Other:** Impervious coveralls, apron and boots is required to prevent skin contact and contamination of personal clothing. A safety shower and eye wash should be available in the immediate work area.

## SECTION 9 PHYSICAL and CHEMICAL PROPERTIES

**Appearance (physical state, color, etc.):** Colored or clear liquid

**Odor:** Aromatic hydrocarbon odor.

<b>Odor threshold:</b> 0.3 ppm (gasoline)	<b>pH:</b> Not applicable
<b>Melting point/Pourpoint:</b> -76°F (-60°C)	<b>Boiling Point:</b> 230° F (110°C)
<b>Flash point:</b> -45°F (-42.8°C)	<b>Evaporation rate:</b> Not available
<b>Flammability (solid, gas):</b> Not applicable	
<b>Flammable limits: LEL:</b> 1.4%	<b>UEL:</b> 7.6%
<b>Vapor pressure:</b> 7-15 psia	<b>Vapor density:</b> >1
<b>Relative density:</b> 0.65-0.75	<b>Solubility:</b> Insoluble in water
<b>Partition coefficient: n-ctanol/water:</b> Not available	<b>Auto-ignition temperature:</b> >530°F (>276.6°C)
<b>Decomposition temperature:</b> Not available	<b>Viscosity:</b> Not applicable

## SECTION 10 STABILITY and REACTIVITY

**Reactivity:** This product is not expected to be reactive.

**Chemical stability:** The product is stable.

**Possibility of hazardous reactions:** None known.

**Conditions to avoid:** Keep away from heat and all sources of ignition.

**Incompatible materials:** Avoid oxidizing agents, acids, alkalies and halogens.

**Hazardous decomposition products:** Thermal decomposition may yield carbon oxides and other products of incomplete combustion.

## SECTION 11 TOXICOLOGICAL INFORMATION

### Health Hazards:

**Inhalation:** Vapors may cause respiratory irritation and central nervous system effect including headache, dizziness, headaches, giddiness, euphoria, vertigo, blurred vision, nausea, numbness, drowsiness, anesthesia, and coma. Gasoline vapors are heavier than air and may cause asphyxiation in enclosed or poorly ventilated area. Overexposure to benzene by inhalation may cause exhilaration, nervous excitation, and/or giddiness, followed by a period of depression, drowsiness, or fatigue, tightness of the chest, unconsciousness, tremors or death.

**Skin Contact:** Skin contact may cause irritation, redness and defatting of the skin.

**Eye Contact:** Eye contact may cause mild irritation with redness, tearing and pain.

**Ingestion:** Swallowing may cause gastrointestinal irritation, nausea, vomiting, diarrhea, vertigo, drowsiness, mental confusion, staggering gait, slurred speech, convulsions, unconsciousness and death due to circulatory failure. Aspiration during swallowing or vomiting may cause lung damage.

**Chronic Effects of Overexposure:** Prolonged occupational overexposure may cause dermatitis. Reports have associated repeated and prolonged overexposure to petroleum distillates with adverse liver, kidney and bone marrow effects and with permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the product may be harmful or fatal. Repetitive direct skin application of kerosene over a two year period resulted in skin cancer in laboratory animals. Petroleum hydrocarbons of similar composition and boiling ranges have been known to product kidney damage and tumors in male rats following prolonged inhalation exposures. Benzene has been shown to cause damage to the blood forming system with anemia, leukopenia and thrombocytopenia by all routes of exposure.

**Mutagenicity:** Benzene did not induce in vitro mutation in bacteria using standard AMES test conditions. Mammalian cell gene mutation tests carried out in various human, mouse and Chinese hamster cells resulted in mixed results. Benzene is an in vivo mutagen in mammals, especially when chromosomal aberrations and micronuclei are induced. It has been reported that benzene exposure in humans induces genotoxic effects in lymphocytes in vivo.

**Reproductive Toxicity:** In a reproductive study, rats were administered 250 and 1000 mg/kg of petroleum distillates for at least 70 days prior to mating and during the 14 day mating cycle. The absence of adverse effects on in-life parameters (such as body weight, feed consumption, and clinical observations), a dosage level of 1000 mg/kg/day was considered to be the no-observed-adverse-effect level (NOAEL) for reproductive and systemic toxicity.

**Carcinogenicity:** Gasoline is listed by IARC as "Possibly Carcinogenic to Humans", Group 2B and as a "Confirmed Animal Carcinogen with Unknown Relevance to Humans: A3 by ACGIH. Benzene is listed by IARC as "Carcinogenic to Humans" Group 1, by NTP as "Known to Be a Human Carcinogen" and as a "Confirmed Human Carcinogen", A1 by ACGIH. Naphthalene is listed by IARC as "Possibly Carcinogenic to Humans", Group 2B, as "Reasonably Anticipated to be a Human Carcinogen" and as a "Confirmed Animal Carcinogen with Unknown Relevance to Humans", A3 by ACGIH.

**Acute Toxicity Values: Acute Toxicity Estimate:** Oral 14492 mg/kg

Gasoline: Oral rat LD50 >5000 mg/kg, Inhalation rat LC50 >5.61 mg/L/4 hr, Dermal rabbit LD50 >2000 mg/kg

Naphthalene: Oral rat LD50 533 mg/kg, Inhalation rat LC0 0.4 mg/L (highest attainable concentration), Dermal rat LC50 >2500 mg/kg

Benzene: Oral rat LD50 >2000 mg/kg, Inhalation rat LC50 41.69 mg/L/4 hr, Dermal rabbit LD50 > 8260 mg/kg

## SECTION 12: ECOLOGICAL INFORMATION

**Ecotoxicity:**

Gasoline: 96 hr LL50 Pimephales promelas 8.2 mg/kg, 48 hr EL50 4.5 mg/L, 72 hr EL50 Pseudokirchnerella subcapitata 3.1 mg/L

Naphthalene: 96 hr LC50 Pimephales promelas 6.08 mg/L, 48 hr EC50 daphnia magna 2.16 mg/L

Benzene: 96 hr LC50 Oncorhynchus mykiss 5.3 mg/L, 48 hr EC50 daphnia magna 10 mg/L, 72 hr EC50

Pseudokirchnerella subcapitata 32 mg/L

**Persistence and degradability:** Gasoline is inherently biodegradable.

**Bioaccumulative potential:** The bioaccumulation potentials of the major components of gasoline range from low to high. Some higher molecular weight components may be taken up by fish and domestic animals and bioconcentrated if they persist in environment.

**Mobility in soil:** Gasoline is expected to possess low to moderate mobility in soil.

**Other adverse effects:** None known.

## SECTION 13: DISPOSAL INFORMATION

**Waste Disposal Method:** Dispose in accordance with all local, state and federal regulations.

## SECTION 14: TRANSPORTATION INFORMATION

	UN Number	Proper shipping name	Hazard Class	Packing Group	Environmental Hazard
DOT	UN1203	Gasoline	3	PG II	No
TDG	UN1203	Gasoline	3	PG II	No
IMDG	UN1203	Gasoline	3	PG II	No
IATA	UN1203	Gasoline	3	PG II	No

**Transport in bulk (according to Annex II of MARPOL 73/78 and the IBC Code):** Not applicable.

**Special precautions:** None known.

## SECTION 15: REGULATORY INFORMATION

**Safety, health, and environmental regulations specific for the product in question.**

**CERCLA Hazardous Substances (Section 103)/RQ:** This product has a Reportable Quantity (RQ) of 3,333 lbs. (based on the RQ for Naphthalene of 100 lbs). Releases above the RQ must be reported to the National Response Center. Many states have more stringent release reporting requirements. Report spills required under federal, state and local regulations.

**EPA SARA 311 Hazard Classification:** Acute Health, Chronic Health, Fire Hazard

**SARA 313:** This product contains the following chemicals subject to Annual Release Reporting Requirements Under SARA Title III, Section 313 (40 CFR 372):

Benzene	71-43-2	0-0.5%
Naphthalene	91-20-3	0-3%

**CALIFORNIA PROPOSITION 65:** This product contains chemicals known to the State of California to cause cancer or reproductive toxicity.

**WHMIS CLASSIFICATION:** Class B, Division 2 (Flammable Liquid), Class D, Division 2A (Very Toxic Material Causing Other Toxic Effects)

This product has been classified in accordance with the hazard criteria in the CPR and the MSDS contains all the information required by the CPR.

**Australia AICS:** All of the components are listed on the Australian Inventory of Chemical Substances.

**Canada DSL:** All of the components are listed on the Canadian Domestic Substances List.

**China:** All the components are listed on Inventory of Existing Chemical Substances in China.

**European EINECS:** All of the ingredients are listed on the EINECS inventory.

**Korea:** All the components are listed on the Korean Existing Chemical List.

**New Zealand:** All the components are listed on the New Zealand Inventory of Chemicals.

**Philippines:** All the components are listed on the Philippine Inventory of Chemical and Chemical Substances inventory.

**US EPA Toxic Substances Control Act:** All of the components of this product are listed on the TSCA inventory.


## SECTION 16: OTHER INFORMATION

**SDS Revision History:** Converted to GHS format – all Sections revised

**Date of current revision:** January 9, 2015

**Date of previous revision:** December 2002

National  
Fire  
Protection  
Association  
(U.S.A)



Health: 2\*  
Flammability : 3  
Instability: 0  
Specific Hazard:

Disclaimer: This product material safety data sheet provides health and safety information. The product should be used in applications consistent with this product literature. For any other uses, exposures should be evaluated so that appropriate handling practices and training programs can be established to ensure safe workplace operations.

This material safety data sheet is provided in good faith and meets the requirements of the hazardous communication provisions of SARA TITLE III and 29 CFR 1910.1200(g) of the OSHA regulations. The above information is based on review of available information Sinclair believes is reliable and is supplied for informational purposes only. Sinclair does not guarantee its completeness or accuracy. Since conditions of use are outside the control of Sinclair, Sinclair disclaims all warranties, express or implied, and any liability for damage or injury which results from the use of the above data. Nothing herein is intended to permit infringement of valid patents and licenses.

## **APPENDIX B – MARINE TRANSPORTATION SERVICES OIL SPILL RESPONSE PLAN**



# OIL SPILL RESPONSE PLAN

Marine Transportation Services

Hay River, NT

Syncro Yard & Terminal C



## TABLE OF CONTENTS

<b>1.0 INTRODUCTION AND SCOPE OF THE PLAN .....</b>	<b>3</b>
<b>2.0 SITE SPECIFICS AND SPILL RISKS.....</b>	<b>4</b>
<b>2.1 FACILITY DESCRIPTION – HAY RIVER, NT SYNCRO YARD.....</b>	<b>4</b>
<b>2.2 SPILL PATHWAYS &amp; AREAS OF SENSITIVITY.....</b>	<b>4</b>
<b>3.0 SPILL PREVENTION.....</b>	<b>5</b>
<b>3.1 INSPECTIONS .....</b>	<b>5</b>
<b>3.2 SPILL EQUIPMENT ON SITE.....</b>	<b>6</b>
<b>3.3 SAFE TRANSFER PROCEDURES.....</b>	<b>7</b>
<b>4.0 SPILL RESPONSE TEAM &amp; INITIAL RESPONSE.....</b>	<b>8</b>
<b>4.1 SPILL RESPONSE TEAM (SRT) – TIERS.....</b>	<b>8</b>
<b>4.2 THE ON-SCENE COMMANDER (OSC) – RESPONSIBILITIES AND TRAINING .....</b>	<b>9</b>
<b>4.3 INITIAL RESPONSE CHECKLIST .....</b>	<b>10</b>
<b>4.4 SAFETY .....</b>	<b>11</b>
<b>4.5 RESPONSE STRATEGIES .....</b>	<b>11</b>
<b>4.5.1 FUEL SPILL AT STORAGE TANK .....</b>	<b>11</b>
<b>4.5.2 FUEL SPILL AS A RESULT OF INCIDENT WITH FUEL TRUCK.....</b>	<b>12</b>
<b>4.5.3 FIRE AT A FUEL STORAGE TANK .....</b>	<b>12</b>
<b>5.0 CONTAINMENT TECHNIQUES, REMOVAL &amp; REPORTING.....</b>	<b>13</b>
<b>5.1 CONTAINMENT METHODS .....</b>	<b>13</b>
<b>5.2 REMOVAL TECHNIQUES .....</b>	<b>14</b>
<b>5.3 DOCUMENTATION.....</b>	<b>16</b>
<b>APPENDIX A: RESPONSE CONTACTS.....</b>	<b>17</b>
<b>APPENDIX B: REGISTERED TANKS .....</b>	<b>18</b>
<b>APPENDIX C: NT-NU SPILL REPORT .....</b>	<b>19</b>
<b>APPENDIX D: SDS SHEET, DIESEL .....</b>	<b>1</b>
<b>APPENDIX E: SDS SHEET, UNLEADED GASOLINE.....</b>	<b>8</b>
<b>APPENDIX F: MONTHLY FUEL TANK INSPECTION .....</b>	<b>16</b>





## 1.0 INTRODUCTION AND SCOPE OF THE PLAN

The purpose of this Oil Spill Response Plan is to outline the general steps to be taken to prevent fuel spills as well as steps to be taken in the event of a fuel spill to mitigate damage to the environment. Specific situations may require adapting the plan to fit the situation. The plan describes the roles and responsibilities of key organizations and personnel, as well as the procedures for responding to a spill while protecting the safety and health of the response team, the community, and the environment.

This Oil Spill Response Plan only applies to the equipment and property used by MTS in its operations, as well as any other environmental and animal pathways or recipients affected by a fuel spill as a result of MTS operations.

Employees will follow the spill procedures posted at the tanks; The QHSE Coordinator will activate the Oil Spill Response Plan and become the On-Scene Commander (OSC) for any oil spills that MTS may be responsible for.

**The Contractor is solely responsible for their employees. If a spill occurs due to inadequate employee awareness and training, bad housekeeping practices or tank overfills, it is the Contractor's responsibility to clean up that spill. MTS will be available to provide assistance however all costs associated with this type of spill is the responsibility of the Contractor. It is therefore imperative that the Contractor trains his staff in Oil Spill Prevention and Response, Workplace Hazardous Materials Information System (WHMIS), Transportation of Dangerous Goods (TDG), and First Aid.**

MTS will also:

- comply with existing regulations;
- protect the environment as much as possible;
- co-operate with other agencies that need help with fuel spills and any related environmental clean-up;
- anticipate future spill response equipment and personnel needs and prepare for them;
- keep employees, government officials and the public informed.

This Oil Spill Contingency Plan will be updated annually. Report changes as they arise to your Supervisor. (ANNEX A).



## 2.0 SITE SPECIFICS AND SPILL RISKS

### 2.1 FACILITY DESCRIPTION – Hay River, NT Syncro Yard

The MTS Syncro Yard is located in Hay River, NT. There are a total of 16 tanks located in the yard and 2 at Terminal C. [Appendix B: Registered Tanks](#) can be viewed.

#### Access (for delivery or spill response)

Access to the Syncro Yard is through main road transportation located at 1-104<sup>th</sup> Ave Hay River, NT. Terminal C can be accessed through the main highway (HWY 2) located at 42003 Mackenzie HWY, Hay River, NT. Both Facilities can be accessed by vehicle.

### 2.2 SPILL PATHWAYS & AREAS OF SENSITIVITY

The Syncro Yard is located at the mouth of the Great Slave Lake and the end of the Hay River. There is limited potential for spill into sensitive areas since all tanks are located in-land. Bulk fuel tanks are also in lined berms.

#### Syncro Yard:



A: Syncro Yard  
B: Hay River/Mouth of Great Slave Lake  
○: Tank Locations

#### Terminal C Yard:



A: Terminal C Yard  
B: Hay River  
○: Tank Locations



### 3.0 SPILL PREVENTION

Petroleum Products are one of the most important energy sources in the world. To successfully manage these energy resources, proper knowledge of spill prevention must be followed. This is completed visually, on a monthly basis through the use of MTS Inspections. Any abnormalities should be immediately reported to your supervisor. Spills can have a significant impact on the environment and they are very costly to clean up. The effects of an oil spill can still be found tens of years after the spill if not cleaned up properly.

Every drop of fuel spilled has an impact on the environment and is very costly. This is clearly demonstrated in the following table:

OIL LOSS BY DRIPS			
RATE	LITRES/YR	COST @ \$1.50/ Litre	CONTAMINATED SOIL (tons)
1 drop/10 seconds	151	\$225	150 tons
1 drop/5 seconds	302	\$350	300 tons
1 drop/second	1550	\$2,325	1500 tons

### 3.1 INSPECTIONS

MTS expects those responsible for the delivery of fuel and dispensing equipment to visually inspect the tank system on days when fuel system checks are required. Some things you should be checking are as follows:

- (i) Continuously check the fuel truck and hoses for leaks when delivering fuel.
- (ii) Visually inspect tank valves and pipe connections.
- (iii) Visually check the fuel pump system (if installed)
- (iv) Investigate any visual signs of fuel spillage on the ground.
- (v) Remove all snow around valves, flex connectors, and flange points.

The QHSE Coordinator must complete the Monthly Tank Inspection. Any abnormalities in the operational equipment or safety concerns will be reported.



## 3.2 SPILL EQUIPMENT ON SITE

All dispensing equipment fed by fuel oil tanks (2500L or larger) shall be equipped with a Spill Kit. The suggested contents of this Kit are listed in the chart below. If you use any of the contents in this kit, please report it to the Supervisor as soon as possible so they can arrange for replacement supplies. It is very important that the best condition of the spill kit is maintained to ensure the contents are ready for use, if necessary.

### SPILL KIT CONTENTS

Syncro yard & Terminal C	<b>On-Site 55 gal. Spill Response Kit</b>			
	High Performance Oil Sorbent Roll	1	Containment/Recovery	38" x 25'
	High Performance Oil Sorbent Pads	2 Bags	Containment/Recovery	17" x 19"
	Powersorb Oil Sorbent Minibooms	6	Containment	2" x 48"
	Powersorb Oil Sorbent Minibooms	1	Containment	3" x 10'
	Saranex-coated Tyvek Coveralls	4	Safety	Disposable
	Pr. PVC Gloves	4	Safety	
	Pr. Splash Goggles	4	Safety	
	Polyethylene Disposable Bags	6	Storage	6 ml. Thickness, 44" x 30"
	Spill Report Forms	1 booklet	Paperwork	Kept in plastic bag inside drum
	55 gal. D.O.T. approved Salvage Drum	1	Storage	c/w Screw-on Top (Polyethylene)

### Mobile Equipment

#### Pump truck #3253



One of the four pump trucks that is available to be used in the event of an emergency spill. Each tank capacity is approximately 8,000 liters.



## Spill Response Containers

Syncro Container # 20262	Terminal C Container # 260413
4 Sections – 50' Bennett River Boom	13 Bundles 38" x 18" x 18" Matasorb
1 Boom Connector Slings	4 3/8" x 38" x 144" Sorbent Rolls
2 50' Hand Lines	4 Oil Snares
2 12" Maker Buoy	2 Boxes Petro Mesh
1 5' x 4" Kamlock 'Manta Ray' Skimmer Head	1 8" x 10" x 40' Sorbent Boom
1 4" x 25' Suction Hose	1 Anchor
1 4" x 50' P.V.C. Hose	6 PFD's
40 Loose – 8" x 10' Sorbent Booms	2 Plug & Dyke
4 Bag – 8" x 10' x 4' Sorbent Booms	1 Long Handled Forks
1 Bag – 3/8" x 38" x 144' Sorbent Roll	1 Short Handled Forks
1 Bags – 18" x 18" 'Matasorb' Sorbent Pads	1 Tool Box (MT)
1 Bag – 18" x 18" 'Econo Sore' Sorbent Pad	1 12" Marker Buoy
7 Boxes – Viscous Oil Sorbent	1 10" Marker Buoy
1 10 lb. ABC Fire Extinguisher	1 Boom Anchor Buoys
	1 Sweds Saw
	1 10 lbs. Fire Extinguisher

## 3.3 SAFE TRANSFER PROCEDURES

It is very important that everyone transferring fuel follow Safe Transfer Procedures.

The Government of the Northwest Territories (GNWT) is committed to providing safe and environmentally sound procedures for bulk product transfers at all of our facilities. The following steps should be taken by all employees involved in the transfer of fuels within the GNWT facility.

### Safety Notes:

- All employees should review and have readily available, the site spill contingency plan and be familiar with its contents.
- Workers shall wear personal protective equipment (PPE) as necessary to protect themselves from any hazards involved. Be sure you have a supply of PPE on hand prior to commencing operations. Please refer to Material Safety Data Sheets (MSDS) located in Appendix D and E.
- Workers must remain on site throughout the transfer process and know how to immediately shut down the transfer in the event of a system failure, fire, or leak. If an immediate shut down is required, the employee shall stop the transfer process and shut




- off the transfer valve. The employee must remain on site to maintain control of the situation, unless deemed unsafe to do so (e.g. fire).
- Workers should inspect emergency equipment prior to any re-supply/transfer operation. Fire extinguishers and spill kits should be inspected regularly and be readily accessible (clear away snow and ice). Any problems with emergency equipment should be reported to your Supervisor.
  - Fill caps shall be locked at all times except during the transfer process.

## 4.0 SPILL RESPONSE TEAM & INITIAL RESPONSE

The Spill observer notifies the QHSE Coordinator immediately. The QHSE Coordinator initiates the Oil Spill Response Plan. Safe and efficient management of an oil spill will prevent it from causing major damage to the environment and/or human inhabitation. Remember, if you leave an oil spill on the ground, it may seep deep into the ground causing a large area of contamination. Also, it is possible for an oil spill to seep down into the water table.

### 4.1 SPILL RESPONSE TEAM (SRT) – TIERS

The SRT is made up of responders and contractors. These people implement the response activities under the management of the local Spill Authority. **In the case of a fuel delivery spill that occurs when no local Spill Authority is present, the Fuel Delivery Contractor (Tier 1) will act as the On-Scene Commander (OSC) until the Infrastructure Representative or Spill Authority (Tier 2) arrives on site.** The Fuel Delivery Contractor will then hand over the duty of OSC to the person of authority.







## 4.2 THE ON-SCENE COMMANDER (OSC) – RESPONSIBILITIES AND TRAINING

The On-Scene Commander (OSC) is initially the most senior representative from the lead agency present at the time of the spill. This person is trained in Basic Oil Spill Response and is typically the QHSE Coordinator.

The responsibilities of the OSC begin before a spill has occurred. Personnel who may have to act as the OSC should be familiar with the operation of the facility; the various actions that need to be taken in the event of an incident; the potential resources, both human and equipment, that will be available; and the potential hazards and concerns that will need to be considered while dealing with the spill (location of drinking water sources, environmentally sensitive areas, etc.)

**The OSC's first priority is always the safety of the workers and the general public. No emergency is considered so important that any worker should be asked to risk their own safety.**

The OSC is directly responsible for:

- Identifying any risks involved with clean-up and related operations.
- Providing protective clothing and equipment to reduce any potential health or safety risks to personnel involved with spill clean-up.
- Evaluating and correcting any unsafe operations or work practices before an incident occurs (e.g. not wearing proper Personal Protection Equipment).
- Will take measures to protect environmental sensitive areas (outlined in Section 2.2), if required.

NOTE: WHEN AN MTS EMPLOYEE ARRIVES ON SITE, THAT PERSON WILL BECOME THE ON-SCENE-COMMANDER (OSC). THE INITIAL OSC WILL TRANSFER DUTIES TO THAT EMPLOYEE BUT WILL REMAIN ON SITE TO PROVIDE ASSISTANCE AS NECESSARY.

### RESPONSE ORGANIZATION TRAINING

#### Tier 3

Fuel Dispensing and Delivery Contractors are trained in Basic Spill Prevention and Response at the start of contract. This may be a good resource in some areas.

The fuel delivery contractor must provide Basic Oil Spill training to their fuel delivery employees. The contractor must keep all training records on file.



The contractor must also provide training to employees in Workplace Hazardous Materials Information System (WHMIS) and Transportation of Dangerous Goods (TDG).

### **Tier 2**

A MTS supervisor may have to become the OSC and as such they should seek training in Basic Spill Response. For larger spills The Canadian Coast Guard (CCG) may be an additional resource in some areas. MTS Spill Response Team are trained in Basic Spill Prevention and Response, Standard First Aid & CPR, TDG and WHMIS.

Should a spill require contracted assistance by a 3<sup>rd</sup> party, OSC would initiate as such.

## **4.3 INITIAL RESPONSE CHECKLIST**

### **Immediately:**

- Stop flow of product
- EVALUATE FIRE AND SAFETY HAZARD, EVACUATE/SECURE AREA IF NECESSARY
- TEND TO THE INJURED
- SHUT OFF ALL POTENTIAL SOURCES OF IGNITION, DO NOT SMOKE
- IN THE EVENT OF AN EMERGENCY, CALL 911
- MOVE VEHICLES ONLY IN THE CASE OF FIRE, AND IF SAFE TO DO SO

### **Following:**

- CONTAIN THE SPILL - BEGIN IMMEDIATELY
- BLOCK OFF DRAINS, CULVERTS, DIKES AND DITCHES
- SURROUND SPILL USING BOOMS, STRAW BALES, PEAT MOSS,
- ABSORBENT MATERIAL, SAND, GRAVEL, EARTH, AND SNOW

### **Report and Clean Up:**

- NOTIFY SUPERVISOR AND GIVE THE FOLLOWING INFORMATION:
  1. SOURCE OF SPILL/PRODUCT
  2. APPROXIMATE AMOUNT
  3. LOCATION AND MOVEMENT OF SPILL
  4. ACTION TAKEN
- CLEAN UP - BEGIN IMMEDIATELY
- COMMENCE RECOVERY, CLEAN UP, RESTORATION





- REPORT THE SPILL TO THE GNWT 24 HOUR SPILL REPORT HOTLINE (867) 920-8130  
CALL COLLECT

## 4.4 SAFETY

**PPE** (Personal Protective Equipment) – Before attempting to clean up any type of petroleum product spill, you must be wearing your PPE. PPE must include Tyvek coveralls, plastic gloves, safety goggles, and leak proof boots.

**SDS** – Review the Safety Data Sheets (SDS) (Appendix D & E). Be sure you familiarize yourself with the hazards associated with each product you are working with.

**Certification** - Supervisors must ensure all potential response staff is certified in Transportation of Dangerous Goods (TDG) and Workplace Hazardous Materials Information System (WHMIS). This training can be completed online for a small fee. Additionally, fuel truck operators must have a valid NWT Driver's License of the appropriate class.

## 4.5 RESPONSE STRATEGIES

This section lists the actions to take for various spill scenarios that may result from daily operations. In most cases, it is assumed that the contractor will be on the site, and therefore will be responsible for any initial action. Subsequent actions will depend upon the location of the spill, the size of the spill, and the potential danger to people, the community as a whole, the environment, and any wildlife in the area.

The below procedures assume the minimum spill is 1m<sup>3</sup>, or 1,000L, and have been developed accordingly. However, MTS will still respond to any size of spill, as required. The below procedures can be adapted where necessary to suit smaller spills.

In all instances, the ultimate success of any action will be more assured personnel remain calm and assertive prior to taking action. The main priority is ensuring public safety and maintaining control of the spill.

### 4.5.1 Fuel Spill at Storage Tank

The first priority is always dealing with any injured personnel.



Next, if safe to do so:

- Close off all valves immediately after identifying a spill. No operations will be restarted if they interfere with spill response, clean-up, or disposal.
- All initial response actions will be completed according to the **Initial Response Checklist** laid out in **Section 4.3**.
- Using the contents of the spill kit (Section 3.2), contain the spilled fuel as best possible. Various containment strategies are illustrated in **Section 5.0**. The OSC will already be familiar with these techniques.

#### 4.5.2 Fuel Spill as a Result of Incident with Fuel Truck

- The priority is dealing with any injuries to personnel involved in the incident. Personnel on scene must follow the **Initial Response Checklist** laid out in **Section 4.3**. The fuel contractor must already be familiar with the necessary procedures.
- Make sure that the truck's engine has been turned off and there is no danger of a spark that may cause a fire.
- Put markers on the road to warn the public of the incident.
- Using the contents of the spill kit (Section 3.2), contain the spilled fuel as best possible.

#### 4.5.3 Fire at a Fuel Storage Tank

Fire extinguishers are located throughout all GNWT buildings

Find out what started the fire and shut off source if it is possible and safe to do so.

- If the fire is still small, attempt to put the fire out using the **PASS** method:

**P**ull the pin;

**A**im the nozzle at the base of the flames;

**S**queeze the trigger; and

**S**weep the nozzle from side to side to extinguish the fire.

- Never turn your back on a fuel fire, as flammable fumes may re-ignite. Back away slowly when you are confident that the fire has been extinguished.
- If the fire is too big for a fire extinguisher alone, leave the area immediately and notify the public. Call the local Fire Department and then your Supervisor.
- In the event of a catastrophic tank failure, evacuation of the facility is a real possibility.
- The possibility of an explosion is a serious threat.



## 5.0 CONTAINMENT TECHNIQUES, REMOVAL & REPORTING

### 5.1 CONTAINMENT METHODS

#### ➤ **Containment of Spills on Land**

Spills on land include spills on rock, gravel, and soil. Soil is a natural sorbent so it will soak up the spilled fuel. It is very important to keep land spills away from any water bodies.

**Absorbents:** If the spill is small, you can use enough absorbent pads to soak up the fuel.

**Dykes:** Dykes can be created using soil surrounding a spill on land. Dykes are constructed down slope and around the entire area of the spill.



**Trenches:** Trenches can be dug out to contain spills as long as the top layer of soil is not frozen. Shovels, axes or a loader can be used, depending on how big the spill is. A trench should be dug down to the bedrock or permafrost so it can be sucked up later by a pump or by using sorbents.

#### ➤ **Containment of Spills on Ice**

Spills on ice are the easiest spills to contain because ice does not soak up the fuel. For small spills, sorbent materials are used to soak up fuel. The contaminated ice can then be scraped up and shoveled into a plastic bag or barrel. However, if a spill occurs on ice that is on top of water it can be very dangerous. If the fuel manages to find its way into cracks in the ice, it will affect the water underneath.

**Dykes:** Dykes can be used to contain fuel spills on ice. Collect new snow, compact it and mound it to form a dyke down slope from the spill. The collected fuel can then be pumped into barrels or collected with sorbents.


**Flooding,** with trenches or sumps to collect oil that is floating, can be used with vacuum systems to recover the oil may be an option.



**Earth or snow dams** constructed across ditches may be used to contain a spill and stop its flow. A dam may be built with earth, wood, sandbags, or snow. The dam should be lined with plastic sheeting to make it impermeable to the oil. In the winter, water may be sprayed on snow dams to form ice to make it impermeable.

**Blocked Culvert** - Care should be taken to ensure the dam is large enough to contain the entire spill; insufficient capacity may result in overtopping failure. For ditches with flowing water or for small streams, it may be necessary to allow water flow to continue and to retain the lighter-than-water liquids.

**Burning** - Under no circumstances should ANYONE attempt to burn spilled oil/gas. A permit must first be obtained from the necessary government agencies – this type of burning would only be completed when PPD, RWED or ENR is on site with a valid permit for burning. Burning is most likely to be successful in winter conditions when the spill can be contained in a cone made of the contaminated snow and other debris.



## 5.2 REMOVAL TECHNIQUES

Excessive removal of soil is often a concern, as natural replacement and re-vegetation rates can be slow in many areas. Clean fill should be used to replace any contaminated soil that is removed.

Treatment or cleanup activities should be planned to avoid mixing clean and contaminated soils. In particular, mixing oil into clean subsurface soils should be avoided.



Avoid tracking oil into clean areas. Vehicles and personnel should always work from a clean area toward a contaminated area to avoid cross-contamination.

During manual treatment, avoid over-filling collection bags or containers to minimize spillage and to prevent bags or containers from breaking.

Contaminated fuel/oil/soil will be disposed of at a registered receiving facility.

- **Manual removal** may include scraping or wiping with sorbent materials. Workers must wear PPE that includes splash suits (Tyvek Coveralls) or rain gear, boots, and gloves. Contaminated materials can be placed directly in plastic bags, drums, or other containers for transfer. If the containers are to be carried to a temporary storage area, they should not weigh more than what can be carried by one person easily and safely. To avoid spillage, containers should not be overfilled or dragged.

Sorbent materials are placed along the perimeter to collect oil as it spreads laterally (protection mode) or in the contaminated area after the spill has stopped spreading (cleanup mode). Commercially available sorbents can be supplied as pads, rugs, blankets, rolls, sweeps, pillows or booms. Locally available materials may be appropriate on occasion (e.g. straw or peat) but usually such natural products are less effective and efficient than commercial sorbents.

- **Vacuum systems** are used primarily where oil is pooled in natural depressions and hollows, or where it has been herded into collection areas such as lined pits or trenches (sumps). This technique can be used in combination with flooding or washing techniques to float and collect oil. A dual-head wash and vacuum system can be used in locations that are difficult to access, such as between boulders.
- **Mechanical removal** can involve a range of devices to remove oil and contaminated surface and subsurface materials. Mechanical removal is more rapid than manual removal but generates larger quantities of waste. The method of operation varies considerably depending on the type of equipment that is available and its ability to operate on the land in question. Some equipment (e.g. elevating scrapers, loaders, backhoes or vacuum trucks) can remove and transfer material directly to a truck or temporary storage area in a single step. Other equipment (graders and bulldozers) are less efficient and require two steps or more to move or side cast material that must then be picked up by other types of equipment (scrapers, loaders or backhoes) for transfer.



- **Vegetation cutting** is a labor-intensive technique used in marshes or on attached plants, such as long grass. It is applicable only where the continued presence of oil may pose a contact threat to animals and birds that use the area, or where mobile oil or oiled plants could be released to impact adjacent healthy organisms. If oiled stems are cut, avoid disturbance of the root systems as this will delay recovery of the plants.

### 5.3 Documentation

Development		
Name	Position	Date
Prepared by: T. Townsend	QHSE Coordinator	Jan. 20, 2021
Reviewed by: S. Hagerman	Director MTS	
Approved by: S. Hagerman	Director MTS	

Revision History					
#	Revised Sections	Description of Revisions	Revised by (name, position)	Approved by (name, position)	Issue Date
01		NEW Oil Spill Response Plan			
02					
03					
04					
05					
06					





## APPENDIX A: RESPONSE CONTACTS

*The QHSE Coordinator Initiates the Oil Spill Response Plan.*

*Emergency services can be reached at **911** or local phone number.*

Organization	Contact	Phone#	Address/Location	Training
MTS	Tyler Townend, QHSE Coordinator	867 874 5120 867 876 0166	1-104 <sup>th</sup> Ave Hay River, NT	OSC WHMIS EMOST TDG
MTS	Tom Maher, Manager, Marine Operations, DPA/CSO	867 874 5106 867 875 8373	1-104 <sup>th</sup> Ave Hay River, NT	DPA CSO
MTS	Seth Barnaby, Shipyard Manager	867 874 5112 867 875 7839		EMOST WHMIS
Midnight Petroleum	Fuel Delivery Contact	867 874 2201	Hay River, NT	
Canadian Coast Guard		867 874 5559 780 841 8974	Hay River, NT	
Local ENR	Albert Bourque	867 875 5571	Hay River, NT	
Environmental Protection		867 669 4730 867 445 5145	Yellowknife, NT	
Fisheries & Oceans				
Transport Canada	CANUTEC	613 996 6666		
<b>RCMP</b>		<b>1 867 874 1111</b>	<b>Hay River, NT</b>	
<b>Fire Department</b>		<b>1 867 874 2222</b>	<b>Hay River, NT</b>	
<b>Ambulance</b>		<b>1 867 874 9333</b>	<b>Hay River, NT</b>	



## APPENDIX B: REGISTERED TANKS

EC#	ID #	Location	Description	Capacity	Material	Double or single wall	Secondary Containment	Product
00055272	4718	Syncro	Syncro Waste Fuel	147,931 L	Steel	Single	Yes	Waste Fuel
00055273	4721	Syncro	Tank Farm Used Oil	147,931 L	Steel	Single	Yes	Used Oil
00055275	4734	Syncro	Tank Farm Used Oil	64,379 L	Steel	Single	Yes	Used Oil
00055274	4736	Syncro	Tank Farm Used Oil	64,379 L	Steel	Single	Yes	Used Oil
00055228	6855	Syncro	Syncro Diesel tank stand	2,900 L	Steel	Single	No	Diesel
00055231	#1	Syncro	Syncro Tank Farm	64,002 L	Steel	Single	Yes	Waste Fuel
00055232	#2	Syncro	Syncro Tank Farm	64,002 L	Steel	Single	Yes	Waste Fuel
00055234	#3	Syncro	Syncro Tank Farm	64,002 L	Steel	Single	Yes	Waste Fuel
00055235	#4	Syncro	Syncro Tank Farm	64,002 L	Steel	Single	Yes	Waste Fuel
00055236	#5	Syncro	Syncro Tank Farm	63,780 L	Steel	Single	Yes	Diesel
00055237	#6	Syncro	Syncro Tank Farm	42,038 L	Steel	Single	Yes	Waste Fuel
00055238	#7	Syncro	Syncro Tank Farm	63,780 L	Steel	Single	Yes	Gas
00055223		Terminal C	Terminal C Diesel Tank	2,400 L	Steel	Double	No	Diesel
00055223		Terminal C	Terminal C Diesel Tank	4,500 L	Steel	Double	No	Diesel
00055243		Syncro	Company Gas Tank	15,532 L	Steel	Single	Yes	Gas
00055279		Syncro	Garage Waste Oil Tank 1	22,031 L	Steel	Single	Yes	Waste Fuel
00055279		Syncro	Garage Waste Oil Tank 2	1,135 L	Steel	Single	Yes	Waste Fuel
00055278		Syncro	Garage Diesel Tank	4,530 L	Steel	Double	No	Diesel





## APPENDIX C: NT-NU SPILL REPORT

### NT-NU SPILL REPORT

OIL, GASOLINE, CHEMICALS AND  
OTHER HAZARDOUS MATERIALS



NT-NU 24-HOUR SPILL REPORT LINE

Tel: (867) 920-8130 • Fax: (867) 873-6924 • Email: [spills@gov.nt.ca](mailto:spills@gov.nt.ca)

REPORT LINE USE ONLY

A	Report Date: MM   DD   YY	Report Time:	<input type="checkbox"/> Original Spill Report OR <input type="checkbox"/> Update # _____ to the Original Spill Report		Report Number:
B	Occurrence Date: MM   DD   YY	Occurrence Time:			
C	Land Use Permit Number (if applicable):		Water Licence Number (if applicable):		
D	Geographic Place Name or Distance and Direction from the Named Location:			Region: <input type="checkbox"/> NT <input type="checkbox"/> Nunavut <input type="checkbox"/> Adjacent Jurisdiction or Ocean	
E	Latitude: _____ Degrees _____ Minutes _____ Seconds		Longitude: _____ Degree _____ Minutes _____ Seconds		
F	Responsible Party or Vessel Name:		Responsible Party Address or Office Location:		
G	Any Contractor Involved:		Contractor Address or Office Location:		
H	Product Spilled: <input type="checkbox"/> Potential Spill	Quantity in Litres, Kilograms or Cubic Metres:		U.N. Number:	
I	Spill Source:		Spill Cause:		Area of Contamination in Square Metres:
J	Factors Affecting Spill or Recovery:		Describe Any Assistance Required:		Hazards to Persons, Property or Environment:
K	Additional Information, Comments, Actions Proposed or Taken to Contain, Recover or Dispose of Spilled Product and Contaminated Materials:				
L	Reported to Spill Line by:	Position:	Employer:	Location Calling From:	Telephone:
M	Any Alternate Contact:	Position:	Employer:	Alternate Contact Location:	Alternate Telephone:

REPORT LINE USE ONLY

N	Received at Spill Line by:	Position:	Employer:	Location Called:	Report Line Number:
Lead Agency: <input type="checkbox"/> EC <input type="checkbox"/> CCGT/CMSS <input type="checkbox"/> GNWT <input type="checkbox"/> GN <input type="checkbox"/> ILA <input type="checkbox"/> AANDC <input type="checkbox"/> NEB <input type="checkbox"/> Other: _____			Significance: <input type="checkbox"/> Minor <input type="checkbox"/> Major <input type="checkbox"/> Unknown		File Status: <input type="checkbox"/> Open <input type="checkbox"/> Closed
Agency:		Contact Name:	Contact Time:	Remarks:	
Lead Agency:					
First Support Agency:					
Second Support Agency:					
Third Support Agency:					



## APPENDIX D: SDS SHEET, DIESEL



Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 1 of 13

### SAFETY DATA SHEET

#### SECTION 1 IDENTIFICATION

##### PRODUCT

Product Name: (see Section 16 for Synonyms) DIESEL/BIODIESEL BLEND  
Product Description: Hydrocarbons and Additives  
SDS Number: 20463

Intended Use: Diesel engine fuel

##### COMPANY IDENTIFICATION

Supplier: Imperial Oil Downstream  
P.O. Box 2480, Station M  
Calgary, ALBERTA T2P 3M9 Canada

24 Hour Emergency Telephone 1-888-232-9563  
Transportation Emergency Phone Number 1-888-232-9563  
Product Technical Information 1-800-268-3183  
Supplier General Contact 1-800-567-3778

#### SECTION 2 HAZARD IDENTIFICATION

This material is considered to be hazardous according to regulatory guidelines.

This product has been classified in accordance with hazard criteria of the Hazardous Products Regulations (HPR) SOR/2015-17 and the SDS contains all the information required by the HPR SOR/2015-17.

##### CLASSIFICATION:

Flammable Liquids — Category 3  
Acute Toxicity (Inhalation) — Category 4  
Skin Irritation — Category 2  
Carcinogenicity — Category 2  
Specific Target Organ Toxicity — Repeated Exposure — Category 2  
Aspiration Hazard — Category 1

##### LABEL:

Pictogram:



Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 2 of 13



Signal Word: Danger

##### Hazard Statements:

H226: Flammable liquid and vapour. H304: May be fatal if swallowed and enters airways. H315: Causes skin irritation. H332: Harmful if inhaled. H351: Suspected of causing cancer. H373: May cause damage to organs through prolonged or repeated exposure. Bone marrow, Liver, Thymus

##### Precautionary Statements:

P101: If medical advice is needed, have product container or label at hand. P102: Keep out of reach of children. P103: Read label before use. P201: Obtain special instructions before use. P202: Do not handle until all safety precautions have been read and understood. P210: Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. P233: Keep container tightly closed. P240: Ground and bond container and receiving equipment. P241: Use explosion-proof electrical, ventilating and lighting equipment. P242: Use non-sparking tools. P243: Take action to prevent static discharges. P260: Do not breathe mist / vapours. P264: Wash skin thoroughly after handling. P271: Use only outdoors or in a well-ventilated area. P273: Avoid release to the environment. P280: Wear protective gloves/protective clothing/eye protection/face protection. P301 + P310: IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician. P302 + P352: IF ON SKIN: Wash with plenty of soap and water. P303 + P361 + P353: IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. P304 + P340: IF INHALED: Remove person to fresh air and keep comfortable for breathing. P308 + P313: IF exposed or concerned: Get medical advice/attention. P312: Call a POISON CENTER or doctor/physician if you feel unwell. P331: Do NOT induce vomiting. P332 + P313: If skin irritation occurs: Get medical advice/attention. P362 + P364: Take off contaminated clothing and wash it before reuse. P370 + P378: In case of fire: Use water fog, foam, dry chemical or carbon dioxide (CO2) to extinguish. P391: Collect spillage. P403 + P235: Store in a well-ventilated place. Keep cool. P405: Store locked up. P501: Dispose of contents and container in accordance with local regulations.

Contains: Fuel oil, No 2; naphthalene

##### Other hazard information:

Health Hazards Not Otherwise Classified: None as defined under HPR SOR/2015-17.

Physical Hazards Not Otherwise Classified: None as defined under HPR SOR/2015-17.

##### PHYSICAL / CHEMICAL HAZARDS

Material can accumulate static charges which may cause an ignition. Material can release vapours that readily form flammable mixtures. Vapour accumulation could flash and/or explode if ignited.

##### HEALTH HAZARDS

High-pressure injection under skin may cause serious damage. Under conditions of poor personal hygiene





Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 3 of 13

and prolonged repeated contact, some polycyclic aromatic compounds (PACs) have been suspected as a cause of skin cancer in humans. May be irritating to the eyes, nose, throat, and lungs. Repeated exposure may cause skin dryness or cracking.

#### ENVIRONMENTAL HAZARDS

Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

NFPA Hazard ID: Health: 2 Flammability: 2 Reactivity: 0  
HMIS Hazard ID: Health: 2\* Flammability: 2 Reactivity: 0

**NOTE:** This material should not be used for any other purpose than the intended use in Section 1 without expert advice. Health studies have shown that chemical exposure may cause potential human health risks which may vary from person to person.

### SECTION 3 COMPOSITION / INFORMATION ON INGREDIENTS

This material is defined as a mixture.

Hazardous Substance(s) or Complex Substance(s) in Hazardous product

Name	CAS#	Concentration*	GHS Hazard Codes
Fuel oil, No 2	68476-30-2	< 66%	H226, H304, H332, H351, H315, H373, H401, H411

#### Hazardous Constituent(s) Contained in Complex Substance(s)

Name	CAS#	Concentration*	GHS Hazard Codes
naphthalene	91-20-3	< 1.0%	H228(2), H302, H351, H400(M factor 1), H410(M factor 1)

\* All concentrations are percent by weight unless ingredient is a gas. Gas concentrations are in percent by volume.

**NOTE:** Composition may contain up to 0.5% performance additives and / or dyes. May contain up to 20% by weight of soybean oil, methyl ester (CAS# 67784-80-9).

### SECTION 4 FIRST-AID MEASURES

#### INHALATION

Immediately remove from further exposure. Get immediate medical assistance. For those providing assistance, avoid exposure to yourself or others. Use adequate respiratory protection. Give supplemental oxygen, if available. If breathing has stopped, assist ventilation with a mechanical device.

#### SKIN CONTACT

Remove contaminated clothing. Dry wipe exposed skin and cleanse with waterless hand cleaner and follow by washing thoroughly with soap and water. For those providing assistance, avoid further skin contact to yourself or others. Wear impervious gloves. Launder contaminated clothing separately before reuse. Discard contaminated articles that cannot be laundered. If product is injected into or under the skin, or into any part of the body, regardless of the appearance of the wound or its size, the individual should be evaluated immediately

Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 4 of 13

by a physician as a surgical emergency. Even though initial symptoms from high pressure injection may be minimal or absent, early surgical treatment within the first few hours may significantly reduce the ultimate extent of injury.

#### EYE CONTACT

Flush thoroughly with water. If irritation occurs, get medical assistance.

#### INGESTION

Seek immediate medical attention. Do not induce vomiting.

#### NOTE TO PHYSICIAN

If ingested, material may be aspirated into the lungs and cause chemical pneumonitis. Treat appropriately.

#### PRE-EXISTING MEDICAL CONDITIONS WHICH MAY BE AGGRAVATED BY EXPOSURE

Contains hydrocarbon solvent/petroleum hydrocarbons; skin contact may aggravate an existing dermatitis.

### SECTION 5 FIRE-FIGHTING MEASURES

#### EXTINGUISHING MEDIA

**Appropriate Extinguishing Media:** Use water fog, foam, dry chemical or carbon dioxide (CO<sub>2</sub>) to extinguish flames.

**Inappropriate Extinguishing Media:** Straight streams of water

#### FIRE FIGHTING

**Fire Fighting Instructions:** FLAMMABLE. Evacuate area. Prevent run-off from fire control or dilution from entering streams, sewers or drinking water supply. Fire-fighters should use standard protective equipment and in enclosed spaces, self-contained breathing apparatus (SCBA). Use water spray to cool fire exposed surfaces and to protect personnel.

**Unusual Fire Hazards:** Vapour is flammable and heavier than air. Vapour may travel across the ground and reach remote ignition sources, causing a flashback fire danger. Hazardous material. Firefighters should consider protective equipment indicated in Section 8.

**Hazardous Combustion Products:** Aldehydes, incomplete combustion products, Oxides of carbon, Smoke, Fume, Sulphur oxides

#### FLAMMABILITY PROPERTIES

Flash Point [Method]: >38°C (100°F) [ASTM D-93]

Flammable Limits (Approximate volume % in air): LEL: N/D UEL: N/D

Autoignition Temperature: N/D

### SECTION 6 ACCIDENTAL RELEASE MEASURES

#### NOTIFICATION PROCEDURES

In the event of a spill or accidental release, notify relevant authorities in accordance with all applicable regulations.

#### PROTECTIVE MEASURES



Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 5 of 13

Avoid contact with spilled material. Warn or evacuate occupants in surrounding and downwind areas if required, due to toxicity or flammability of the material. See Section 5 for fire fighting information. See the Hazard Identification Section for Significant Hazards. See Section 4 for First Aid Advice. See Section 8 for advice on the minimum requirements for personal protective equipment. Additional protective measures may be necessary, depending on the specific circumstances and/or the expert judgment of the emergency responders.

For emergency responders: Respiratory protection: half-face or full-face respirator with filter(s) for organic vapor and, when applicable, H<sub>2</sub>S, or Self Contained Breathing Apparatus (SCBA) can be used depending on the size of spill and potential level of exposure. If the exposure cannot be completely characterized or an oxygen deficient atmosphere is possible or anticipated, SCBA is recommended. Work gloves that are resistant to aromatic hydrocarbons are recommended. Note: gloves made of polyvinyl acetate (PVA) are not water-resistant and are not suitable for emergency use. Chemical goggles are recommended if splashes or contact with eyes is possible. Small spills: normal antistatic work clothes are usually adequate. Large spills: full body suit of chemical resistant, antistatic material is recommended.

#### SPILL MANAGEMENT

**Land Spill:** Eliminate all ignition sources (no smoking, flares, sparks or flames in immediate area). Stop leak if you can do so without risk. All equipment used when handling the product must be grounded. Do not touch or walk through spilled material. Prevent entry into waterways, sewer, basements or confined areas. A vapour-suppressing foam may be used to reduce vapour. Use clean non-sparking tools to collect absorbed material. Absorb or cover with dry earth, sand or other non-combustible material and transfer to containers. Large Spills: Water spray may reduce vapour, but may not prevent ignition in enclosed spaces.

**Water Spill:** Stop leak if you can do so without risk. Eliminate sources of ignition. Warn other shipping. If the Flash Point exceeds the Ambient Temperature by 10 deg C or more, use containment booms and remove from the surface by skimming or with suitable absorbents when conditions permit. If the Flash Point does not exceed the Ambient Air Temperature by at least 10C, use booms as a barrier to protect shorelines and allow material to evaporate. Seek the advice of a specialist before using dispersants.

Water spill and land spill recommendations are based on the most likely spill scenario for this material; however, geographic conditions, wind, temperature, (and in the case of a water spill) wave and current direction and speed may greatly influence the appropriate action to be taken. For this reason, local experts should be consulted. Note: Local regulations may prescribe or limit action to be taken.

#### ENVIRONMENTAL PRECAUTIONS

Large Spills: Dyke far ahead of liquid spill for later recovery and disposal. Prevent entry into waterways, sewers, basements or confined areas.

### SECTION 7 HANDLING AND STORAGE

#### HANDLING

Avoid all personal contact. Do not siphon by mouth. Place rags, absorbent pads, paper towels etc. contaminated with biodiesel in a container and cover with water. Secure the lid on the container (See Section 5 - Unusual Fire Hazards). Do not use as a cleaning solvent or other non-motor fuel uses. For use as a motor fuel only. It is dangerous and/or unlawful to put petrol into unapproved containers. Do not fill container while it is in or on a vehicle. Static electricity may ignite vapour and cause fire. Place container on ground when filling and keep nozzle in contact with container. Do not use electronic devices (including but not limited to cellular phones, computers, calculators, pagers or other electronic devices, etc.) during safety critical tasks, such as bulk fuel loading or unloading operations, or in storage areas where vapours may be present, unless the

Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 6 of 13

devices are certified intrinsically safe by an approved national testing agency and to the safety standards required by national and/or local laws and regulations. Prevent small spills and leakage to avoid slip hazard. Material can accumulate static charges which may cause an electrical spark (ignition source). Use proper bonding and/or ground procedures. However, bonding and grounds may not eliminate the hazard from static accumulation. Consult local applicable standards for guidance. Additional references include American Petroleum Institute 2003 (Protection Against Ignitions Arising out of Static, Lightning and Stray Currents) or National Fire Protection Agency 77 (Recommended Practice on Static Electricity) or CENELEC CLC/TR 50404 (Electrostatics - Code of practice for the avoidance of hazards due to static electricity).

**Static Accumulator:** This material is a static accumulator. A liquid is typically considered a nonconductive, static accumulator if its conductivity is below 100 pS/m (100x10E-12 Siemens per meter) and is considered a semiconductive, static accumulator if its conductivity is below 10,000 pS/m. Whether a liquid is nonconductive or semiconductive, the precautions are the same. A number of factors, for example liquid temperature, presence of contaminants, anti-static additives and filtration can greatly influence the conductivity of a liquid.

#### STORAGE

The type of container used to store the material may affect static accumulation and dissipation. Keep container closed. Handle containers with care. Open slowly in order to control possible pressure release. Store in a cool, well-ventilated area. Storage containers should be earthed and bonded. Fixed storage containers, transfer containers and associated equipment should be grounded and bonded to prevent accumulation of static charge.

### SECTION 8 EXPOSURE CONTROLS / PERSONAL PROTECTION

#### EXPOSURE LIMIT VALUES

Substance Name	Form	Limit/Standard			Note	Source
Fuel oil, No 2	Stable Aerosol.	TWA	5 mg/m3		Skin	Supplier
Fuel oil, No 2	Vapour.	TWA	200 mg/m3		Skin	Supplier
FUEL OIL NO. 2 [total hydrocarb, vapor/aerosol]	Inhalable fraction and vapour	TWA	100 mg/m3		Skin	ACGIH
naphthalene		TWA	10 ppm		Skin	ACGIH

NOTE: Limits/standards shown for guidance only. Follow applicable regulations.

#### ENGINEERING CONTROLS

The level of protection and types of controls necessary will vary depending upon potential exposure conditions. Control measures to consider:

Use explosion-proof ventilation equipment to stay below exposure limits.

#### PERSONAL PROTECTION

Personal protective equipment selections vary based on potential exposure conditions such as applications,







Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 7 of 13

handling practices, concentration and ventilation. Information on the selection of protective equipment for use with this material, as provided below, is based upon intended, normal usage.

**Respiratory Protection:** If engineering controls do not maintain airborne contaminant concentrations at a level which is adequate to protect worker health, an approved respirator may be appropriate. Respirator selection, use, and maintenance must be in accordance with regulatory requirements, if applicable. Types of respirators to be considered for this material include:

No special requirements under ordinary conditions of use and with adequate ventilation.

For high airborne concentrations, use an approved supplied-air respirator, operated in positive pressure mode. Supplied air respirators with an escape bottle may be appropriate when oxygen levels are inadequate, gas/vapour warning properties are poor, or if air purifying filter capacity/rating may be exceeded.

**Hand Protection:** Any specific glove information provided is based on published literature and glove manufacturer data. Glove suitability and breakthrough time will differ depending on the specific use conditions. Contact the glove manufacturer for specific advice on glove selection and breakthrough times for your use conditions. Inspect and replace worn or damaged gloves. The types of gloves to be considered for this material include:

Chemical resistant gloves are recommended. If contact with forearms is likely wear gauntlet style gloves.

**Eye Protection:** If contact with material is likely, chemical goggles are recommended.

**Skin and Body Protection:** Any specific clothing information provided is based on published literature or manufacturer data. The types of clothing to be considered for this material include:  
Chemical/oil resistant clothing is recommended.

**Specific Hygiene Measures:** Always observe good personal hygiene measures, such as washing after handling the material and before eating, drinking, and/or smoking. Routinely wash work clothing and protective equipment to remove contaminants. Discard contaminated clothing and footwear that cannot be cleaned. Practise good housekeeping.

#### ENVIRONMENTAL CONTROLS

Comply with applicable environmental regulations limiting discharge to air, water and soil. Protect the environment by applying appropriate control measures to prevent or limit emissions.

#### SECTION 9 PHYSICAL AND CHEMICAL PROPERTIES

**Note:** Physical and chemical properties are provided for safety, health and environmental considerations only and may not fully represent product specifications. Contact the Supplier for additional information.

#### GENERAL INFORMATION

Physical State: Liquid  
Colour: Amber  
Odour: Petroleum/Solvent  
Odour Threshold: N/D

#### IMPORTANT HEALTH, SAFETY, AND ENVIRONMENTAL INFORMATION

Relative Density (at 15 °C): 0.82 - 0.9

Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 8 of 13

Flammability (Solid, Gas): N/A  
Flash Point [Method]: >38°C (100°F) [ASTM D-93]  
Flammable Limits (Approximate volume % in air): LEL: N/D UEL: N/D  
Autoignition Temperature: N/D  
Boiling Point / Range: > 150°C (302°F)  
Decomposition Temperature: N/D  
Vapour Density (Air = 1): > 2 at 101 kPa  
Vapour Pressure: 0.067 kPa (0.5 mm Hg) at 20°C  
Evaporation Rate (n-butyl acetate = 1): N/D  
pH: N/A  
Log Pow (n-Octanol/Water Partition Coefficient): N/D  
Solubility in Water: Negligible  
Viscosity: 1.6 cSt (1.6 mm<sup>2</sup>/sec) at 40°C - 5 cSt (5 mm<sup>2</sup>/sec) at 40°C  
Oxidizing Properties: See Hazards Identification Section.

#### OTHER INFORMATION

Freezing Point: N/D  
Melting Point: N/A

#### SECTION 10 STABILITY AND REACTIVITY

**STABILITY:** Material is stable under normal conditions.

**CONDITIONS TO AVOID:** Avoid heat, sparks, open flames and other ignition sources.

**MATERIALS TO AVOID:** Halogens, Strong Acids, Strong Bases, Strong oxidizers

**HAZARDOUS DECOMPOSITION PRODUCTS:** Material does not decompose at ambient temperatures.

**POSSIBILITY OF HAZARDOUS REACTIONS:** Hazardous polymerization will not occur.

#### SECTION 11 TOXICOLOGICAL INFORMATION

##### INFORMATION ON TOXICOLOGICAL EFFECTS

Hazard Class	Conclusion / Remarks
<b>Inhalation</b>	
Acute Toxicity: No end point data for material.	Moderately toxic. Based on assessment of the components.
Irritation: No end point data for material.	Elevated temperatures or mechanical action may form vapours, mist, or fumes which may be irritating to the eyes, nose, throat, or lungs.
<b>Ingestion</b>	
Acute Toxicity: No end point data for material.	Minimally Toxic. Based on assessment of the components.
<b>Skin</b>	
Acute Toxicity: No end point data for material.	Minimally Toxic. Based on assessment of the components.
Skin Corrosion/Irritation: No end point data for material.	Irritating to the skin. Based on assessment of the components.



Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 9 of 13

<b>Eye</b>	
Serious Eye Damage/Irritation: No end point data for material.	May cause mild, short-lasting discomfort to eyes. Based on assessment of the components.
<b>Sensitisation</b>	
Respiratory Sensitization: No end point data for material.	Not expected to be a respiratory sensitizer.
Skin Sensitization: No end point data for material.	Not expected to be a skin sensitizer. Based on assessment of the components.
<b>Aspiration:</b> Data available.	May be fatal if swallowed and enters airways. Based on physico-chemical properties of the material.
<b>Germ Cell Mutagenicity:</b> No end point data for material.	Not expected to be a germ cell mutagen. Based on assessment of the components.
<b>Carcinogenicity:</b> No end point data for material.	Caused cancer in laboratory animals, but the relevance to humans is uncertain. Based on assessment of the components.
<b>Reproductive Toxicity:</b> No end point data for material.	Not expected to be a reproductive toxicant. Based on assessment of the components.
<b>Lactation:</b> No end point data for material.	Not expected to cause harm to breast-fed children.
<b>Specific Target Organ Toxicity (STOT)</b>	
Single Exposure: No end point data for material.	Not expected to cause organ damage from a single exposure.
Repeated Exposure: No end point data for material.	Concentrated, prolonged or deliberate exposure may cause organ damage. Based on assessment of the components.

#### TOXICITY FOR SUBSTANCES

NAME	ACUTE TOXICITY
Fuel oil, No 2	Inhalation Lethality: 4 hour(s) LC50 4.1 mg/l (Vapor and aerosol)
naphthalene	Inhalation Lethality: 4 hour(s) LC50 > 0.4 mg/l (Max attainable vapor conc.) (Rat); Oral Lethality: LD 50 533 mg/kg (Mouse)

#### OTHER INFORMATION

For the product itself:

Target Organs Repeated Exposure: Bone marrow, Liver, Thymus

Vapour concentrations above recommended exposure levels are irritating to the eyes and the respiratory tract, may cause headaches and dizziness, are anaesthetic and may have other central nervous system effects. Small amounts of liquid aspirated into the lungs during ingestion or from vomiting may cause chemical pneumonitis or pulmonary edema.

Diesel fuel: Carcinogenic in animal tests. Caused mutations in-vitro. Repeated dermal exposures to high concentrations in test animals resulted in reduced litter size and litter weight, and increased fetal resorptions at maternally toxic doses. Dermal exposure to high concentrations resulted in severe skin irritation with weight loss and some mortality. Inhalation exposure to high concentrations resulted in respiratory tract irritation, lung changes/infiltration/accumulation, and reduction in lung function. Diesel exhaust fumes: Carcinogenic in animal tests. Inhalation exposures to exhaust for 2 years in test animals resulted in lung tumours and lymphoma. Extract of particulate produced skin tumours in test animals. Caused mutations in-vitro.

#### Contains:

NAPHTHALENE: Exposure to high concentrations of naphthalene may cause destruction of red blood cells, anemia, and cataracts. Naphthalene caused cancer in laboratory animal studies, but the relevance of these findings to humans is uncertain.

Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 10 of 13

#### CMR Status:

Chemical Name	CAS Number	List Citations
Fuel oil, No 2	68476-30-2	4
naphthalene	91-20-3	3, 4

#### —REGULATORY LISTS SEARCHED—

1 = IARC 1  
2 = IARC 2A  
3 = IARC 2B  
4 = ACGIH ALL  
5 = ACGIH A1  
6 = ACGIH A2

#### SECTION 12 ECOLOGICAL INFORMATION

The information given is based on data for the material, components of the material, or for similar materials, through the application of bridging principals.

#### ECOTOXICITY

Material — Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

#### MOBILITY

More volatile component — Highly volatile, will partition rapidly to air. Not expected to partition to sediment and wastewater solids.

High molecular wt. component — Low solubility and floats and is expected to migrate from water to the land. Expected to partition to sediment and wastewater solids.

#### PERSISTENCE AND DEGRADABILITY

##### Biodegradation:

Material — Expected to be inherently biodegradable

##### Atmospheric Oxidation:

More volatile component — Expected to degrade rapidly in air

#### SECTION 13 DISPOSAL CONSIDERATIONS

Disposal recommendations based on material as supplied. Disposal must be in accordance with current applicable laws and regulations, and material characteristics at time of disposal.

#### DISPOSAL RECOMMENDATIONS





Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 11 of 13

Product is suitable for burning in an enclosed controlled burner for fuel value or disposal by supervised incineration at very high temperatures to prevent formation of undesirable combustion products.

#### REGULATORY DISPOSAL INFORMATION

**Empty Container Warning** Empty Container Warning (where applicable): Empty containers may contain residue and can be dangerous. Do not attempt to refill or clean containers without proper instructions. Empty drums should be completely drained and safely stored until appropriately reconditioned or disposed. Empty containers should be taken for recycling, recovery, or disposal through suitably qualified or licensed contractor and in accordance with governmental regulations. DO NOT PRESSURISE, CUT, WELD, BRAZE, SOLDER, DRILL, GRIND, OR EXPOSE SUCH CONTAINERS TO HEAT, FLAME, SPARKS, STATIC ELECTRICITY, OR OTHER SOURCES OF IGNITION. THEY MAY EXPLODE AND CAUSE INJURY OR DEATH.

#### SECTION 14 TRANSPORT INFORMATION

##### LAND (TDG)

Proper Shipping Name: DIESEL FUEL  
Hazard Class & Division: 3  
UN Number: 1202  
Packing Group: III  
Special Provisions: 88, 150

##### LAND (DOT)

Proper Shipping Name: DIESEL FUEL  
Hazard Class & Division: COMBUSTIBLE LIQUID  
ID Number: NA1993  
Packing Group: III  
ERG Number: 128  
Label(s): NONE  
Transport Document Name: NA1993, DIESEL FUEL, COMBUSTIBLE LIQUID, PG III

Footnote: The flash point of this material is greater than 38°C/100°F. Regulatory classification of this material varies. DOT: Flammable liquid or combustible liquid. OSHA: Combustible liquid. IATA/IMO: Flammable liquid. This material is not regulated under 49 CFR in a container of 450 litre/119 gallon capacity or less when transported solely by land, as long as the material is not a hazardous waste, a marine pollutant, or specifically listed as a hazardous substance.

##### SEA (IMDG)

Proper Shipping Name: GAS OIL  
Hazard Class & Division: 3  
EMS Number: F-E, S-E  
UN Number: 1202  
Packing Group: III  
Marine Pollutant: No  
Label(s): 3  
Transport Document Name: UN1202, GAS OIL, 3, PG III, (38°C c.c.)

##### AIR (IATA)

Proper Shipping Name: GAS OIL  
Hazard Class & Division: 3

Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 12 of 13

UN Number: 1202  
Packing Group: III  
Label(s) / Mark(s): 3  
Transport Document Name: UN1202, GAS OIL, 3, PG III

#### SECTION 15 REGULATORY INFORMATION

CEPA: All components of this product are either on the Domestic Substance List (DSL) or are exempt.

Listed or exempt from listing/notification on the following chemical inventories (May contain substance(s) subject to notification to the EPA Active TSCA inventory prior to import to USA): DSL

The Following Ingredients are Cited on the Lists Below: None.

1 = TSCA 4  
2 = TSCA 5a2  
3 = TSCA 5e  
4 = TSCA 6  
5 = TSCA 12b  
6 = NPRI

—REGULATORY LISTS SEARCHED—

#### SECTION 16 OTHER INFORMATION

N/D = Not determined, N/A = Not applicable

##### KEY TO THE H-CODES CONTAINED IN SECTION 3 OF THIS DOCUMENT (for information only):

H302: Harmful if swallowed; Acute Tox Oral, Cat 4  
H304: May be fatal if swallowed and enters airways; Aspiration, Cat 1  
H315: Causes skin irritation; Skin Cor/Irritation, Cat 2  
H332: Harmful if inhaled; Acute Tox Inh, Cat 4  
H351: Suspected of causing cancer; GHS Carcinogenicity, Cat 2  
H400: Very toxic to aquatic life; Acute Env Tox, Cat 1  
H401: Toxic to aquatic life; Acute Env Tox, Cat 2  
H410: Very toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 1  
H411: Toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 2

##### THIS SAFETY DATA SHEET CONTAINS THE FOLLOWING REVISIONS:

Updates made in accordance with implementation of GHS requirements.

**SYNONYMS:** BIODIESEL BLEND B2, BIODIESEL BLEND B5, BIODIESEL BLEND B10, BIODIESEL BLEND B20, DIESEL LOW SULPHUR with BIO up to 10%, DIESEL LOW SULPHUR DYED with BIO up to 10%, DIESEL LOW SULPHUR DYED may contain biodiesel, DIESEL LOW SULPHUR may contain biodiesel, FURNACE FUEL DYED may contain biodiesel, DIESEL LOW SULPHUR RAIL may contain biodiesel, DIESEL LOW SULPHUR RAIL DYED may





Product Name: DIESEL/BIODIESEL BLEND  
Revision Date: 17 Dec 2019  
Page 13 of 13

---

contain biodiesel, DIESEL LOW SULPHUR 1% biodiesel, DIESEL LOW SULPHUR 10% biodiesel, DIESEL LOW SULPHUR 2% biodiesel, DIESEL LOW SULPHUR 20% biodiesel, DIESEL LOW SULPHUR 5% biodiesel, DIESEL LOW SULPHUR DYED 1% biodiesel, DIESEL LOW SULPHUR DYED 10% biodiesel, DIESEL LOW SULPHUR DYED 2% biodiesel, DIESEL LOW SULPHUR DYED 20% biodiesel, DIESEL LOW SULPHUR DYED 5% biodiesel, DIESEL LS RAIL 5% biodiesel, DIESEL LS RAIL DYED 5% biodiesel, FURNACE FUEL DYED 5% biodiesel, DIESEL LOW SULPHUR RAIL 5% biodiesel, DIESEL LOW SULPHUR RAIL DYED 5% biodiesel

---

The information and recommendations contained herein are, to the best of Imperial Oil's knowledge and belief, accurate and reliable as of the date issued. Imperial Oil assumes no responsibility for accuracy of information unless the document is the most current available from an official Imperial Oil distribution system. The information and recommendations are offered for the user's consideration and examination, and it is the user's responsibility to satisfy itself that they are suitable and complete for its particular use. If buyer repackages this product, legal counsel should be consulted to insure proper health, safety and other necessary information is included on the container. Appropriate warnings and safe-handling procedures should be provided to handlers and users. Alteration of this document is strictly prohibited. Except to the extent required by law, republication or retransmission of this document, in whole or in part, is not permitted.

---

DGN: 7093830 (1016263)

---

Copyright 2002 Imperial Oil Limited, All rights reserved





## APPENDIX E: SDS SHEET, UNLEADED GASOLINE



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 1 of 15

### SAFETY DATA SHEET

#### SECTION 1 IDENTIFICATION

##### PRODUCT

Product Name: UNLEADED GASOLINE  
Product Description: Hydrocarbons and Additives  
SDS Number: 8522

Intended Use: Fuel

Trade Names	Trade Names
AUTOMOTIVE GASOLINE	ESSO EXTRA GASOLINE
ESSO MIDGRADE GASOLINE	ESSO PREMIUM GASOLINE
ESSO REGULAR GASOLINE	ESSO SUPREME GASOLINE
EXXON MIDGRADE GASOLINE	EXXON PREMIUM GASOLINE
EXXON REGULAR GASOLINE	GASOLINE MIDGRADE UNLEADED MUL89
GASOLINE MIDGRADE UNLEADED MUL89 DCA	GASOLINE MIDGRADE UNLEADED MUL89 DCA DYED
GASOLINE MIDGRADE UNLEADED MUL89 LDCA	GASOLINE MIDGRADE UNLEADED MUL89 LDCA DYED
GASOLINE PREMIUM UNLEADED PUL91	GASOLINE PREMIUM UNLEADED PUL91 DCA
GASOLINE PREMIUM UNLEADED PUL91 DCA DYED	GASOLINE PREMIUM UNLEADED PUL91 LDCA
GASOLINE PREMIUM UNLEADED PUL91 LDCA DYED	GASOLINE RBOB BLENDSTOCK P91
GASOLINE RBOB BLENDSTOCK R87	GASOLINE REGULAR UNLEADED RUL87
GASOLINE REGULAR UNLEADED RUL87 DCA	GASOLINE REGULAR UNLEADED RUL87 DCA DYED
GASOLINE REGULAR UNLEADED RUL87 DYED	GASOLINE REGULAR UNLEADED RUL87 LDCA
GASOLINE REGULAR UNLEADED RUL87 LDCA DYED	

##### COMPANY IDENTIFICATION

Supplier: Imperial Oil Downstream  
P.O. Box 2480, Station M  
Calgary, ALBERTA T2P 3M9 Canada  
24 Hour Emergency Telephone 1-888-232-9583  
Transportation Emergency Phone Number 1-888-232-9583  
Product Technical Information 1-800-268-3183  
Supplier General Contact 1-800-567-3776

#### SECTION 2 HAZARD IDENTIFICATION

This material is considered to be hazardous according to regulatory guidelines.

This product has been classified in accordance with hazard criteria of the Hazardous Products Regulations (HPR) SOR/2015-17 and the SDS contains all the information required by the HPR SOR/2015-17.

Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 2 of 15



##### CLASSIFICATION:

Flammable Liquids — Category 1  
Skin Irritation — Category 2  
Germ Cell Mutagenicity — Category 1B  
Carcinogenicity — Category 1B  
Reproductive Toxicity (Developmental) — Category 2  
Specific Target Organ Toxicity — Single Exposure (Central Nervous System) — Category 3  
Aspiration Hazard — Category 1

##### LABEL:

###### Pictogram:



Signal Word: Danger

##### Hazard Statements:

H224: Extremely flammable liquid and vapour. H304: May be fatal if swallowed and enters airways. H315: Causes skin irritation. H336: May cause drowsiness or dizziness. H340: May cause genetic defects. H350: May cause cancer. H361: Suspected of damaging the unborn child.

##### Precautionary Statements:

P101: If medical advice is needed, have product container or label at hand. P102: Keep out of reach of children. P103: Read label before use. P201: Obtain special instructions before use. P202: Do not handle until all safety precautions have been read and understood. P210: Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. P233: Keep container tightly closed. P240: Ground and bond container and receiving equipment. P241: Use explosion-proof electrical, ventilating and lighting equipment. P242: Use non-sparking tools. P243: Take action to prevent static discharges. P261: Avoid breathing mist / vapours. P264: Wash skin thoroughly after handling. P271: Use only outdoors or in a well-ventilated area. P273: Avoid release to the environment. P280: Wear protective gloves/protective clothing/eye protection/face protection. P301 + P310: IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician. P302 + P352: IF ON SKIN: Wash with plenty of soap and water. P303 + P361 + P353: IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. P304 + P340: IF INHALED: Remove person to fresh air and keep comfortable for breathing. P308 + P313: IF exposed or concerned: Get medical advice/attention. P312: Call a POISON CENTER or doctor/physician if you feel unwell. P331: Do NOT induce vomiting. P332 + P313: If skin irritation occurs: Get medical advice/attention. P362 + P364: Take off contaminated clothing and wash it before reuse. P370 + P378: In case of fire: Use water fog, foam, dry chemical or carbon dioxide (CO2) to extinguish. P391: Collect spillage. P403 + P235: Store in a well-ventilated place. Keep cool. P405: Store locked up. P501: Dispose of contents and container in accordance with local regulations.

Contains: Benzene; GASOLINE; Toluene



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 3 of 15

#### Other hazard information:

**Health Hazards Not Otherwise Classified:** None as defined under HPR SOR/2015-17.

**Physical Hazards Not Otherwise Classified:** None as defined under HPR SOR/2015-17.

#### PHYSICAL / CHEMICAL HAZARDS

Material can accumulate static charges which may cause an ignition. Material can release vapours that readily form flammable mixtures. Vapour accumulation could flash and/or explode if ignited.

#### HEALTH HAZARDS

High-pressure injection under skin may cause serious damage. May be irritating to the eyes, nose, throat, and lungs. May cause central nervous system depression. Exposure to benzene is associated with cancer (acute myeloid leukaemia and myelodysplastic syndrome), damage to the blood-producing system, and serious blood disorders (see Section 11).

#### ENVIRONMENTAL HAZARDS

Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

NFPA Hazard ID: Health: 2 Flammability: 3 Reactivity: 0  
HMIS Hazard ID: Health: 2\* Flammability: 3 Reactivity: 0

**NOTE:** This material should not be used for any other purpose than the intended use in Section 1 without expert advice. Health studies have shown that chemical exposure may cause potential human health risks which may vary from person to person.

### SECTION 3 COMPOSITION / INFORMATION ON INGREDIENTS

This material is defined as a mixture.

#### Hazardous Substance(s) or Complex Substance(s) in Hazardous product

Name	CAS#	Concentration*	GHS Hazard Codes
ETHYL ALCOHOL	64-17-5	0 - 1%	H225, H319(2A)
GASOLINE	86290-81-5	98 - 100%	H224, H304, H336, H340(1B), H350(1B), H361(D), H315, H401, H411

#### Hazardous Constituent(s) Contained in Complex Substance(s)

Name	CAS#	Concentration*	GHS Hazard Codes
Benzene	71-43-2	0 - 1.5%	H225, H303, H304, H340(1B), H350(1A), H315, H319(2A), H372, H401
CUMENE	98-82-8	0 - 1%	H226, H304, H336, H351, H401, H411
CYCLOHEXANE	110-82-7	0 - 1.5%	H225, H304, H336, H315, H400(M factor 1), H410(M factor 1)
ETHYL BENZENE	100-41-4	0 - 3.5%	H225, H332, H373, H401, H412

Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 4 of 15



Name	CAS#	Concentration*	GHS Hazard Codes
n-Hexane	110-54-3	0 - 5%	H225, H304, H336, H361(F), H315, H373, H401, H411
Naphthalene	91-20-3	0 - 1%	H302, H351, H400(M factor 1), H410(M factor 1)
Toluene	108-88-3	0 - 20%	H225, H304, H336, H361(D), H315, H373, H401, H412
XYLENES	1330-20-7	0 - 20%	H226, H304, H312, H332, H336, H315, H320(2B), H373, H401

\* All concentrations are percent by weight unless ingredient is a gas. Gas concentrations are in percent by volume.

**NOTE:** The concentration of the components shown above may vary substantially. In certain countries, benzene content may be limited to lower levels. Oxygenates such as tertiary-amy-methyl ether, ethanol, di-isopropyl ether, and ethyl-tertiary-butyl ether may be present. Because of volatility considerations, gasoline vapor may have concentrations of components very different from those of liquid gasoline. The major components of gasoline vapor are: butane, isobutane, pentane, and isopentane. The reportable component percentages, shown in the composition/information on ingredients section, are based on API's evaluation of a typical gasoline mixture.

### SECTION 4 FIRST-AID MEASURES

#### INHALATION

Immediately remove from further exposure. Get immediate medical assistance. For those providing assistance, avoid exposure to yourself or others. Use adequate respiratory protection. Give supplemental oxygen, if available. If breathing has stopped, assist ventilation with a mechanical device.

#### SKIN CONTACT

Wash contact areas with soap and water. Remove contaminated clothing. Launder contaminated clothing before reuse. If product is injected into or under the skin, or into any part of the body, regardless of the appearance of the wound or its size, the individual should be evaluated immediately by a physician as a surgical emergency. Even though initial symptoms from high pressure injection may be minimal or absent, early surgical treatment within the first few hours may significantly reduce the ultimate extent of injury.

#### EYE CONTACT

Flush thoroughly with water. If irritation occurs, get medical assistance.

#### INGESTION

Seek immediate medical attention. Do not induce vomiting.

#### NOTE TO PHYSICIAN

If ingested, material may be aspirated into the lungs and cause chemical pneumonitis. Treat appropriately. This material, or a component, may be associated with cardiac sensitization following very high exposures (well above occupational exposure limits) or with concurrent exposure to high stress levels or heart-stimulating substances like epinephrine. Administration of such substances should be avoided.

### SECTION 5 FIRE-FIGHTING MEASURES

#### EXTINGUISHING MEDIA

**Appropriate Extinguishing Media:** Use water fog, foam, dry chemical or carbon dioxide (CO2) to extinguish





Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 5 of 15

flames.

**Inappropriate Extinguishing Media:** Straight streams of water

#### FIRE FIGHTING

**Fire Fighting Instructions:** Evacuate area. If a leak or spill has not ignited, use water spray to disperse the vapours and to protect personnel attempting to stop a leak. Prevent run-off from fire control or dilution from entering streams, sewers or drinking water supply. Fire-fighters should use standard protective equipment and in enclosed spaces, self-contained breathing apparatus (SCBA). Use water spray to cool fire exposed surfaces and to protect personnel.

**Unusual Fire Hazards:** Extremely Flammable. Vapour is flammable and heavier than air. Vapour may travel across the ground and reach remote ignition sources, causing a flashback fire danger. Hazardous material. Firefighters should consider protective equipment indicated in Section 8.

**Hazardous Combustion Products:** Aldehydes, Incomplete combustion products, Oxides of carbon, Smoke, Fume, Sulphur oxides

#### FLAMMABILITY PROPERTIES

Flash Point [Method]: -40°C (-40°F) [ASTM D-92]

Flammable Limits (Approximate volume % in air): LEL: 1.4 UEL: 7.6

Autoignition Temperature: >250°C (482°F)

#### SECTION 6 ACCIDENTAL RELEASE MEASURES

##### NOTIFICATION PROCEDURES

In the event of a spill or accidental release, notify relevant authorities in accordance with all applicable regulations.

##### PROTECTIVE MEASURES

Avoid contact with spilled material. Warn or evacuate occupants in surrounding and downwind areas if required, due to toxicity or flammability of the material. See Section 5 for fire fighting information. See the Hazard Identification Section for Significant Hazards. See Section 4 for First Aid Advice. See Section 8 for advice on the minimum requirements for personal protective equipment. Additional protective measures may be necessary, depending on the specific circumstances and/or the expert judgment of the emergency responders.

For emergency responders: Respiratory protection: half-face or full-face respirator with filter(s) for organic vapor and, when applicable, H<sub>2</sub>S, or Self Contained Breathing Apparatus (SCBA) can be used depending on the size of spill and potential level of exposure. If the exposure cannot be completely characterized or an oxygen deficient atmosphere is possible or anticipated, SCBA is recommended. Work gloves that are resistant to aromatic hydrocarbons are recommended. Note: gloves made of polyvinyl acetate (PVA) are not water-resistant and are not suitable for emergency use. Chemical goggles are recommended if splashes or contact with eyes is possible. Small spills: normal antistatic work clothes are usually adequate. Large spills: full body suit of chemical resistant, antistatic material is recommended.

##### SPILL MANAGEMENT

**Land Spill:** Eliminate all ignition sources (no smoking, flares, sparks or flames in immediate area). Stop leak if you can do so without risk. All equipment used when handling the product must be grounded. Do not touch or walk through spilled material. Prevent entry into waterways, sewer, basements or confined areas. A



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 6 of 15

vapour-suppressing foam may be used to reduce vapour. Use clean non-sparking tools to collect absorbed material. Absorb or cover with dry earth, sand or other non-combustible material and transfer to containers. **Large Spills:** Water spray may reduce vapour, but may not prevent ignition in enclosed spaces.

**Water Spill:** Eliminate all ignition sources (no smoking, flares, sparks or flames in immediate area). Stop leak if you can do so without risk. Do not confine in area of spill. Advise occupants and shipping in downwind areas of fire and explosion hazard and warn them to stay clear. Allow liquid to evaporate from the surface. Seek the advice of a specialist before using dispersants.

Water spill and land spill recommendations are based on the most likely spill scenario for this material; however, geographic conditions, wind, temperature, (and in the case of a water spill) wave and current direction and speed may greatly influence the appropriate action to be taken. For this reason, local experts should be consulted. Note: Local regulations may prescribe or limit action to be taken.

#### ENVIRONMENTAL PRECAUTIONS

**Large Spills:** Dyke far ahead of liquid spill for later recovery and disposal. Prevent entry into waterways, sewers, basements or confined areas.

#### SECTION 7 HANDLING AND STORAGE

##### HANDLING

Avoid all personal contact. Prevent exposure to ignition sources, for example use non-sparking tools and explosion-proof equipment. Potentially toxic/irritating fumes/vapour may be evolved from heated or agitated material. Do not siphon by mouth. Use only with adequate ventilation. Do not use as a cleaning solvent or other non-motor fuel uses. For use as a motor fuel only. It is dangerous and/or unlawful to put petrol into unapproved containers. Do not fill container while it is in or on a vehicle. Static electricity may ignite vapour and cause fire. Place container on ground when filling and keep nozzle in contact with container. Do not use electronic devices (including but not limited to cellular phones, computers, calculators, pagers or other electronic devices etc) in or around any fuelling operation or storage area unless the devices are certified intrinsically safe by an approved national testing agency and to the safety standards required by national and/or local laws and regulations. Prevent small spills and leakage to avoid slip hazard. Material can accumulate static charges which may cause an electrical spark (ignition source). Use proper bonding and/or ground procedures. However, bonding and grounds may not eliminate the hazard from static accumulation. Consult local applicable standards for guidance. Additional references include American Petroleum Institute 2003 (Protection Against Ignitions Arising out of Static, Lightning and Stray Currents) or National Fire Protection Agency 77 (Recommended Practice on Static Electricity) or CENELEC CLC/TR 50404 (Electrostatics - Code of practice for the avoidance of hazards due to static electricity).

**Static Accumulator:** This material is a static accumulator. A liquid is typically considered a nonconductive, static accumulator if its conductivity is below 100 pS/m (100x10E-12 Siemens per meter) and is considered a semiconductive, static accumulator if its conductivity is below 10,000 pS/m. Whether a liquid is nonconductive or semiconductive, the precautions are the same. A number of factors, for example liquid temperature, presence of contaminants, anti-static additives and filtration can greatly influence the conductivity of a liquid.

##### STORAGE

Ample fire water supply should be available. A fixed sprinkler/deluge system is recommended. The type of container used to store the material may affect static accumulation and dissipation. Keep container closed. Handle containers with care. Open slowly in order to control possible pressure release. Store in a cool, well-ventilated area. Outside or detached storage preferred. Storage containers should be earthed and bonded.



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 7 of 15

Fixed storage containers, transfer containers and associated equipment should be grounded and bonded to prevent accumulation of static charge.

## SECTION 8 EXPOSURE CONTROLS / PERSONAL PROTECTION

### EXPOSURE LIMIT VALUES

Substance Name	Form	Limit/Standard	Note	Source
Benzene		STEL 1 ppm		Supplier
Benzene		TWA 0.5 ppm		Supplier
Benzene		STEL 2.5 ppm	Skin	ACGIH
Benzene		TWA 0.5 ppm	Skin	ACGIH
CUMENE		TWA 5 ppm	Skin	Supplier
CUMENE		TWA 50 ppm		ACGIH
CYCLOHEXANE		TWA 100 ppm		ACGIH
ETHYL ALCOHOL		STEL 1000 ppm		ACGIH
ETHYL BENZENE		TWA 20 ppm		ACGIH
GASOLINE		STEL 200 ppm		Supplier
GASOLINE		TWA 100 ppm		Supplier
GASOLINE		STEL 500 ppm		ACGIH
GASOLINE		TWA 300 ppm		ACGIH
n-Hexane		TWA 50 ppm	Skin	ACGIH
Naphthalene		TWA 10 ppm	Skin	ACGIH
Toluene		TWA 20 ppm		ACGIH
XYLENES		STEL 150 ppm		ACGIH
XYLENES		TWA 100 ppm		ACGIH

NOTE: Limits/standards shown for guidance only. Follow applicable regulations.

### ENGINEERING CONTROLS

The level of protection and types of controls necessary will vary depending upon potential exposure conditions. Control measures to consider:  
Use explosion-proof ventilation equipment to stay below exposure limits.

### PERSONAL PROTECTION

Personal protective equipment selections vary based on potential exposure conditions such as applications, handling practices, concentration and ventilation. Information on the selection of protective equipment for use with this material, as provided below, is based upon intended, normal usage.

**Respiratory Protection:** If engineering controls do not maintain airborne contaminant concentrations at a level which is adequate to protect worker health, an approved respirator may be appropriate. Respirator selection, use, and maintenance must be in accordance with regulatory requirements, if applicable. Types of



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 8 of 15

respirators to be considered for this material include:

No protection is ordinarily required under normal conditions of use and with adequate ventilation.

For high airborne concentrations, use an approved supplied-air respirator, operated in positive pressure mode. Supplied air respirators with an escape bottle may be appropriate when oxygen levels are inadequate, gas/vapour warning properties are poor, or if air purifying filter capacity/rating may be exceeded.

**Hand Protection:** Any specific glove information provided is based on published literature and glove manufacturer data. Glove suitability and breakthrough time will differ depending on the specific use conditions. Contact the glove manufacturer for specific advice on glove selection and breakthrough times for your use conditions. Inspect and replace worn or damaged gloves. The types of gloves to be considered for this material include:

Chemical resistant gloves are recommended.

**Eye Protection:** If contact is likely, safety glasses with side shields are recommended.

**Skin and Body Protection:** Any specific clothing information provided is based on published literature or manufacturer data. The types of clothing to be considered for this material include:  
Chemical/oil resistant clothing is recommended.

**Specific Hygiene Measures:** Always observe good personal hygiene measures, such as washing after handling the material and before eating, drinking, and/or smoking. Routinely wash work clothing and protective equipment to remove contaminants. Discard contaminated clothing and footwear that cannot be cleaned. Practise good housekeeping.

### ENVIRONMENTAL CONTROLS

Comply with applicable environmental regulations limiting discharge to air, water and soil. Protect the environment by applying appropriate control measures to prevent or limit emissions.

## SECTION 9 PHYSICAL AND CHEMICAL PROPERTIES

Note: Physical and chemical properties are provided for safety, health and environmental considerations only and may not fully represent product specifications. Contact the Supplier for additional information.

### GENERAL INFORMATION

Physical State: Liquid  
Colour: Clear (May Be Dyed)  
Odour: Petroleum/Solvent  
Odour Threshold: N/D

### IMPORTANT HEALTH, SAFETY, AND ENVIRONMENTAL INFORMATION

Relative Density (at 15 °C): 0.74  
Flammability (Solid, Gas): N/A  
Flash Point [Method]: -40°C (-40°F) [ASTM D-92]  
Flammable Limits (Approximate volume % in air): LEL: 1.4 UEL: 7.6  
Autoignition Temperature: >250°C (482°F)  
Boiling Point / Range: > 20°C (68°F) - 225°C (437°F)  
Decomposition Temperature: N/D  
Vapour Density (Air = 1): 3.2 at 101 kPa





Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 9 of 15

Vapour Pressure: > 26.6 kPa (200 mm Hg) at 20°C | 76 kPa (570 mm Hg) at 38 °C - 103 kPa (772.5 mm Hg) at 38°C  
Evaporation Rate (n-butyl acetate = 1): > 10  
pH: N/A  
Log Pow (n-Octanol/Water Partition Coefficient): > 3  
Solubility in Water: Negligible  
Viscosity: <1 cSt (1 mm<sup>2</sup>/sec) at 40°C  
Oxidizing Properties: See Hazards Identification Section.

#### OTHER INFORMATION

Freezing Point: N/D  
Melting Point: N/A

#### SECTION 10 STABILITY AND REACTIVITY

**STABILITY:** Material is stable under normal conditions.

**CONDITIONS TO AVOID:** Avoid heat, sparks, open flames and other ignition sources.

**MATERIALS TO AVOID:** Alkalies, Halogens, Strong Acids, Strong oxidizers

**HAZARDOUS DECOMPOSITION PRODUCTS:** Material does not decompose at ambient temperatures.

**POSSIBILITY OF HAZARDOUS REACTIONS:** Hazardous polymerization will not occur.

#### SECTION 11 TOXICOLOGICAL INFORMATION

##### INFORMATION ON TOXICOLOGICAL EFFECTS

Hazard Class	Conclusion / Remarks
<b>Inhalation</b>	
Acute Toxicity: (Rat): 4 hour(s) LC50 > 5000 mg/m <sup>3</sup> (Vapour)	Minimally Toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 403
Irritation: No end point data for material.	Elevated temperatures or mechanical action may form vapours, mist, or fumes which may be irritating to the eyes, nose, throat, or lungs.
<b>Ingestion</b>	
Acute Toxicity (Rat): LD50 > 5000 mg/kg	Minimally Toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 401
<b>Skin</b>	
Acute Toxicity (Rabbit): LD50 > 2000 mg/kg	Minimally Toxic. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 402
Skin Corrosion/Irritation: No end point data for material.	Irritating to the skin. Based on test data for structurally similar materials.
<b>Eye</b>	
Serious Eye Damage/Irritation: No end point data for material.	May cause mild, short-lasting discomfort to eyes. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 405
<b>Sensitisation</b>	
Respiratory Sensitization: No end point data	Not expected to be a respiratory sensitizer.

Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 10 of 15

for material.	
Skin Sensitization: Data available.	Not expected to be a skin sensitizer. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 406
Aspiration: Data available.	May be fatal if swallowed and enters airways. Based on physico-chemical properties of the material.
Germ Cell Mutagenicity: Data available.	Caused genetic effects in laboratory animals, but the relevance to humans is uncertain. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 471 475 478
Carcinogenicity: Data available.	Caused cancer in laboratory animals. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 451
Reproductive Toxicity: Data available.	Caused damage to the fetus in laboratory animals, but the relevance to humans is uncertain. Based on assessment of the components.
Lactation: No end point data for material.	Not expected to cause harm to breast-fed children.
Specific Target Organ Toxicity (STOT)	
Single Exposure: No end point data for material.	May cause drowsiness or dizziness.
Repeated Exposure: Data available.	Not expected to cause organ damage from prolonged or repeated exposure. Based on test data for structurally similar materials. Test(s) equivalent or similar to OECD Guideline 410 412 453

#### TOXICITY FOR SUBSTANCES

NAME	ACUTE TOXICITY
ETHYL BENZENE	Inhalation Lethality: 4 hour(s) LC50 17.8 mg/l (Vapour) (Rat); Oral Lethality: LD 50 3.5 g/kg (Rat)
Naphthalene	Inhalation Lethality: 4 hour(s) LC50 > 0.4 mg/l (Max attainable vapor conc.) (Rat); Oral Lethality: LD 50 533 mg/kg (Mouse)

#### OTHER INFORMATION

For the product itself:

Laboratory animal studies have shown that prolonged and repeated inhalation exposure to light hydrocarbon vapours in the same boiling range as this product can produce adverse kidney effects in male rats. However, these effects were not observed in similar studies with female rats, male and female mice, or in limited studies with other animal species. Additionally, in a number of human studies, there was no clinical evidence of such effects at normal occupational levels. In 1991, The U.S. EPA determined that the male rat kidney is not useful for assessing human risk. Vapour concentrations above recommended exposure levels are irritating to the eyes and the respiratory tract, may cause headaches and dizziness, are anaesthetic and may have other central nervous system effects. Small amounts of liquid aspirated into the lungs during ingestion or from vomiting may cause chemical pneumonitis or pulmonary edema. Exposure to this material, or one of its components, in situations where there is the potential for high levels, such as in confined spaces or with abuse, may result in abnormal heart rhythm (arrhythmia). High-level exposure to hydrocarbons (above occupational exposure limits) may initiate arrhythmia in a worker that is undergoing stress or is taking a heart-stimulating substance such as epinephrine, a nasal decongestant, or an asthma or cardiovascular drug.

**Contains:**  
BENZENE: Caused cancer (acute myeloid leukemia and myelodysplastic syndrome), damage to the blood-producing system, and serious blood disorders in human studies. Caused genetic effects and effects on the immune system in laboratory animal and some human studies. Caused toxicity to the fetus and cancer in laboratory animal studies.  
CUMENE: Repeated inhalation exposure of cumene vapour produced damage in the kidney of male rats only.



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 11 of 15

These effects are believed to be species specific and are not relevant to humans. **ETHANOL:** Prolonged or repeated exposure to high concentrations of ethanol vapour or overexposure by ingestion may produce adverse effects to brain, kidney, liver, and reproductive organs, birth defects in offspring, and developmental toxicity in offspring. **GASOLINE UNLEADED:** Carcinogenic in animal tests. Chronic inhalation studies resulted in liver tumours in female mice and kidney tumours in male rats. Neither result considered significant for human health risk assessment by the United States EPA and others. Did not cause mutations in-vitro or in-vivo. Negative in inhalation developmental studies and reproductive tox studies. Inhalation of high concentrations in animals resulted in reversible central nervous system depression, but no persistent toxic effect on the nervous system. Non-sensitizing in test animals. Caused nerve damage in humans from abusive use (sniffing). **NAPHTHALENE:** Exposure to high concentrations of naphthalene may cause destruction of red blood cells, anemia, and cataracts. Naphthalene caused cancer in laboratory animal studies, but the relevance of these findings to humans is uncertain.

**N-HEXANE:** Prolonged and/or repeated exposures to n-Hexane can cause progressive and potentially irreversible damage to the peripheral nervous system (e.g. fingers, feet, arms, legs, etc.). Simultaneous exposure to Methyl Ethyl Ketone (MEK) or Methyl Isobutyl Ketone (MIBK) and n-Hexane can potentiate the risk of adverse effects from n-Hexane on the peripheral nervous system. n-Hexane has been shown to cause testicular damage at high doses in male rats. The relevance of this effect for humans is unknown. **TOLUENE:** Concentrated, prolonged or deliberate inhalation may cause brain and nervous system damage. Prolonged and repeated exposure of pregnant animals (> 1500 ppm) have been reported to cause adverse fetal developmental effects. **ETHYLBENZENE:** Caused cancer in laboratory animal studies. The relevance of these findings to humans is uncertain.

#### CMR Status:

Chemical Name	CAS Number	List Citations
Benzene	71-43-2	1, 4, 5
CUMENE	98-82-8	3, 4
CYCLOHEXANE	110-82-7	4
ETHYL ALCOHOL	64-17-5	4
ETHYL BENZENE	100-41-4	3, 4
GASOLINE	86290-81-5	3, 4
n-Hexane	110-54-3	4
Naphthalene	91-20-3	3, 4
Toluene	108-88-3	4
XYLENES	1330-20-7	4

#### —REGULATORY LISTS SEARCHED—

1 = IARC 1  
2 = IARC 2A

3 = IARC 2B  
4 = ACGIH ALL

5 = ACGIH A1  
6 = ACGIH A2

#### SECTION 12 ECOLOGICAL INFORMATION

The information given is based on data for the material, components of the material, or for similar materials, through the application of bridging principals.

#### ECOTOXICITY



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 12 of 15

Material – Expected to be toxic to aquatic organisms. May cause long-term adverse effects in the aquatic environment.

#### MOBILITY

More volatile component – Highly volatile, will partition rapidly to air. Not expected to partition to sediment and wastewater solids.

Less volatile component – Low solubility and floats and is expected to migrate from water to the land. Expected to partition to sediment and wastewater solids.

#### PERSISTENCE AND DEGRADABILITY

##### Biodegradation:

Majority of components – Expected to be inherently biodegradable

##### Atmospheric Oxidation:

More volatile component – Expected to degrade rapidly in air

#### BIOACCUMULATION POTENTIAL

Majority of components – Has the potential to bioaccumulate, however metabolism or physical properties may reduce the bioconcentration or limit bioavailability.

#### SECTION 13 DISPOSAL CONSIDERATIONS

Disposal recommendations based on material as supplied. Disposal must be in accordance with current applicable laws and regulations, and material characteristics at time of disposal.

#### DISPOSAL RECOMMENDATIONS

Product is suitable for burning in an enclosed controlled burner for fuel value or disposal by supervised incineration at very high temperatures to prevent formation of undesirable combustion products.

#### REGULATORY DISPOSAL INFORMATION

Empty Container Warning Empty Container Warning (where applicable): Empty containers may contain residue and can be dangerous. Do not attempt to refill or clean containers without proper instructions. Empty drums should be completely drained and safely stored until appropriately reconditioned or disposed. Empty containers should be taken for recycling, recovery, or disposal through suitably qualified or licensed contractor and in accordance with governmental regulations. DO NOT PRESSURISE, CUT, WELD, BRAZE, SOLDER, DRILL, GRIND, OR EXPOSE SUCH CONTAINERS TO HEAT, FLAME, SPARKS, STATIC ELECTRICITY, OR OTHER SOURCES OF IGNITION. THEY MAY EXPLODE AND CAUSE INJURY OR DEATH.

#### SECTION 14 TRANSPORT INFORMATION

##### LAND (TDG)

Proper Shipping Name: GASOLINE  
Hazard Class & Division: 3  
UN Number: 1203





Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 13 of 15

Packing Group: II  
Marine Pollutant: Yes  
Special Provisions: 17, 88, 98, 150

Footnote: Marine Pollutant designation is applicable only if shipped over water.

#### LAND (DOT)

Proper Shipping Name: GASOLINE  
Hazard Class & Division: 3  
ID Number: 1203  
Packing Group: II  
ERG Number: 128  
Label(s): 3  
Transport Document Name: UN1203, GASOLINE, 3, PG II

#### SEA (IMDG)

Proper Shipping Name: MOTOR SPIRIT or GASOLINE or PETROL  
Hazard Class & Division: 3  
EMS Number: F-E, S-E  
UN Number: 1203  
Packing Group: II  
Marine Pollutant: No  
Label(s): 3  
Transport Document Name: UN1203, MOTOR SPIRIT or GASOLINE or PETROL, 3, PG II, (-40°C c.c.)

#### AIR (IATA)

Proper Shipping Name: MOTOR SPIRIT or GASOLINE or PETROL  
Hazard Class & Division: 3  
UN Number: 1203  
Packing Group: II  
Label(s) / Mark(s): 3  
Transport Document Name: UN1203, GASOLINE, 3, PG II

### SECTION 15 REGULATORY INFORMATION

CEPA: All components of this product are either on the Domestic Substance List (DSL) or are exempt.

Listed or exempt from listing/notification on the following chemical inventories (May contain substance(s) subject to notification to the EPA Active TSCA inventory prior to import to USA): AICS, DSL, ENCS, KECI, PICCS, TSCA

The Following Ingredients are Cited on the Lists Below:

Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 14 of 15

Chemical Name	CAS Number	List Citations
Benzene	71-43-2	6
CUMENE	98-82-8	6
CYCLOHEXANE	110-82-7	6
ETHYL BENZENE	100-41-4	6
n-Hexane	110-54-3	6
Naphthalene	91-20-3	6
Toluene	108-88-3	6
XYLENES	1330-20-7	6

#### —REGULATORY LISTS SEARCHED—

1 = TSCA 4  
2 = TSCA 5a2  
3 = TSCA 5e  
4 = TSCA 6  
5 = TSCA 12b  
6 = NPRI

### SECTION 16 OTHER INFORMATION

N/D = Not determined, N/A = Not applicable

#### KEY TO THE H-CODES CONTAINED IN SECTION 3 OF THIS DOCUMENT (for information only):

H224: Extremely flammable liquid and vapor; Flammable Liquid, Cat 1  
H225: Highly flammable liquid and vapor; Flammable Liquid, Cat 2  
H226: Flammable liquid and vapour; Flammable Liquid, Cat 3  
H302: Harmful if swallowed; Acute Tox Oral, Cat 4  
H303: May be harmful if swallowed; Acute Tox Oral, Cat 5  
H304: May be fatal if swallowed and enters airways; Aspiration, Cat 1  
H312: Harmful in contact with skin; Acute Tox Dermal, Cat 4  
H315: Causes skin irritation; Skin Corr/Irritation, Cat 2  
H319(2A): Causes serious eye irritation; Serious Eye Damage/Irr, Cat 2A  
H320(2B): Causes eye irritation; Serious Eye Damage/Irr, Cat 2B  
H332: Harmful if inhaled; Acute Tox Inh, Cat 4  
H335: May cause respiratory irritation; Target Organ Single, Resp Irr  
H336: May cause drowsiness or dizziness; Target Organ Single, Narcotic  
H340(1B): May cause genetic defects; Germ Cell Mutagenicity, Cat 1B  
H350(1A): May cause cancer; Carcinogenicity, Cat 1A  
H350(1B): May cause cancer; Carcinogenicity, Cat 1B  
H351: Suspected of causing cancer; GHS Carcinogenicity, Cat 2  
H361(D): Suspected of damaging the unborn child; Repro Tox, Cat 2 (Develop)  
H361(F): Suspected of damaging fertility; Repro Tox, Cat 2 (Fertility)  
H372: Causes damage to organs through prolonged or repeated exposure; Target Organ, Repeated, Cat 1  
H373: May cause damage to organs through prolonged or repeated exposure; Target Organ, Repeated, Cat 2  
H400: Very toxic to aquatic life; Acute Env Tox, Cat 1  
H401: Toxic to aquatic life; Acute Env Tox, Cat 2  
H410: Very toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 1  
H411: Toxic to aquatic life with long lasting effects; Chronic Env Tox, Cat 2  
H412: Harmful to aquatic life with long lasting effects; Chronic Env Tox, Cat 3

THIS SAFETY DATA SHEET CONTAINS THE FOLLOWING REVISIONS:



Product Name: UNLEADED GASOLINE  
Revision Date: 01 Oct 2018  
Page 15 of 15

---

Updates made in accordance with implementation of GHS requirements.

---

The information and recommendations contained herein are, to the best of Imperial Oil's knowledge and belief, accurate and reliable as of the date issued. Imperial Oil assumes no responsibility for accuracy of information unless the document is the most current available from an official Imperial Oil distribution system. The information and recommendations are offered for the user's consideration and examination, and it is the user's responsibility to satisfy itself that they are suitable and complete for its particular use. If buyer repackages this product, legal counsel should be consulted to insure proper health, safety and other necessary information is included on the container. Appropriate warnings and safe-handling procedures should be provided to handlers and users. Alteration of this document is strictly prohibited. Except to the extent required by law, republication or retransmission of this document, in whole or in part, is not permitted.

---

DGN: 5007481 (1006754)

---

Copyright 2002 Imperial Oil Limited, All rights reserved



*Monthly Fuel Tank Inspection will be performed on IAUDITOR (APP) and is where records will be kept. This form can also be used.*

**General inspection Information:**

Inspector Name (print): \_\_\_\_\_

Inspectors Signature: \_\_\_\_\_

Tank Inspected or ID #: \_\_\_\_\_

- This checklist is intended as a model. Locally developed checklists are acceptable as long as they are substantially equivalent (as applicable). Inspections of multiple tanks may be captured on one form as long as the tanks are substantially the same.
- For equipment not included in this Standard, follow the manufacturer recommended inspection/testing schedules and procedures.
- Upon discovery of water in the primary tank, secondary containment area, interstice, or spill container, remove promptly or take other corrective action. Inspect the liquid for regulated products or other contaminants and dispose of properly.
- Retain the completed checklists for at least 36 months.
- After severe weather (snow, ice, wind storms) or maintenance (such as coating) that could affect the operation of critical components (normal and emergency vents, valves), an inspection of these components is required as soon as the equipment is safely accessible after the event.

pumps, etc.) free of visible leaks? Note: If "No", identify location and describe leak.	<input type="checkbox"/> No <input type="checkbox"/> NA	
Do the ladders/platforms/walkways appear to be secure with no sign of severe corrosion or damage?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA	
Containment		
Is the containment free of excess liquid, debris, cracks, corrosion, erosion, fire hazards and other integrity issues?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA	
Are containment egress pathways clear and any gates/doors operable?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Na	
Other Conditions		
Is the system free of any other conditions that need to be addressed for continued safe operation?	<input type="checkbox"/> Yes <input type="checkbox"/> No	

[illegible]

## APPENDIX C – REPORTABLE SPILL QUANTITIES

Substance	Reportable Quantity
Explosives Compressed gas (toxic/corrosive) Infectious substances Sewage and wastewater (unless otherwise authorized) Radioactive materials Unknown substances	Any amount
Compressed gas (flammable) Compressed gas (non-corrosive, non-flammable)	Any amount of gas from containers with a capacity greater than 100 L
Flammable liquid	≥100 L
Flammable solid Substances liable to spontaneous combustion Water-reactant substances	≥25 kg
Oxidizing substances	≥50 L or 50 kg
Organic peroxides Environmentally hazardous substances intended for disposal	≥1 L or 1 kg
Toxic substances	≥5 L or 5 kg
Corrosive substances Miscellaneous products, substances, or organisms	≥5 L or 5 kg
Polychlorinated biphenyl mixtures of 5 ppm or more	≥0.5 L or 0.5 kg
Other contaminants, such as crude oil, drilling fluid, produced water, waste or spent chemicals, used or waste oil, vehicle fluids, wastewater	≥100 L or 100 kg
Sour natural gas (i.e., contains hydrogen sulphide) Sweet natural gas	Uncontrolled release or sustained flow of 10 minutes or more
Flammable liquid Vehicle fluid	≥20 L When released on a frozen waterbody that is being used as a working surface
Reported releases or potential releases of any size that:	Any amount

Substance	Reportable Quantity
<ul style="list-style-type: none"><li>• are near or in an open waterbody;</li><li>• are near or in a designated sensitive environment or habitat;</li><li>• pose an imminent threat to human health or safety; or</li><li>• pose an imminent threat to a listed species at risk or its critical habitat.</li></ul>	

Table information from :[Report a spill | Environment and Natural Resources \(gov.nt.ca\)](#)

## APPENDIX D – NT-NU SPILL REPORT FORM

# NT-NU SPILL REPORT

OIL, GASOLINE, CHEMICALS AND  
OTHER HAZARDOUS MATERIALS



Canada



## NT-NU 24-HOUR SPILL REPORT LINE

Tel: (867) 920-8130 • Email: spills@gov.nt.ca

### REPORT LINE USE ONLY

A	Report Date: MM   DD   YY	Report Time:	<input type="checkbox"/> Original Spill Report <b>OR</b> <input type="checkbox"/> Update # _____ to the Original Spill Report		Report Number:
	Occurrence Date: MM   DD   YY	Occurrence Time:			
C	Land Use Permit Number (if applicable):		Water Licence Number (if applicable):		
D	Geographic Place Name or Distance and Direction from the Named Location:			Region: <input type="checkbox"/> NT <input type="checkbox"/> Nunavut <input type="checkbox"/> Adjacent Jurisdiction or Ocean	
E	Latitude: _____ Degrees _____ Minutes _____ Seconds		Longitude: _____ Degrees _____ Minutes _____ Seconds		
F	Responsible Party or Vessel Name:		Responsible Party Address or Office Location:		
G	Any Contractor Involved:		Contractor Address or Office Location:		
H	Product Spilled: <input type="checkbox"/> Potential Spill	Quantity in Litres, Kilograms or Cubic Metres:		U.N. Number:	
I	Spill Source:	Spill Cause:		Area of Contamination in Square Metres:	
J	Factors Affecting Spill or Recovery:	Describe Any Assistance Required:		Hazards to Persons, Property or Environment:	
K	Additional Information, Comments, Actions Proposed or Taken to Contain, Recover or Dispose of Spilled Product and Contaminated Materials:				
L	Reported to Spill Line by:	Position:	Employer:	Location Calling From:	Telephone:
M	Any Alternate Contact:	Position:	Employer:	Alternate Contact Location:	Alternate Telephone:

### REPORT LINE USE ONLY

N	Received at Spill Line by:	Position:	Employer:	Location Called:	Report Line Number:
Lead Agency: <input type="checkbox"/> EC <input type="checkbox"/> CCG/TCMSS <input type="checkbox"/> GNWT <input type="checkbox"/> GN <input type="checkbox"/> ILA <input type="checkbox"/> AANDC <input type="checkbox"/> NEB <input type="checkbox"/> Other: _____			Significance: <input type="checkbox"/> Minor <input type="checkbox"/> Major <input type="checkbox"/> Unknown		File Status: <input type="checkbox"/> Open <input type="checkbox"/> Closed
Agency:		Contact Name:	Contact Time:	Remarks:	
Lead Agency:					
First Support Agency:					
Second Support Agency:					
Third Support Agency:					